

UP-2019-0367-5I

DEPARTMENT OF PERMITS, APPROVALS & INSPECTIONS A 111 WEST CHESAPEAKE AVENUE

TOWSON, MD 21204 410-887-3391

SIGN USE PERMIT

A
The applicant is authorized
to affirm that there are no
current violations at this
site pursuant to Section
112.7 BCC

Permit Fees are Non-Refundable; Make Check Payable to "Baltimore County, Maryland" 112.7 BCC Initials
PROPERTY ADDRESS 1011 Rolling Rd Catonsville MD ZIP CODE 21228
BUSINESS NAME McDanaldes ZONING BM
OWNER'S NAME McDonald's Corp. PHONE NO. 443-917-2694 HISTORIC DISTRICT Yes No
MAILING ADDRESS PO BOX 6299 Columbia (MI) 21045
APPLICANT/OWNER'S AGENT Ken Padgett- PHONE NO. 301-370-2126
SIGN COMPANY NAME Northcroft Signs PHONE NO. 301-477-3600
TYPE OF SIGN: Window Sign TAX ACCOUNT NO. 190 / 060 / 1499
☐ Temporary- Including Real Estate/Construction/Event Temporary Signs in the Last Year: ☐ Yes ☑ No
Permanent Changeable Copy Wall Face Change Only Non-Illuminated
Freestanding Pylon Monument Illuminated (separate electrical permit required)
Size: feet x feet = square feet Height: 5.94 feet (freestanding signs)
Property Line/Street Right-of-Way Setbacks: front, sides and, and rear
NOTE: A construction plan, drawn to scale and clearly showing that all requirements have been met, must be attached; a site plan also
must be attached for freestanding signs.
Table of Sign Regulations: 450.4. Attachment 1, 1 An Electronic Changeable Copy Sign may only have a maximum Frequency of one
instantaneous message change per 15 second cycle. 450.6.B.3 Changeable copy signs must operate at a constant intensity and not give the appearance of movement by
flashing, blinking, strobing, scrolling, oscillating, or alternating lights.
PROHIBITIONS: including roof signs (Sections 450.5.B.7 and 450.6.A, <u>Baltimore County Zoning Regulations</u>):
1. Signs cannot impair motorist's clear view of traffic or government signs. All signs are subject to Section 102.5, BCZR.
2. Signs cannot imitate or resemble government signs, except for private traffic control and notice signs.
3. Signs cannot be placed in or project into or above street right of way or governmental property.
4. Sign or framework cannot obstruct window or opening for light and air or access to building, fire hydrant, or stand pipe.
5 Vehicle cannot be parked for the purpose of displaying an attached sign.
6. Except for flags exempted, flags, pennants, ribbons, streamers, tethered balloons, laser projections, and similar objects are
prohibited. 7. Portable signs are prohibited, except for A-frame and sandwich board signs issued a use permit in B.M. – C.T. zones.
8. There can be no display or simulation of moving parts or message, except for an outdoor advertising sign with tri-vision, a
changeable copy sign, or a thermometer, barometer, weather vane, barber pole, or clock.
9. No sign may emit sound
Work Description (including number of signs, special conditions, materials, locations and size):
Install 2 new menuboards in Drive-Thru land for McDonald's
(1) 2.42' × 4.15' = 10.04 \$ 5.96' OAH (2) 4.83' × 4.14' = 19.99 \$ 5.96' OAH (3) CORNER LOT
(1) 4.83, 7 4.14, = 10.88 \$ 2.80, OAH
OWNER/AGENT CERTIFICATION Which is a second by the second the shown are true and further than the contents of the above are true and further than the contents of the above are true and further than the contents of the above are true and further than the contents of the above are true and further than the contents of the above are true and further than the contents of the above are true and further than the contents of the above are true and further than the contents of the above are true and further than the contents of the above are true and further than the contents of the above are true and further than the contents of the above are true and further than the contents of the above are true and further than the contents of the above are true and further than the contents of the above are true and further than the contents of the above are true and the contents of t
I solemnly affirm under the penalties of perjury and upon personal knowledge that the contents of the above are true and further agree to locate the proposed sign such that it will not violate Baltimore County laws and regulations.
Of the state Ken Fodgett
Signature Date Print/Type Name
Signature A Signature S
Copies: White-Office; Yellow- Applicant (keep Author Yunder Section 500.4, BCZR PAI Approval (SIGN ONLY)
this Copy for your permanent records) REV 10/14 Signature Initials Date

Signature



Permits, Approvals & Inspections

111W. Chesapeake Avenue Towson, MD 21204

Report Generated On: 3/22/2019

Permit Processing Commerical Permit & Development Report

Page 1 of 1

Property Information

Tax Account Number: 1900001499

Plat Ref: 047:082

Election District: 1

Owner Name(s): MCDONALDS CORPORATION and C/O CATHY BELL

PDM #: 01-0213

Address: PO BOX 6299

Zoning District(s): BM AS

COLUMBIA, MD 21045 Premise Address: 1011 ROLLING RD

Elevation Range: 526ft - 534ft

Affected Overlays Instructions: Begin review process with Zoning Review, Room 111 Potential Overlay Issues Growth Tier 1: Served by public sewer and inside URDL Planning Jefferson Building Room 101 Phone: 410-887-3211 DEPS-Sed. Control Jefferson Building 4th Floor Phone: 410-887-3226 PAI-Public Services County Office Building Room 119 Phone: 410-887-3391 Zoning Review County Office Building Room 119 Phone: 410-887-3391	Premise Address: 1011 ROL	LING ND	1							9	5. 02				
Contact Agency Potential Overlay Issues Growth Tier 1: Served by public sewer and inside URDL Planning Jefferson Building Room 101 Phone: 410-887-3211 DEPS-Sed. Control Jefferson Building 4th Floor Phone: 410-887-3226 PAI-Public Services County Office Building Room 119 Phone: 410-887-3751 Zoning Review County Office Building Room 111 Zoning Cases: 1972-0298-X; 1961-5221-X; R-1955-3514 Zoning Cases: 1972-0298-X; 1961-5221-X; R-1955-3514	Affected Overlays	Instructions: Begin review process with Zoning Review, Room 111	ם Bldg.	n Bldg. Its. Alts. ngs		sbu	SW		%Bulk		Occup.	ntenna	A STATE OF THE STA	Jumb	
Jefferson Building Room 101 Phone: 410-887-3211 DEPS-Sed. Control Jefferson Building 4th Floor Phone: 410-887-3226 PAI-Public Services County Office Building Room 119 Phone: 410-887-3751 Zoning Review County Office Building Room 111 Solution in the sent to Sediment Control for review. Note: All Razing Permits must be sent to Sediment Control for review. Note: All Permits for Grading, New Buildings & Building Additions must be sent to Public Services. Zoning Review County Office Building Room 111 Zoning Cases: 1972-0298-X; 1961-5221-X; R-1955-3514 X X X X X X X X X X X X X X X X X X X	407		New Con	Interior A	Add / Ext	Piers/Pili	Grading/8	Tanks	Ret.Walls	Razing	Chg. of C	Tower Ar	Signs	∞ಶ	_
Jefferson Building 4th Floor Phone: 410-887-3226 PAI-Public Services County Office Building Room 119 Phone: 410-887-3751 Zoning Review County Office Building Room 111 Zoning Review County Office Building Room 111	Jefferson Building Room 101	Commercial Revitalization Districts - Baltimore National Pike	X		X	ALLONGO	Control of the Contro						X	анасаты	arributessus prostauren sutespekten aus det van aus aus de se
County Office Building Room 119 Phone: 410-887-3751 Zoning Review County Office Building Room 111 Zoning Review Room 111	Jefferson Building 4th Floor	Note: All Razing Permits must be sent to Sediment Control for review.					The same and the s	,					2 100000000		амера прити достава наста поттексо под в сотоста на под тесто
County Office Building Room 111	County Office Building Room 119							2					2	- Andrews - Andr	
	County Office Building Room 111	Zoning Cases: 1972-0298-X; 1961-5221-X; R-1955-3514	X			X					*		X CONTRACTOR		anadustraainty vasteria kuntuurin kaisen

Notice: This report is not inclusive as additional issues may arise which would affect the ability to obtain a building permit. This Report is solely for Departmental use and nothing herein creates any right which would accrue to the applicant. Form171C



SINGLE 55"

Modular Range

Hot-dipped galvanized frame

Aluminum panels

Modular Mounting Structure


Allows for various screen sizes with panel/mount replacement

Option for crane in or manual 2 person assembly

Currently designed for the Samsung OHF panel but mounting hardware can be modified for alternate screen specifications in future

(2.42!)2'-5 1/8" Now more choices **All Day** Breakfast · McMuffin' sandwiches - Biscuits - McCridd oc (4.15') Choose a side. 4'-1 3/4" • Fries • Hash Browns' (5.961) 5'-11 1/2"

2.42' x 4.15' = 10.04 SF





For enquiries and further information on our range of products please visit www.coatesgroup.com

OAH



DOUBLE 55"

Modular Range

Hot-dipped galvanized frame

Aluminum panels

(4.14')

Modular Mounting Structure

4'-1 5/8"

Allows for various screen sizes with panel/mount replacement

Option for crane in or manual 2 person assembly

Currently designed for the Samsung OHF panel but mounting hardware can be modified for alternate screen specifications in future

Thank you for your order. Please **Proceed** to the next window.


(4.831)


4'-10"


Crushes hunger. Quenches thirst Made For You' Meals 🏬

> 5'-11 5/8" (5.96!)OAH

4.83' x 4.14' = 19.99 SF







LEGEND

NOT ALL SYMBOLS APPEAR ON SHEET EXISTING CURB AND GUTTER TO REMAIN

= == == EXISTING CURB AND GUTTER TO BE REMOVED

NEW CURB AND GUTTER. SEE SCHEDULE NOTE 5.

NEW STRIPING (4" WHITE)

EXISTING CONCRETE PAVEMENT

NEW 6" CONCRETE SLAB

FXTENT OF SIDEWALK ADA WORK

PROPOSED ASPHALT

EXISTING PROPOERTY LINE (APPROX. - NOT SURVEYED)

EXISTING SANITARY SEWER

EXISTING STRIPING TO BE REMOVED

EXISTING BOLLARD

EXISTING SANITARY SEWER MANHOLE

EXISTING TREES TO REMAIN (TYP)

GENERAL NOTES

- A. DIMENSIONS AND RADII SHOWN ARE TO FLOWLINE UNLESS OTHERWISE STATED.
- B. ALL CURBS ARE 6" AND SHALL BE POURED MONOLITHICALLY WITH CONCRETE PAVEMENT
- DISCREPANCIES WITH MCDONALDS PROJECT MANAGER PRIOR TO COMMENCING WORK.

 D. COORDINATE ALL DRIVE-THRU STRIPING AND MARKINGS WITH THE
- MCDONALDS PROJECT MANAGER.
- E. CONCRETE SHALL BE 6" MIN. THICKNESS AND 4000 PSI STRENGTH AT 28 DAYS. PROVIDE #4 REINFORCEMENT AT 12" O.C. AND SAWCUT JOINTS IN CONCRETE PAVEMENT IN ACCORDANCE WITH ACI STANDARDS.
- COORDINATE GROUND COVER OF NEW ISLANDS WITH MCDONALDS PROJECT MANAGER.
- C. ALL SITE WORK INCLUDING BUT NOT LIMITED TO ASPHALT OVERLAY, SUBGRADE PREPARATION AND CAST IN PLACE CONCRETE SHALL BE IN
- ACCORDANCE WITH MCDONALDS CONSTRUCTION SPECIFICATIONS.

 H. MAINTAIN EXISTING DRAINAGE PATTERNS WITH NEW CONSTRUCTION.

SCHEDULE

NOTE: NOT ALL NOTES ARE USED ON PLAN

- EXISTING MCDONALDS BUILDING.
- 2. NEW WALL MODIFICATIONS TO EXISTING BUILDING; SEE ARCHITECTURAL PLANS.
- 3. RESTRIPE PARKING SPACES WITH 4" WHITE PARKING STALL STRIPING.
- 4. PAINT/STENCIL IN BLUE. PLACE HANDICAP SIGNS PER DETAILS (B) US (SD2) (SD1)
- 5. 6" VERTICAL CURB OR CURB AND GUTTER REINFORCED W/ FIBERMESH. (8)
- 6. 6" CONCRETE SLAB REINFORCED W/ FIBERMESH IN NEW DRIVE THRU LANES. MATCH EXISTING CONCRETE (TO REMAIN) ALONG JOINT LINES WHERE POSSIBLE. (7)
- 7. NEW CURB RAMP. ENSURE LEVEL LANDINGS TOP AND BOTTOM. RAMP TO
 HAVE 1:12 MAXIMUM RUNNING SLOPE WITH 1:48 MAXIMUM CROSS SLOPE.
- 8. STRIPING AND PAVEMENT MARKINGS TO BE INSTALLED AS SHOWN ON THE PLAN; USE YELLOW PAINT. (a) $\frac{1}{501}$, $\frac{1}{501}$
- 9. 8" WIDE YELLOW STRIPE PAINTED. THIS STRIPING ALSO REPRESENTS THE LIMIT OF THE NEW CONCRETE INSTALLATION.
- 10. 6" WIDE YELLOW STRIPE PAINTED. FOR MERGE POINT STRIPING
- 11. NEW 'GATEWAY' SIGN. FOOTING TO BE 18" TO 24" FROM FACE OF CURB. 6 4 502 502
- 12. NEW "ANY LANE / ANY TIME" SIGN.
- 13. NEW PRE-BROWSE BOARD. (2)
- 14. NEW COD CUSTOMER ORDER DISPLAY
- 15. NEW LOOP DETECTORS. (OPTIONAL)
- 1<mark>6. NEW OUTDOOR DIGITAL MENUBOARD. ANGLE SHOULD BE 25"-35" FOR MAXIMUM VISIBILITY.</mark>
- 17. NOT USED.

ADJACENT LOT)

ADA PARKING PROVIDED

4 SPACES

- 18. NOT USED.
- 19. EXISTING CONCRETE PAD TO REMAIN IN EXISTING DRIVE-THRU LANE.

FY THAT THES AM A DULY L F THE STATE 1/15/19 -65 THAT LAWS DATE: EREB AND IRE ON ER, ER E G E



architects - e
One Penn Pl
New York, N
973.883,859

∢ McDonald's

EOTF NG BU PLAN SITE

SP.1 SITE PLAN



BALTIMORE COUNTY DEPARTMENT OF PERMITS, APPROVALS & INSPECTIONS 111 WEST CHESAPEAKE AVENUE TOWSON, MD 21204

410-887-3391

SIGN USE PERMIT

USE	PER	MIT	RE	CEIPT	
# 1	8	70	7	J	

The applicant must affirm by initials below that there are no current violations at this site, pursuant to Section 112.7, B.C.C. Initials:

Permit Fees are Non-Refundable; Make Check Payable to "Baltimore	County, Maryland"
PROPERTY ADDRESS ON NOWAY KO	ZIP CODE
BUSINESS NAME MC David's Co.Z.	ZONING De/C
OWNER'S NAME CATHY BELL PHONE NO.	30-623-300 HISTORIC DISTRICT Yes 🖾 N
MAILING ADDRESS 110 N Carpenter St	Chicago IL 60607
APPLICANT/OWNER'S AGENT Nogh Fisschagun	PHONE NO. 301-497-8585
SIGN COMPANY NAME CLEAR COMMUNICATIONS	The PHONE NO. 301-451-8589
TYPE OF SIGN:	X ACCOUNT NO. 190 100061557
☐ Temporary- Including Real Estate/Construction/Event	Temporary Signs in the Last Year: Yes No
☐ Permanent ☐ Changeable Copy ☐ Wall ☐ Face Cha	ange Only Non-Illuminated
Freestanding Pylon Monument Illuminated (sepa	rate electrical permit required)
Size: feet x feet = square feet	Height: feet (freestanding signs)
Property Line/Street Right-of-Way Setbacks: front, sides	and, and rear
NOTE: A construction plan, drawn to scale and clearly showing that all	l requirements have been met, must be attached.
A site plan must also be attached for freestanding signs.	
Table of Sign Regulations: 450.4.1 An Electronic Changeable Copy Sign	n may only have a maximum frequency of one instantaneous
message change per 15 second cycle. 450.6.B.3 - Changeable copy signs mappearance of movement by flashing, blinking, strobing, scrolling, oscillations.	
 PROHIBITIONS: including roof signs (Sections 450.5.B.7 and 450.6.A, Signs cannot impair motorist's clear view of traffic or government Signs cannot imitate or resemble government signs, except for privalising cannot be placed in or project into or above street right of wards. Signs cannot be placed in or project into or above street right of wards. Vehicle cannot be parked for the purpose of displaying an attached. Except for flags exempted, flags, pennants, ribbons, streamers, teth prohibited. Portable signs are prohibited, except for A-frame and sandwich bows. There can be no display or simulation of moving parts or message changeable copy sign, or a thermometer, barometer, weather vane. 	signs. All signs are subject to Section 102.5, BCZR. wate traffic control and notice signs. ay or governmental property. d air or access to building, fire hydrant, or stand pipe. It sign. hered balloons, laser projections, and similar objects are ard signs issued a use permit in B.M. – C.T. zones. except for an outdoor advertising sign with tri-vision, a
9. No sign may emit sound	
Work Description (including number of signs, special conditions, man First Sign 17-6 State Stand Sign 8. 8 Stand Sig	cerials, locations and size): CORNER LOT?
OWNER/AGENT CERT I solemnly affirm under the penalties of perjury and upon personal knoagree to locate the proposed sign such that it will not violate Baltimore	owledge that the contents of the above are true and furthe
Signature Date	Print/Type Name
Require Planning Signature	Date
this Copy for your permanent records)	der Section 500.4, BCZR PAI Approval (SIGN ONLY)
REV 04/17/2019	Intelals Date



Permits, Approvals & Inspections

111W. Chesapeake Avenue Towson, MD 21204

Report Generated On: 7/9/2019

Permit Processing Commerical Permit & Development Report

Page 1 of 1

Property Information

Tax Account Number: 1900006557

Election District: 2

Owner Name(s): MCDONALDS CORP and % SRD MANGEMENT INC

PDM #: 02-0772

Address: SCOTT RARDIN 8017 DORSEY RUN RD #A1

Zoning District(s): DR 16

JESSUP,MD 20794

DR 5.5

Premise Address: ROLLING RD

Floration Pance: 510ft 519ft

Affected						iev	atio	n K	ang	e: 5	Ή	- 5	18ft	
Affected Overlays	Instructions: Begin review process with Zoning Review, Room 111	Bldg.	,	Alts.	Js.	>		3ulk		cnb.	inna		Plumb	Agency
04-14	Potential Overlay Issues	New Com	Interior Alts.	Add / Ext. Alts.	Piers/Pilings	Grading/SW		Ret.Walls/Bulk	D	of Occup.	Tower Antenna		ల	Acknowledgmen
Contact Agency	Growth Tier 1: Served by public sewer and inside URDL	Vew	nteri	/pp\	Jiers,	Gradi	Tanks	Ret.M	Razing	Chg.	owel	Signs	Elect.	Initial & Date
Planning Jefferson Building Room 101 Phone: 410-887-3211	Commercial Revitalization Districts - Liberty Rd	X		X				ш.	The state of the s		L	X	_	7/9/19
DEPS-Sed. Control Jefferson Building 4th Floor Phone: 410-887-3226	Note: All Razing Permits must be sent to Sediment Control for review.													
PAI-Public Services County Office Building Room 119 Phone: 410-887-3751	Note: All permits for Grading, New Buildings & Building Additions must be sent to Public Services.			To the second										
Zoning Review County Office Building Room 111 Phone: 410-887-3391	Zoning Cases: R-1951-2075; 1973-0028-SPH; 2013-0006-SPHA; 2013-0113-SPHA	X		X	X	X	X			X	X	X		
otice: This report is not inclusive as additional in	sues may arise which would affect the ability to obtain a building permit. This Report is solely for Doppe											and the state of t		

ould affect the ability to obtain a building permit. This Report is solely for Departmental use and nothing herein creates any right which would accrue to the applicant. Form171C



BALTIMORE COUNTY DEPARTMENT OF PERMITS, APPROVALS & INSPECTIONS 111 WEST CHESAPEAKE AVENUE TOWSON, MD 21204

410-887-3391

SIGN USE PERMIT

Permit Fees are Non-Refundable; Make Check Payable to "Baltimore County, Maryland"

USE	PER	MIT	REC	CEIPT	
# 1	C	70	7	1	
π	- 4	_/ -	,	/	_

The applicant must affirm by initials below that there are no current violations at this site, pursuant to Section 112.7, B.C.C. Initials:

PROPERTY ADDRESS OI N KOLLING KO	ZIP CODE
BUSINESS NAME MC Danald's Co.Z.	ZONING De / C
OWNER'S NAME CATHY BELL PHO	ONE NO. 630 - 632 - 300 HISTORIC DISTRICT \square Yes \square No
MAILING ADDRESS 110 N Carpenter	St Chicago IL 60607
APPLICANT/OWNER'S AGENT Noal Fissel	PHONE NO. 301-495-8585
SIGN COMPANY NAME CLEAR COMMUNICATI	025 Inc PHONE NO. 301-457-8589
TYPE OF SIGN: Window Sign	TAX ACCOUNT NO. 190 100061557
☐ Temporary- Including Real Estate/Construction/Event	Temporary Signs in the Last Year: Yes No
Permanent Changeable Copy Wall	Face Change Only Non-Illuminated
Freestanding Pylon Monument Illumin	ated (separate electrical permit required)
Size:feet xfeet =square feet	Height: feet (freestanding signs)
Property Line/Street Right-of-Way Setbacks: front, sid	es, and rear
NOTE: A construction plan, drawn to scale and clearly show	ing that all requirements have been met, must be attached.
A site plan must also be attached for freestanding sig	ns.
message change per 15 second cycle. 450.6.B.3 - Changeable co	
appearance of movement by flashing, blinking, strobing, scrolling	g, oscillating, or alternating lights.
 Signs cannot imitate or resemble government signs, exc. Signs cannot be placed in or project into or above street Sign or framework cannot obstruct window or opening f Vehicle cannot be parked for the purpose of displaying a Except for flags exempted, flags, pennants, ribbons, stre prohibited. Portable signs are prohibited, except for A-frame and sa 	ept for private traffic control and notice signs. right of way or governmental property. or light and air or access to building, fire hydrant, or stand pipe. an attached sign. amers, tethered balloons, laser projections, and similar objects are ndwich board signs issued a use permit in B.M. – C.T. zones. r message, except for an outdoor advertising sign with tri-vision, a
Work Description (including number of signs, special condi	
I solemnly affirm under the penalties of perjury and upon per	CORNER LOT? NT CERTIFICATION rsonal knowledge that the contents of the above are true and further
agree to locate the proposed sign such that it will not violate E	saltimore County laws and regulations.
07/09/15	NOAN FISSELAL
Signature Date	Print/Type Name
Require Planning Signature	7/9/1 Date
1 1 1	Authority under Section 500.4, BCZR PAI Approval (SIGN ONLY)
this Copy for your permanent records)	Jahren 3h 7/9/18
REV 04/17/2019	Signature Initials Date

- CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS AND EXISTING CONDITIONS PRIOR TO BID TO DETERMINE THE EXTENT OF WORK. THE CONTRACTOR SHALL NOTIFY THE ARCHITECT OF ANY DISCREPANCIES PRIOR
- ALL FXISTING MATERIALS TO REMAIN WHICH ARE DAMAGED OR OTHERWISE DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE PATCHED OR REPAIRED TO MATCH THE EXISTING ADJACENT MATERIALS, SO THAT THE REPAIR IS IMPERCEPTIBLE.
- DURING THE COURSE OF CONSTRUCTION, IF THE CONTRACTOR UNCOVERS ANY CODE VIOLATION KNOWN TO HIM OR ANY DISCREPANCY WITH THE DESIGN, CONTRACTOR SHALL NOTIFY THE ARCHITECT OF SUCH IMMEDIATELY.
- CONTRACTOR SHALL ASSEMBLE AND INSTALL MATERIALS/ PRODUCTS IN STRICT ACCORDANCE WITH THE MANUF'S RECOMMENDATIONS AND INDUSTRIAL/ASSOCIATION STANDARDS.
- CONTACT ARCHITECT AND COORDINATE WITH TENANT ANY ADDITIONAL SPECIFICATIONS NOT SPECIFIED HEREIN AND/OR CLARIFICATIONS REGARDING THE CONTRACT DOCUMENTS
- NO CURRENT SURVEY WAS PERFORMED. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY, IN WRITING, OF ANY DISCREPANCIES OR OMISSIONS TO THE TOPOGRAPHIC INFORMATION. THE CONTRACTOR(S) SHALL BE RESPONSIBLE FOR CONFIRMING THE LOCATION (HORIZONTAL (VERTICAL) OF ANY BURIED CABLES CONDUITS PIPES AND STRUCTURES (STORM SEWER, SANITARY SEWER, WATER, GAS, TELEVISION, TELEPHONE, ETC.) WHICH IMPACT THE CONSTRUCTION SITE. THE CONTRACTOR(S) SHALL NOTIFY THE OWNER AND ENGINEER IN WRITING IF ANY DISCREPANCIES ARE FOUND BETWEEN THE ACTUAL CONDITIONS VERSUS THE DATA CONTAINED IN THE CONSTRUCTION PLANS. ANY COSTS INCURRED AS THE RESULT OF NOT CONFIRMING THE ACTUAL LOCATION (HORIZONTAL/VERTICAL) OF SAID CABLES, CONDUITS, PIPES, AND STRUCTURES SHALL BE BORNE BY THE CONTRACTOR. ADDITIONALLY, THE CONTRACTOR(S) SHALL NOTIFY THE OWNER AND ENGINEER IN WRITING IF ANY ERRORS OR DISCREPANCIES ARE FOUND ON THE CONSTRUCTION DOCUMENTS (PS&E), WHICH NEGATIVELY IMPACT THE PROJECT. THE ENGINEER AND OWNER SHALL BE INDEMNIFIED OF PROBLEMS AND/OR COST WHICH MAY RESULT FROM THE CONTRACTOR'S FAILURE TO NOTIFY THE ENGINEER AND OWNER.
- IT IS STRONGLY RECOMMENDED THAT NO CONTRACTUAL AGREEMENT OF ANY KIND BE SIGNED PRIOR TO RECEIVING AND THOROUGHLY REVIEWING ALL APPROVALS FROM ALL OF THE REGULATORY AUTHORITIES HAVING JURISDICTION OVER THIS PROJECT.

BUILDING CODE SUMMARY

APPLICABLE BUILDING CODE: 2015 INTERNATIONAL BUILDING CODE

BALTIMORE, MD 21228


APPLICABLE ELECTRICAL CODE: 2017 NATIONAL ELECTRICAL CODE

USE GROUP: A2 - ASSEMBLY

BUILDING DEPARTMENT PHONE NO: 410-887-3953

EXISTING SIGNAGE AREA TO BE REMOVED: 53.0 SQ FT

NEW SIGNAGE AREA TO BE ADDED: 26.4 SQ FT PROJECT ADDRESS: 1011 N ROLLING RD





MENU BOARD 42 SQ FT EXISTING MENU BOARD TO BE REPLACED







17.6 SQ FT

NEW MENU BOARDS AND PRE-BROWSE BOARDS

SITE NOTES

- ALL DIMENSIONS SHOWN ARE TO FACE OF CURB UNLESS NOTED OTHERWISE. 2. BASES, ANCHOR BOLTS, CONDUIT, AND WIRING FOR ALL SIGNS ARE BY THE GENERAL CONTRACTOR.
- EXISTING MENU BOARDS AND PRE-SELL BOARD TO BE REMOVED FROM BASES AND DISPOSED OF OFF-SITE, EXISTING BASES FOR MENU BOARDS AND PRE-SELL BOARD TO BE PROTECTED FROM DAMAGE. CONDUITS TO BE CAPPED TO PREVENT MOISTURE ENTRANCE.

UTILITY NOTES

- ALL ELECTRICAL/CONDUIT RUNS ARE SCHEMATIC ONLY. CONDUIT SIZES AND ROUTING PROVIDED BY BAILIWICK.
 IT SHALL BE THE SIGN INSTALLER'S RESPONSIBILITY TO ENSURE THE
- PROPOSED SIGN LOCATION DOES NOT INTERFERE WITH ANY UTILITIES AND COMPLIES WITH ALL APPLICABLE CITY CODES. SIGN INSTALLER SHALL ALSO OBTAIN APPROVAL FROM THE APPROPRIATE ENTITIES PRIOR TO INSTALLING THE SIGN OVER ANY EXISTING EASEMENTS.
- REFER TO THE BUILDING ELECTRICAL DRAWINGS FOR UTILITY SERVICE ENTRANCE LOCATIONS, SIZES, AND CIRCUITING.

DEMOLITION NOTES

- CONTRACTOR IS RESPONSIBLE FOR THE REPAIR OF ANY DAMAGE TO EXISTING IMPROVEMENTS DURING CONSTRUCTION, SUCH AS, BUT NOT LIMITED TO: DRAINAGE, UTILITIES, PAVEMENT, STRIPING, CURB, ETC.
- REPAIRS SHALL BE EQUAL TO OR BETTER THAN EXISTING CONDITIONS.
 ALL WORK ON THIS PLAN SHALL BE DONE IN STRICT ACCORDANCE WITH SITE
- CONTRACTOR SHALL COMPLY TO THE FULLEST EXTENT WITH THE LATEST STANDARDS OF OSHA DIRECTIVES OR ANY OTHER AGENCY HAVING JURISDICTION FOR EXCAVATION AND TRENCHING PROCEDURE. CONTRACTOR SHALL USE SUPPORT SYSTEMS, SLOPING, BENCHING, OR OTHER MEANS OF PROTECTION, INCLUDING BUT IS NOT LIMITED TO, ACCESS AND EGRESS FROM ALL EXCAVATION AND TRENCHING. CONTRACTOR IS RESPONSIBLE TO COMPLY WITH PERFORMANCE CRITERIA FOR OSHA.
- CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING THE PUBLIC DURING CONSTRUCTION. INCLUDING BUT NOT LIMITED TO: CONSTRUCTION FENCING, BARRICADES, SIGNAGE, ETC.
- CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL UTILITIES AND NOTIFYING THE APPROPRIATE UTILITY COMPANY PRIOR TO BEGINNING CONSTRUCTION.
- CONTRACTOR SHALL VERIFY HORIZONTAL AND VERTICAL LOCATION OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION.

SCOPE OF WORK

REMOVE EXISTING MENU BOARDS AND CAP CONDUIT PER SITE NOTES. INSTALL NEW MENU BOARDS AND ALL REQUIRED CONDUIT AND WIRING. REFER TO MANUFACTURERS BOARD PUBLISHED INSTALLATION INSTRUCTIONS.

EXISTING BUILDING - AREA OF WORK

EXISTING OVERALL SITE PLAN

0 20' 30' 1"=10'-0"



1317 Executive Blvd, Suite 200 Chesapeake, VA 23320 (757)622-2828 / fax (757)622-6883




LLC NSN 2388 © S2017 McDonald's USA,


1011 N ROLLING F BALTIMORE, MD 2 Ë

18790-33 PROJEC^{*} CHECKED


> SITE PLAN AND NOTES

> > C1.0





ENLARGED SITE PLAN





- ONE 3/4" PVC CONDUIT (4-#12, 1-#12 GRD, 1-#12 IG) BOARDS FOR RECONNECTION TO NEW DIGITAL MENU BOARDS.

 EXISTING FEEDS: IF PRACTICAL AND POSSIBLE CONTRACTOR TO UTILIZE EXISTING PULLBOXES, UNDERGROUND CONDUIT AND WIRING FEEDING EXISTING TO BE DEMOLISHED MENU BOARDS FOR NEW MENU BOARDS OR PROVIDE
 - FROM PANEL CP TO J-BOX
 - ONE 3/4" PVC CONDUIT (2#12, 1#12 GRD, 1#12 IG) FROM J-BOX TO LANE 1 PRE-SELL BOARD
 - 3 ONE 3/4" PVC CONDUIT (2-#12, 1-#12 GRD, 1-#12 IG) FROM J-BOX TO LANE 1 MENU BOARD

ELECTRICAL PLAN NOTES

NEW AS SHOWN

INTENT OF DESIGN: DISCONNECT POWER AND DATA FEEDS FROM EXISTING PRIMARY AND SECONDARY MENU

REUSE OF EXISTING BRANCH CIRCUITS: CONTRACTOR TO UTILIZE EXISTING BRANCH CIRCUITS (COMMONLY TWO BRANCH CIRCUITS)

NOTED CIRCUIT NUMBERS DERIVED FROM EXISTING PANEL DIRECTORY INSERTS, CONTRACTOR TO FIELD VERIFY

AND UTILIZE EXISTING BRANCH CIRCUITS FEEDING THE PRIMARY (BRANCH CIRCUIT 1) AND SECONDARY (BRANCH CIRCUIT 2) MENU BOARDS AND PRE-BROWSE BOARDS.

COORDINATE ALL CONDUIT AND CIRCUITING SIZE REQUIREMENTS WITH MANUFACTURERS INSTALL REQUIREMENTS

ONE 2" PVC CONDUIT (CAT6 DATA CABLES)
 FROM BUILDING TO LANE 1 MENU BOARD

ENLARGED CONDUIT PLAN

1"=20'-0"

1"=10'-0"

- ONE 1" PVC CONDUIT (CAT6 DATA CABLES) FROM LANE 1 MENU BOARD TO LANE 1 PRE-SELL BOARD



1317 Executive Blvd, Suite 200 Chesapeake, VA 23320 (757)622-2828 / fax (757)622-6883



LLC NSN 2388 McDonald's USA,

1011 BAL


PROJECT CHECKED

ENLARGED UTILITY PLANS

W

C1.1






FOUNDATION ELEVATION (MENU BOARD)


2.00

CLARITY.

ANCHOR BOLT, NUT AND WASHER NOTES:

- 1. TOP OF PIERS SHALL BE SLOPED SUCH THAT MOISTURE CANNOT ACCUMULATE ON TOP OF FOUNDATION.
- 2. USE F1554 GRADE 36 BOLTS MINIMUM.
- 3. USE HOT-DIP GALVANIZED BOLTS IN ACCORDANCE WITH ASTM A-123.
- 4. ANCHOR BOLTS TO BE SET IN ACCORDANCE WITH AISC CODE OF STANDARD PRACTICE
- 5. ANCHOR BOLTS, NUTS AND WASHERS SHALL BE SHIPPED AS AN ASSEMBLY FROM THE SIGN/LIGHTING
- 6. DO NOT CUT ANCHOR BOLTS AFTER INSTALLATION OF FRAME.





- LEVELING NU

DOUBLE NUTS (GALV.) -

BEYOND HAND-TIGHT

(MIN 60°, MAX 80°) -

TIGHTEN TOP NUT 1/2 TURN

(TURN OF NUT METHOD)


NOTE: THE DISTANCE FROM THE TOP

OF THE FOUNDATION TO THE

BOTTOM OF THE BASE PLATE

SHALL BE NO GREATER THAN 2'

TYPICAL ANCHOR BOLT PATTERN



TYPICAL BASE PLATE DETAIL TYPICAL CONNECTION DETAIL NOT TO SCALE NOT TO SCALE

STEEL NOTES:

- REINFORCEMENT: GRADE 60
- 2. NUTS: A563DH OR A194-2H.
- 4. ANCHOR BOLTS: ASTM F1554, GRADE 36 HOT-DIP GALVANIZED IN ACCORDANCE WITH ASTM A-123
- 5. ALL HARDWARE SHALL BE HOT-DIP GALVANIZED UNLESS OTHERWISE NOTED
- ANCHOR RODS, NUTS, AND WASHERS SHALL BE SHIPPED AS AN ASSEMBLY FROM THE SIGN/LIGHTING MANUFACTURER. COORDINATE WITH MANUFACTURER.
- NO FIELD HEATING TO BEND STEEL SHALL BE ALLOWED
- 8. DO NOT CUT ANCHOR BOLTS AFTER INSTALLATION OF POLE.
- REFER TO SIGN MANUFACTURER DRAWINGS AND INSTRUCTIONS FOR ADDITIONAL INFORMATION.
- 10. CONTRACTOR (INSTALLER) IS RESPONSIBLE FOR THE MEANS AND METHODS OF CONSTRUCTION IN REGARDS TO JOBSITE
- 11. STRUCTURAL SIGN FRAME AND BASE PLATE DETAILS ARE PROVIDED BY SIGN MANUFACTURER. COORDINATE ALL ATTACHMENTS OF SIGN WITH MANUFACTURER

GENERAL NOTES:


- THE FOLLOWING CODES WERE USED IN DESIGN 2016 MARYLAND BUILDING PERFORMANCE STANDARDS, IBC 2015 AND ASCE-7 (2010).
- 2. STRUCTURAL LOADINGS:

WIND (3 SECOND GUST). $V_{ULT} = 115 MPH$ $V_{ASD} = 90 MPH$ EXPOSURE. RISK CATEGORY WIND BASE SHEAR .. Vb = 400 LBS (PRE-SELL BOARD) Vb = 700 LBS (MENU BOARD) SEISMIC IMPORTANCE FACTOR (Ie) MAPPED SPECTRAL RESPONSE ACCELERATIONS..Ss......0.130g DESIGN SPECTRAL RESPONSE ACCELERATIONS 0 1390 ..0.083g SITE CLASS SEISMIC DESIGN CATEGORY. SEISMIC RESPONSE COEFFICIENT (Cs) COMPONENT RESPONSE MODIFICATION FACTOR (Rp)..3.5 SEISMIC DESIGN FORCE (Fp).. ..0.01 KIPS (PRE-SELL BOARD) FROST DEPTH.

- ALL FOOTING EXCAVATIONS ARE TO BE CLEAR OF WATER AND FOREIGN MATTER BEFORE PLACING CONCRETE
- PRESUMPTIVE MINIMUM ALLOWABLE LATERAL SOIL BEARING PRESSURE (So.) OF 150 PSF. CONTRACTOR SHALL HIRE A GEOTECHNICAL ENGINEER TO CONFIRM AN ALLOWABLE BEARING PRESSURE (S.) OF 1.500 PSF AND SHALL SUBMIT GEOTECHNICAL REPORT TO ARCHITECT AND STRUCTURAL ENGINEER OF RECORD. ALLOWABLE BEARING PRESSURE SHALL BE VERIFIED PRIOR TO CONCRETE PLACEMENT
- FOUNDATION SHALL NOT BE PLACED ON OR AT THE TOP OF A SLOPE EXCEEDING 3:1 WITHOUT EVALUATION BY A PROFESSIONAL LICENSED IN THAT STATE. DO NOT PLACE FOUNDATION IN FILL MATERIAL
- DEPTH OF PIER FOUNDATIONS MAY BE LOWERED IF NEEDED TO OBTAIN LOCAL FROST DEPTH ELEVATIONS OR IF REQUIRED DUE TO POOR SOIL CONDITIONS. VERIFY FROST DEPTH ELEVATIONS WITH LOCAL BUILDING CODE
- ELECTRICAL CONTRACTOR TO PROVIDE INFORMATION ON CONDUIT AND ELECTRICAL REQUIREMENTS AND CONTRACTOR (INSTALLER) SHALL COORDINATE PLACEMENT TO MAINTAIN 2" CLEAR TO ANCHOR BOLTS.
- COORDINATE LOCATIONS OF SIGNS AND FOUNDATIONS WITH SITE PLAN.
- CONTRACTOR SHALL CUT EXCESS SONOTUBE FROM AROUND THE PERIMETER OF THE PIER FOUNDATION AFTER PLACEMENT OF BOARD (PRIOR TO LEAVING SITE).
- CONTRACTOR SHALL NOT DEVIATE FROM STRUCTURAL DRAWING WITHOUT PRIOR WRITTEN CONSENT AND INSTRUCTIONS REGARDING ANY CHANGE TO THE CONTRACT DRAWINGS. ANY DEVIATION FROM THIS DESIGN OR FROM ANY PART OF THIS DRAWING WITHOUT PRIOR WRITTEN CONSENT OF THIS ENGINEER SHALL VOID ALL LIABILITY ASSOCIATED WITH THIS WORK.
- 11. SPECIAL INSPECTION IS NOT REQUIRED FOR THE SIGN FOUNDATIONS

CONCRETE NOTES:

- ALL FOOTINGS SHALL BEAR ON FIRM UNDISTURBED RESIDUAL SOIL AND/OR ENGINEERED EARTH FILL COMPACTED TO 95% OF ITS MAXIMUM DRY DENSITY AS PER ASTM D698 (STANDARD PROCTOR) UNLESS NOTED OTHERWISE. A LICENSED GEOTECHNICAL ENGINEER SHALL CONFIRM SOIL CAPACITY PRIOR TO CONCRETE
- ALL PIERS TO EXTEND TO FROST DEPTH AS DETERMINED BY LOCAL JURISDICTION, VERIFY WITH LOCAL BUILDING OFFICIAL.
- TOP OF PIERS SHALL BE SLOPED SUCH THAT MOISTURE CANNOT ACCUMULATE.
- ALL CONCRETE CONSTRUCTION SHALL BE IN ACCORDANCE WITH ACI 301 "STRUCTURAL CONCRETE FOR BUILDINGS" AND ACI 318 "BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE."
- ALL CAST-IN-PLACE CONCRETE SHALL ATTAIN AN ULTIMATE COMPRESSIVE STRENGTH (fc) OF 3000 PSI AT AN AGE OF 28 DAYS UNLESS OTHERWISE NOTED.
- ALL REINFORCING STEEL SHALL BE ASTM A 615, GRADE 60 DEFORMED BARS, UNLESS OTHERWISE NOTED.
- CONCRETE PROTECTION FOR REINFORCING AS WELL AS PLACING AND FABRICATION OF REINFORCING SHALL BE IN ACCORDANCE WITH THE "THE AMERICAN CONCRETE INSTITUTE BUILDING CODE REQUIREMENTS" (ACI
- ALL CAST-IN-PLACE CONCRETE SHALL BE AIR-ENTRAINED TO 6% (±1½%). WATER/CEMENT RATIO SHALL NOT
- THE MINIMUM CONCRETE COVER FOR THE PROTECTION OF REINFORCEMENT SHALL BE AS NOTED.
- 10. BEFORE PLACING CONCRETE, ALL EMBEDDED ITEMS SHALL BE PROPERLY PLACED, ACCURATELY POSITIONED, AND MAINTAINED SECURELY IN PLACE. NO "WET SETTING" IS ALLOWED.
- 11. AGGREGATES IN NORMAL WEIGHT CONCRETE SHALL CONFORM TO ASTM C-33 (HARDROCK).
- 12. PORTLAND CEMENT SHALL BE TYPE II FOR ALL CONCRETE CONFORMING TO ASTM C150, LOW ALKALI
- 13. FLY ASH OR OTHER POZZOLANS CONFORMING TO ASTM C618 CLASS N OR F MAY BE USED AS A PARTIAL SUBSTITUTION FOR PORTLAND CEMENT UP TO A MAXIMUM OF 25% TOTAL CEMENTITIOUS MATERIALS BE WEIGHT IF THE MIX DESIGN IS PROPORTIONED PER ACI318, SECTION 5.3. CONTRACTOR SHALL FORWARD DESIGN MIX TO ARCHITECT AND STRUCTURAL ENGINEER OF RECORD
- CONCRETE MIXING OPERATIONS, ETC. SHALL CONFORM TO ASTM C94.
- 15. DO NOT USE ANY CONCRETE OR GROUT CONTAINING CHLORIDES. WATER USED IN MIX SHALL BE CLEAN AND POTABLE.



508 baylor court





LLC LLC USA, McDonald's 101 RAI Ë

18790-33 RSW

BOARD FOUNDATIONS

PRE-SELL / MENU

S_{1.0} 1" = 1'-0"

\$1.0 \$1.0