

BALTIMORE COUNTY, MARYLAND  
DEPARTMENT OF PUBLIC WORKS AND TRANSPORTATION  
DIVISION OF CONSTRUCTION CONTRACTS ADMINISTRATION  
111 WEST CHESAPEAKE AVENUE  
TOWSON, MARYLAND 21204



Contract No. 23186 WX0  
Workday No. PROJ-10000520  
Back River Neck Road 16" and 24" Water Main Replacement Phase 3  
(Back River Neck Road from Homberg Avenue to North Hyde Park Road)  
Essex – District 15c7  
Job Order No's. 231-203-0067-0783

**ADDENDUM NO. 8**

**DATE:** 5/4/2026

**Contact:** Barb Wentworth, 410-887-3531, [bwentworth@baltimorecountymd.gov](mailto:bwentworth@baltimorecountymd.gov)

**To All Bidders**

This addendum is hereby made a part of the Proposal and the Special Provisions, and is hereby incorporated into the Contract. Should this addendum conflict with any portion of the Special Provisions, the Proposal, or any prior addenda, this addendum shall supersede and control.

Please note the attached changes, corrections, and/or information in connection with the contract and submit bids and be otherwise governed accordingly.

**For Your Information**

Attached are questions and answers received from contractors for clarifications on previous Addendums.

**In the Specifications**

**Remove and replace:**

- Page 11, Special Provisions Table of Contents, **Remove** line Thermoplastic Pavement Markings – Section 554.
- Page 18, Special Provisions, General Special Provisions, **Remove** Page 18 and **Replace with Revised** Page 18.
- Page 19, Special Provisions, General Special Provisions, **Remove** Page 19 and **Replace with Revised** Page 19.
- Pages 63 through 71, Special Provisions, Section 554 – Thermoplastic Pavement Markings **Delete** these pages entirely.

**In the Proposal**

**Revised and attached to be inserted:**

- Page 251, Proposal, Section IV – Description of Items & Schedules of Prices, **revise to** Item 10 F, Mix No. 1 Concrete for Miscellaneous Structures, Unit Price \$450.00 **from** Item 10, Mix No. 1 Concrete for Miscellaneous Structures.
- Page 253, Proposal, Section IV – Description of Items & Schedules of Prices, **revise** Item 36 description **to** Hot Mix Asphalt State 1 for Temporary Trench Repair @ 2"Depth **from** Hot Mix Asphalt State 1 for Temporary Trench Repair @ 3"Depth.

- Page 253, Proposal, Section IV – Description of Items & Schedules of Prices, **revise** Item 42 F, Borrow for Backfilling Trenches w/Proper Offsite Disposal of Unsuitable Material (Fixed Price Contingent Item) Estimated Quantity **to** 50 Cubic Yards (CY) **from** 9000 Cubic Yards (CY).
- Page 253, Proposal, Section IV – Description of Items & Schedules of Prices, **revise** Item 45 description **to** GAB for MOT, Estimated Quantity **to** 4,500 Ton (TON) and **from** GAB for Trench Repair, Estimated Quantity 4,000 Ton (TON).
- Page 253, Proposal, Section IV – Description of Items & Schedules of Prices, **Delete** Item 46, Milling Asphalt Paving Minimum 2”.
- Page 253, Proposal, Section IV – Description of Items & Schedules of Prices, **Delete** Item 47, 5 Inch Solid White Thermoplastic Pavement Markings.
- Page 253, Proposal, Section IV – Description of Items & Schedules of Prices, **Delete** Item 48, 5 Inch Solid Yellow Thermoplastic Pavement Markings.
- Page 253, Proposal, Section IV – Description of Items & Schedules of Prices, **Delete** Item 49, 16 Inch Solid White Thermoplastic Pavement Markings for Cross Hatch.
- Page 253, Proposal, Section IV – Description of Items & Schedules of Prices, **Delete** Item 50, 24 Inch Solid White Thermoplastic Pavement Markings for Stop Bars.
- Page 253, Proposal, Section IV – Description of Items & Schedules of Prices, **Delete** Item 51, Thermoplastic Pavement Markings and Legends and Symbols.

Attachments – 18

**Please sign below acknowledging receipt of this addendum and return with your bid.**

\_\_\_\_\_  
Company Name

\_\_\_\_\_  
Signature

**Updated responses to RFI Bidder questions from Addendum No. 5 (4/7/26 to 4/10/26)**

**4-7-26**

1. Please provide or reference the standard details for bid items 36 and 37, Stage 1 and Stage 2 Trench Repair.

Response: Refer to Baltimore County Standard Details G-6, G-7, W-29 and R-38 for trench repair and repaving.

7. Why is there not an item for 2" Overlay. Item 37 quantity is severely understated to cover both trench repair and overlay.

Response: Bid item 46 has been removed. Trench repair and overlay will be done as shown in Baltimore County standard detail R-38 and will be paid with bid item 37.

8. For item 37 will the County pay the volume of Stage 2 trench patch complete, or will the amount milled out for Stage 2 Overlay be discounted?

Response: Please refer to standard detail R-38 for Repaving Trench Opening. Milling Bid item has been removed.

**4-8-26**

1. Will the County measure and pay for Stage 1, Stage 2 Trench repair, GAB, R&R Curb & sidewalk, etc. under those bid items as it relates to the installation, removal & restoration for the Temp By-pass items or will this work be incidental? Please confirm or clarify.

Response: Temporary bypass payment includes excavation, backfill and compaction, graded aggregate base (GAB), concrete, restoration and all work necessary to restore driveway entrances. Hot mix will be paid with stage 2

**4-9-26**

2. Addendum 3 Bid Form, Item 45 GAB for Trench Repair is noted as "Write-in" which implies contingent item. Please confirm or clarify, is GAB for Trench Repair paid under item 45 or is it incidental to all pipe/trench items?

Response: This item has renamed as GAB for MOT. GAB requires within the trench to install the pipe is incidental to the pipe. The GAB used as part of any base for Stage II- Permanent trench repair widening, crossings etc.

3. Plate R-38 is not referenced in Addendum 3 as it relates to Stage 1 and Stage 2 Trench Repair Items. Please state the net depth of GAB that is to remain in the full width of the trench following the Stage 2 repairs.

Response: Stage 1 and Stage 2 will be done as per County detail R-38. For trench width refer to County detail G-6. GAB used with in the trench width will be incidental to the pipe.

6. Why is item 61 being considered a contingent item?

Response: Item 61 is not contingent item. Write-ins are for line items without pre-existing commodity codes.

#### **4-10-26**

1. On Page 18 of the Proposal, it states that "Geotextile filter fabric shall be placed between the sub-base material and the GAB". Please confirm that geotextile filter fabric is to be placed under the GAB.

Response: Page 18 and 19 has been revised. Please refer to addendum#8

3. Please confirm if Line Items 36 and 37 will apply to restoring the trenched bypass pipe, or if the rehabilitation costs for the trenched bypass pipe is incidental to the line item.

Response: Line items 36 and 37 apply to restoring trench for both pipe and bypass.

5. Please confirm Item #46 includes milling 2" depth and paving 2" depth.

Response: This Bid item has been removed, Trench repair shall be done as per R-38 and restoration will be paid under bid item 36 and 37.

6. For the sand around the Ductile Iron Pipe per W-29, would a limestone sand be acceptable if it meets the ASTM C-33 specifications?

Response: Sand should meet ASTM C-33 which can be limestone-based product for Ductile Iron Pipe bedding.

**Standard Specifications for Construction SPECIAL PROVISIONS**

General Special Conditions.....N/A  
Selected Backfill .....Section 302  
Erosion and Sediment Control.....Section 308  
Water Mains.....Section 351  
Water House Service, Water Meter Setting, and Vaults.....Section 353  
Corrosion Control .....Section 372  
Temporary Water Bypass .....Section 373  
Miscellaneous .....Section 921

APPENDIX A – GEOTECHNICAL EVALUATION REPORT

APPENDIX B – TEST HOLE REPORTS

APPENDIX C – VALVE SHUTDOWN REQUEST FORM

APPENDIX D – BALTIMORE COUNTY DEPARTMENT OF ENVIRONMENTAL  
PROTECTION & SUSTAINABILITY STORMWATER MANAGEMENT  
VARIANCE

APPENDIX E – PERMITS

APPENDIX F – TEMPORARY BYPASS SKETCHES

**Contract No. 23186 WX0**  
**Addendum No. 8**  
**Revised, May 4, 2026**

Plans included with the Contract Drawings and the Maryland Manual on Uniform Traffic Control Devices (MD MUTCD) 2011 Edition and all supplements and revisions.

11. Trench and Paving Restoration

All final paving shall be done by a County prequalified A2 Contractor. Refer to Standard Details G-6 and G-7 for trench width and quantities.

For trench restoration Contractor shall refer to the details provided, including Baltimore County Standard Detail R-38, in the Contract Documents and as directed by the area Engineer.

Graded Aggregate Base for MOT will be paid under Bid Item# 45.

Temporary Trench Repair – Stage 1 asphalt (2- inch thickness) will be paid under Bid Item#36.

Base Coarse for permanent Trench Restoration will be paid under Bid item#37.

12. Contingent Bid Items

Bid items that are identified as “Contingent Bid Items” are established for the sole purpose of obtaining unit costs on pay items that may be incorporated into the project. The Engineer shall have sole discretion in determining whether and to what extent such items will be incorporated into the project. The Engineer may order incorporation of such items at any location within the Contract and at any time during the work. Neither the Contractor nor his/her subcontractor shall make claims for additional compensation because of any increase/decrease in quantities, or the complete elimination of such items.

**THIS  
PAGE IS  
NOW  
BLANK**

**Contract No. 23186 WX0  
Addendum No. 8  
Revised, May 4, 2026**

**THIS  
PAGE IS  
NOW  
BLANK**

**Contract No. 23186 WX0  
Addendum No. 8  
Revised, May 4, 2026**

**THIS  
PAGE IS  
NOW  
BLANK**

**Contract No. 23186 WX0  
Addendum No. 8  
Revised, May 4, 2026**

**THIS  
PAGE IS  
NOW  
BLANK**

**Contract No. 23186 WX0  
Addendum No. 8  
Revised, May 4, 2026**

**THIS  
PAGE IS  
NOW  
BLANK**

**Contract No. 23186 WX0  
Addendum No. 8  
Revised, May 4, 2026**

**THIS  
PAGE IS  
NOW  
BLANK**

**Contract No. 23186 WX0  
Addendum No. 8  
Revised, May 4, 2026**

**THIS  
PAGE IS  
NOW  
BLANK**

**Contract No. 23186 WX0  
Addendum No. 8  
Revised, May 4, 2026**

**THIS  
PAGE IS  
NOW  
BLANK**

**Contract No. 23186 WX0  
Addendum No. 8  
Revised, May 4, 2026**

**THIS  
PAGE IS  
NOW  
BLANK**

**Contract No. 23186 WX0  
Addendum No. 8  
Revised, May 4, 2026**

## CONTRACT PROPOSAL

BACK RIVER NECK ROAD 16" AND 24" WATER MAIN REPLACEMENT - PHASE 3

CONTRACT NUMBER: 23186-WX0

WORKDAY NUMBER: 10000520

JOB ORDER NUMBER: 231-203-0067-0783

WORKING CALENDAR DAYS: 400

**CONTRACTOR:** \_\_\_\_\_  
**ADDRESS:** \_\_\_\_\_  
**PHONE:** \_\_\_\_\_

BID ITEM	COMM. CODE		DESCRIPTION	UNIT	ESTIMATED QUANTITY	UNIT PRICE	TOTAL AMOUNT
1	130850		MOBILIZATION	LS	1		\$
2	120500		MAINTENANCE OF TRAFFIC	LS	1		\$
3	WRITE-IN		INLET PROTECTION - CURB	EA	35		\$
4	704345		PLACING FURNISHED TOPSOIL 4 INCH DEPTH	SY	48		\$
5	707301		SEEDING	SY	48		\$
6	WRITE-IN		TEMPORARY MULCHING	SY	48		\$
7	130840		CONSTRUCTION STAKEOUT	LS	1		\$
8	800010	F	TEST PIT EXCAVATION IN COUNTY ROADS VIA TRADITIONAL METHOD	CY	300	\$360.00	\$108,000.00
9	110330		ENGINEER'S OFFICE NO.3	LS	1		\$
10	800050	F	MIX NO. 1 CONCRETE FOR MISCELLANEOUS STRUCTURES	CY	8	\$450.00	\$3,600.00
11			DELETED		0	\$0.00	\$0.00
12	863060		6 INCH DUCTILE IRON PIPE AND FITTINGS - CLASS 54	LF	496		\$
13	863080		8 INCH DUCTILE IRON PIPE AND FITTINGS - CLASS 54	LF	480		\$

14	863120		12 INCH DUCTILE IRON PIPE AND FITTINGS - CLASS 54	LF	169		\$
15	863160		16 INCH DUCTILE IRON PIPE AND FITTINGS - CLASS 54	LF	2,325		\$
16	863240		24 INCH DUCTILE IRON PIPE AND FITTINGS - CLASS 54	LF	2,913		\$
17	847060		6" FIRE HYDRANT / FURNISH AND INSTALL	EA	11		\$
18			DELETED		0	\$0.00	\$0.00
19	836060		6 INCH VALVE AND VAULT - VERTICAL	EA	12		\$
20	836080		8 INCH VALVE AND VAULT - VERTICAL	EA	10		\$
21	836120		12 INCH VALVE AND VAULT - VERTICAL	EA	3		\$
22	836160		16 INCH VALVE AND VAULT - VERTICAL	EA	1		\$
23	836230		24 INCH VALVE AND VAULT - VERTICAL	EA	2		\$
24	842010		3/4 IN. WATER SERVICE TAP AND CORPORATION	EA	38		\$
25	843010		3/4 IN. COPPER WATER SERVICE AND FITTINGS	LF	1,020		\$
26	842020		1 IN. WATER SERVICE TAP AND CORPORATION	EA	5		\$
27	843020		1 IN. COPPER WATER SERVICE AND FITTINGS	LF	125		\$
28	842030		1-1/2 IN. WATER SERVICE TAP AND CORPORATION	EA	3		\$
29	843030		1-1/2 IN. COPPER WATER SERVICE AND FITTINGS	LF	81		\$
30	842040		2 IN. WATER SERVICE TAP AND CORPORATION	EA	4		\$
31	843040		2 IN. COPPER WATER SERVICE AND FITTINGS	LF	149		\$
32			DELETED		0	\$0.00	\$0.00
33	WRITE-IN	C	REPLACEMENT OF WATER METER SETTING (ALL SIZES) (CONTINGENT ITEM)	EA	8		\$

34	WRITE-IN	C	REPLACEMENT OF WATER METER FRAME, COVER, AND VAULT (ALL SIZES) (CONTINGENT ITEM)	EA	8		\$
35			DELETED		0	\$0.00	\$0.00
36	120561		HOT MIX ASPHALT STAGE 1 FOR TEMPORARY TRENCH REPAIR @ 2" DEPTH	TON	930		\$
37	120562		HOT MIX ASPHALT STAGE 2 FOR PERMANENT TRENCH REPAIR	TON	2,500		\$
38	210011		REMOVE AND REPLACE EXISTING CURB AND GUTTER	LF	305		\$
39	210021		REMOVE AND REPLACE EXISTING CONCRETE SIDEWALK	SF	720		\$
40	WRITE-IN	C	GEOTEXTILE CLASS SE (CONTINGENT ITEM)	SY	8,000		\$
41	WRITE-IN	C	GEOTEXTILE CLASS ST (CONTINGENT ITEM)	SY	8,000		\$
42	800060	F	BORROW FOR BACKFILLING TRENCHES W/ PROPER OFFSITE DISPOSAL OF UNSUITABLE MATERIAL (FIXED PRICE CONTINGENT ITEM)	CY	50	\$80.00	\$4,000.00
43	800020	F	CLASS 3 EXCAVATION W/ SELECT BACKFILL & PROPER OFFSITE DISPOSAL OF UNSUITABLE MATERIAL (FIXED PRICE CONTINGENT ITEM)	CY	300	\$130.00	\$39,000.00
44	Write In	C	TRENCH ROCK EXCAVATION WITH PROPER DISPOSAL (CONTINGENT ITEM)	CY	250		\$
45	WRITE-IN	C	GAB FOR MOT	TON	4,500		\$
46			DELETED		0	\$0.00	\$0.00
47	0		DELETED		0	\$0.00	\$0.00
48	0		DELETED		0	\$0.00	\$0.00
49	0		DELETED		0	\$0.00	\$0.00
50	0		DELETED		0	\$0.00	\$0.00
51			DELETED		0	\$0.00	\$0.00

52	WRITE-IN	C	PITCHER FILTER WITH SIX MONTHS OF REPLACEMENT CARTRIDGES	EA	5		\$
53	WRITE-IN	C	FURNISH AND INSTALL ADDITIONAL 16" MJ RESTRAINED DUCTILE IRON 1/8 BENDS	EA	8		\$
54	WRITE-IN	C	FURNISH AND INSTALL ADDITIONAL 24" MJ RESTRAINED DUCTILE IRON 1/8 BENDS	EA	8		\$
55	WRITE-IN		REMOVAL OF 6" FIRE HYDRANT AND CAP AT TEE	EA	3		\$
56	837260		8 INCH X 6 INCH TAPPING SLEEVE, VALVE, AND VAULT	EA	3		\$
57	WRITE IN		24 INCH X 6 INCH TAPPING SLEEVE, VALVE, AND VAULT (PCCP )	EA	3		\$
58	849410		2 INCH TEMPORARY BY-PASS LINES	LF	1,045		\$
59	849420		4 INCH TEMPORARY BY-PASS LINES	LF	450		\$
60	849430		6 INCH TEMPORARY BY-PASS LINES	LF	280		\$
61	849440		8 INCH TEMPORARY BY-PASS LINES	LF	3,650		\$
<b>TOTAL COST FOR CONTRACT</b>							\$

---

*TOTAL COST FOR CONTRACT IN WORDS*

---

OFFICER SIGNATURE

---

TITLE

**Contract No. 23186 WX0  
Addendum No. 8  
Revised, May 4, 2026**