# PROPOSAL FORM

# BALTIMORE COUNTY DEPARTMENT OF PUBLIC WORKS & TRANSPORTATION TOWSON. MARYLAND

# Division of Construction Contracts Administration



Contract Number 23186 WX0 WATER DESIGN PROJECT

Back River Neck Road 16"and 24" Water Main Replacement - Phase 3 (Back River Neck Road from Homberg Avenue to North Hyde Park Road)
Essex - District 15c7

Workday Number PROJ-10000520 Job Order Number 231-203-0067-0783

CONTRACT BASED ON SEPTEMBER 2023
STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS
AND STANDARD DETAILS FOR CONSTRUCTION

## **Bidders Information**

A pre-bid meeting **ONLY** for Prevailing Wage & Local Hiring and MBE/WBE requirements will be held on Wednesday, October 15, 2025 at 10:00 a.m. EST via WebEx.

Phone-In (Audio Only) 1-415-655-0001, Meeting Number 2312 514 5226##.

Video Conference go to <a href="https://signin.webex.com/join">https://signin.webex.com/join</a> Meeting Number 2312 514 5226,

Password **8RUv8UyT8PH**, for Webex link go to:

www.baltimorecountymd.gov/departments/public-works/engineering/contracts/current-solicitations

Last day for questions will be Friday, October 17, 2025 at 4:00 p.m. EST. Questions should be emailed to Pawan Poudel at <a href="mailto:ppoudel@baltimorecountymd.gov">ppoudel@baltimorecountymd.gov</a> and Barbara Wentworth at <a href="mailto:bwentworth@baltimorecountymd.gov">bwentworth@baltimorecountymd.gov</a>.

Baltimore County Prevailing Wage and Local Hiring Affidavit, Wage Rates & Requirements **see** pages <u>262-269</u>

(Contract Disclosure): "Wage rates that are in effect as of the contract solicitation date will be the wage rates through the duration of the project"

MBE/WBE Requirements & Forms see pages 270-284

# THIS PROPOSAL FORM INCLUDES AND INCORPORATES ALL DOCUMENTS AND INFORMATION REFLECTED, LISTED, AND/OR REFERENCED IN THIS TABLE OF CONTENTS, AND ALL SUCH DOCUMENTS AND INFORMATION ARE PART OF AND INCORPORATED INTO THE CONTRACT DOCUMENTS.

# TABLE OF CONTENTS

	Number	SECTION NAME	Page <u>Number</u>
	Page (cover)e of Contents		
I.	INFORMATION FOR BIDDERS	S	3-6
II.	SPECIAL PROVISIONS		7-238
III.	Grading Permit Stormwater Management Vari Environmental Agreement	iance	240-241 242 243-244
IV.	PROPOSAL (This section to be	e completed at time of bid)	249
	Description of Items & So Proposal Affidavit Bid Bond Baltimore County Prevail Affidavit, Wage Rates an	chedule of Pricesling Wage and Local Hiring	251-254 255-260 261 262-269
V.	POST AWARD DOCUMENTS	s and Forms  (This Section to be completed	270-284
••		er award)	285
	Performance Bond Payment Bond		289 290

# SECTIONI

# **INFORMATION FOR BIDDERS**

# **ELECTRONIC SUBMITTAL PROCESS**

To be considered, Bids (Section IV – Proposal) shall be received by the bid closing date and time to the following email address <a href="mailto:dpwbid@baltimorecountymd.gov">dpwbid@baltimorecountymd.gov</a>. The contract number and company name should be referenced in the Subject Line of the email. Bids may not be submitted by any other means. Bids that are mailed or otherwise delivered to the Purchasing Division (including emails which indicate links to locations where the bid may be downloaded) and/or emails sent to any other Baltimore County email address will not be accepted.

Late Bids will not be considered. Bidders are strongly encouraged not to wait until the last minute to submit bids. The time stated on the auto-receipt (described below) will be definitive of the time of receipt. Bids received after the deadline will not be accepted. Bidders are advised that the County cannot receive email attachments greater in size than twenty-five (25) megabytes and this size limitation may be further reduced by requirements of the Bidder's email provider which are beyond the control of the County. Bidder should consider separating any large bid attachment into multiple parts and emailing each part separately. In such case, Bidder will note that each email is 1 of 2, 2 of 2, etc. Multiple part bids will not be considered unless all parts are received by the bid closing date and time.

After submitting a Bid to <a href="mailto:dpwbid@baltimorecountymd.gov">dpwbid@baltimorecountymd.gov</a>, and upon successful receipt by the County thereof, Bidder will receive an auto-receipt email. This receipt is proof that the bid has been received by the Division of Construction Contracts Administration and should be retained for Bidder's records. In the case of a bid submitted in multiple parts as described above, an auto-receipt email will be generated for each part. The County has no obligation to consider any Bid for which an auto-receipt was not generated.

As with any system, power outages or technology problems may arise that are outside of the County's control and could affect your submission. The County will not be held accountable for such issues that may delay the transmission of any Bid.

**NOTE:** Electronic copy of the Bid Bond will be accepted at bid opening. The apparent low bidder is required to submit the original Bid Bond within ten (10) days after the bid opening to the Division of Construction Contracts Administration, 111 West Chesapeake Avenue, Room 300B, Towson, Maryland 21204.

# **INSTRUCTIONS AND SPECIFICATIONS**

Refer to the enclosed proposal sheets for quantities to be bid upon. All proposals submitted on the attached form must give the price in clear figures for each item of the proposed work and be signed by the bidder with his name and address. Bidders must not change any item in the proposal for which a price has been stipulated by the County. Any change will cause rejection of the proposal.

NOTE: STATEMENT UNDER OATH FORM TO ACCOMPANY BID as per Baltimore County Purchasing Act 65-98, Section 15-94 and 15-95 which requires that the enclosed affidavit (see Proposal Affidavit pages in Section IV) be completed and submitted as part of the sealed bid.

Proposals made on any other than the attached form will not be considered. All papers included in, bound thereto, or attached to the Proposal Form are necessary parts thereof and shall not be detached, separated, or altered in their intent.

Changes in the phraseology of the proposal, additions, or limiting provisions will render the proposal informal or void and may cause its rejection.

All right is hereby reserved by the Purchasing Agent to reject any or all proposals and to waive formalities and technicalities as the interest of the County may require.

No successful bidder may withdraw his bid within **NINETY (90)** days after the opening thereof.

The successful bidder will be required to be bonded to Baltimore County, Maryland to the sum of One Hundred per Cent (100%) of the amount of his proposal or proposals according to the form of bond hereto attached for projects in excess of \$25,000.00.

This Proposal must be accompanied by a Bid Bond in an amount of 5% of the bid, the exact amount to be determined by the difference between the low bid and the next lowest bid if two or more bids are received, or 5% of the bid if one bid is received. This guarantees payment of the amount thus determined in case of a default in any matter specified as required before award or in any matter resulting in failure to execute and deliver an Agreement, together with Payment and Performance Bonds, after award. The Bid Bond must be in the form accompanying the Proposal executed by a Surety licensed in the State of Maryland. The Surety must be currently rated "B" or better by the A. M. Best Company, and the bid must be in an amount less than, or equal to, the underwriting limitation contained in Department of Treasury Circular 570 as amended at the time of the underwriting.

All work to be performed under this contract shall be done under strict compliance with Baltimore County Department of Public Works and Transportation September 2023 <u>Standard Specifications for Construction and Materials</u> and <u>Standard Details for Construction</u> and any and all proposed revisions thereto as of the date of advertisement and copies of which are available on the County's website at <u>www.baltimorecountymd.gov/departments/public-works/standards</u>, and all of which are made a part hereof and incorporated herein (collectively, the "Specifications").

If the bidder to whom an award is made shall fail to execute the contract and bond hereto attached and as herein provided, the award may be annulled and the contract awarded to the lowest responsible bidder who has consented to a time extension, and such bidder shall fulfill every stipulation embraced herein as if he were the original party to whom the award was made, or the Purchasing Agent may reject all of the bids as the interest of the County may require.

The Bid Bond of the three lowest bidders is deemed to be effective until the execution and delivery of the Contract Agreement, together with Payment and Performance Bonds for projects in excess of \$25,000.00 or until rejection of all bids, whereupon Surety is deemed relieved of all further obligations under the bid bonds provided.

Bidders must examine the drawings and specifications carefully and must make a personal examination of the location and nature of the proposed work. In case doubt shall arise as to the meaning or intent of anything shown on the drawings or comprised in the specification, inquiry shall be made of the Director of Public Works and Transportation at least five (5) days prior to the date of

bid opening. The submission of the Proposal shall indicate that the bidder thoroughly understands the drawings and the terms of the Specifications.

To better ensure fair competition and to permit a determination of the lowest bidder, unresponsive bids or bids obviously unbalanced may be rejected by the Purchasing Agent.

Bidders are required to fill out the total price column and total their proposals so that the result of the bidding, barring possible arithmetical errors, will be known at once. Any errors in computations will be corrected by the Engineer when the proposals are canvassed. Where the unit price and the total price are at variance, the unit price will prevail.

Bidders must be prepared to complete the work within the time stated in the proposal.

NOTE: ONLY CONTRACTORS FORMALLY PRE-QUALIFIED WITHIN THE ADVERTISED WORK CLASSIFICATION BY THE DIRECTOR OF PUBLIC WORKS AND TRANSPORTATON OF BALTIMORE COUNTY 10 CALENDAR DAYS PRIOR TO BID OPENING WILL BE ELIGIBLE TO SUBMIT BIDS.

Contracts for work under this proposal will obligate the contractors and subcontractors not to discriminate in employment practices. Bidders must, if requested, submit a compliance report concerning their employment practices and policies in order to maintain their eligibility to receive the award of the contract. Successful bidders must be prepared to comply in all respects with the Contract Provisions regarding nondiscrimination.

Baltimore County has adopted a Minority Business Enterprise (MBE) program and Women's Business Enterprise (WBE) Program. The percentage of participation applies to the contract amount awarded to the Contractor. Qualified minority subcontractors are those certified as being a Minority Business Enterprise by the following:

- 1. Maryland Department of Transportation Certification Committee (MDOT)
- 2. City of Baltimore, Minority Business Certification Council

Projects funded by the Federal Highway Administration are limited to the certification listed under #1 (MDOT).

More detailed information regarding the County's MBE/WBE Program can be obtained from the County MBE Office, telephone (410) 887-3407. See Executive Order dated December 6, 2022. MBE/WBE Participation Summary and Forms A, B, C, D and E enclosed in this proposal booklet.

**NOTE:** If you do not complete and submit the enclosed forms with your bid or offer to the County, the County may, in its sole discretion, deem your bid or offer **NON-RESPONSIVE** and accordingly the **COUNTY WILL NOT CONSIDER YOU FOR CONTRACT AWARD**.

The County reserves the right to require the low bidder to produce evidence indicating that the company's financial condition is equal to, or better than, that enjoyed by the company at the time of prequalification. This additional information may be in the form of a financial statement or other evidence satisfactory to the Office of Budget and Finance.

Bidders' attention is directed to the requirement that a permit must be obtained from the Baltimore County Bureau of Highways and Bureau of Traffic Engineering prior to cutting any County

road for the purpose of obtaining sub-surface soils information, and permission must be obtained from the State Highways Administration prior to making any openings in a State road.

Under no circumstances shall a bidder enter upon any property outside a County or State road for the purpose of securing sub-surface soils information until permission is received from the property owner. The fact that the County has obtained a utility easement does not give the bidder the right to enter upon the property.

# Prevailing index price of asphalt cement/ton \$640.00.

<u>INCLEMENT WEATHER POLICY:</u> If Baltimore County <u>General Government</u> Offices are open or open with liberal leave the day the bids are due, the bids are due as stated in the bid documents (date and time). <u>ONLY</u> when the Baltimore County <u>General Government Offices</u> are <u>OFFICIALLY CLOSED</u> the day the bids are due, the bid date will be postponed and an Addendum will be issued the next business (or next day buildings are officially open) day the county offices are open with the new bid date and time.

<u>BID TABULATIONS:</u> All bid tabulations will be confidential until after final award, at which time the total bid amounts for all bidders, as well as the complete bid tabulations for the top three (3) bidders, can be inspected by others when requested in writing pursuant to the Maryland Public Information Act.

ALTERNATIVE SOURCES OF CONTRACT BONDS: In the event your company is unable to qualify for bonding through a traditional commercial surety company, you may qualify for the required bonds through the State of Maryland, Department of Commerce (DOC). The Maryland Small Business Development Financing Authority (MSBDFA, pronounced Mis-Bid-Fa), an agency of DOC, operates a Surety Bond Program designed to assist small businesses, based in Maryland, that are unable to obtain adequate bonding on reasonable terms in the commercial marketplace. MSBDFA provides bid, payment and performance bonds for contracts funded by government agencies, regulated utilities and private entities. The penal sums of the bonds are limited to the aggregate amount of \$2,500,000 and companies may pre-qualify for multiple bonds within pre-approved terms and conditions. MSBDFA also provides lines of credit, term loans and loan guarantees to help qualified businesses purchase equipment and real property, make improvements to leased property, refinance existing debt and assist them with their working capital needs. For more information on how to apply, you may contact: Meridian Management Group, Inc. (MMG), (the Program's Manager), 826 E. Baltimore Street, Baltimore, Maryland 21202, Telephone: (410) 333-4270. Or visit their website at <a href="www.mmgcapitalgroup.com">www.mmgcapitalgroup.com</a> for information, applications and a checklist of required documents and reports that must accompany the application.

# SECTION II

**SPECIAL PROVISIONS** 

# **MAINTENANCE BOND**

Per the Baltimore County Department of Public Works and Transportation September 2023 Standard Specifications for Construction and Materials, Section GP - 4.10 (C) states, the contractor is required to post a maintenance bond in the amount of five (5) percent of the total cost of the contract or withhold five (5) percent retainage for two (2) years from the date of Final Acceptance.

GP-SECTION 4.10(C) **REVISED** 09/2024 8

BOND NO
CONTRACT NO
MAINTENANCE BOND
THIS MAINTENANCE BOND is entered into on this day of , 20, by and between
as principal ("Principal") and, a business entity that is authorized to transact business in the State of Maryland and is organized and existing under the laws of the State of, as surety ("Surety"), are held and firmly bound unto Baltimore County, Maryland, a body corporate and politic of the State of Maryland ("County"), as Obligee.
WHEREAS, the above-named Principal has entered into a written contract known as Contract Number dated, 20 with Obligee for
(the "Agreement"), the terms of which are hereby incorporated by reference; and
WHEREAS, Principal has completed construction under the Agreement; and
WHEREAS, the Agreement includes a warranty on the quality of the Work performed that runs for a period of two (2) years from the date of the County's final acceptance and that runs for two (2) additional years beyond the repair date if any repair is done during the warranty period; and
WHEREAS, Principal is required to cause this instrument to be executed and delivered to Obligee as security for maintenance during the warranty period in an amount equal to 5% of the total value of the Contract.
NOW, THEREFORE, the Principal and Surety are held and firmly bound unto the Obligee in the sum of \$
Sum of \$
The conditions of this bond are as follows:
1. The Principal shall, for a period of two (2) years from and after the date of completion and acceptance of same by Obligee, replace all defects arising in the Work, whether resulting from defective materials, equipment, design furnished or workmanship. After such period, this obligation shall be null and void; otherwise it shall remain in full force and effect.

BALTIMORE COUNTY, MARYLAND

GP-SECTION 4.10(C) **REVISED** 9

- 2. In the event of a default on the part of the Principal that may be the subject of a claim under this bond, Obligee shall mail, by certified mail, to Surety at the address listed below, a written statement that a claim is being made under the bond and, with substantial accuracy, the amount of the claim. Surety shall have no obligation to Obligee under this bond until the notice of claim is mailed.
- 3. When the Obligee has satisfied the condition of Paragraph 2 that a notice of claim be mailed, the Surety shall promptly and at the Surety's expense send an answer to Obligee within 30 days after the date of the claim. The answer shall state the amounts that are undisputed and the basis for challenging any amounts that are disputed. The answer shall be accompanied by payment (or arrangements for immediate payment) of any undisputed amounts.
- 4. Surety expressly waives any right to receive notice of extensions of time or alterations or modifications to the Agreement that may be granted by Obligee and agreed upon by Principal, and any such extensions, alterations, or modifications shall not affect the obligation of the Surety under this bond.
- 5. This bond is a specialty governed by the twelve-year statute of limitations period set forth in the Annotated Code of Maryland Courts and Judicial Proceedings §5-102.

WITNESS OR ATTEST:	(Principal – Contractor Name)	
	By:	
	Type Name:	
	Type Title:	
	Date:	
	(Surety)	
	By:	
	Type Name:	
	Type Title:	
	Type Address:	
	Date:	

GP-SECTION 4.10(C) REVISED 09/2024

# **Standard Specifications for Construction SPECIAL PROVISIONS**

General Special Conditions	N/A
Selected Backfill	Section 302
Erosion and Sediment Control	Section 308
Water Mains	Section 351
Water House Service, Water Meter Setting, and Vaults	Section 353
Corrosion Control	Section 372
Temporary Water Bypass	Section 373
Thermoplastic Pavement Markings	Section 554
Miscellaneous	Section 921

APPENDIX A – GEOTECHNICAL EVALUATION REPORT

APPENDIX B – TEST HOLE REPORTS

APPENDIX C – VALVE SHUTDOWN REQUEST FORM

APPENDIX D – BALTIMORE COUNTY DEPARTMENT OF ENVIRONMENTAL PROTECTION & SUSTAINABILITY STORMWATER MANAGEMENT VARIANCE

APPENDIX E – PERMITS

## **GENERAL SPECIAL CONDITIONS**

# 1. <u>Location and Description of the Water Main Work</u>

The work to be completed under this Contract includes all labor, materials, and equipment necessary to furnish and install various diameter ductile iron water mains along Back River Neck Road from Homberg Avenue to Hyde Park Road, including valves, valve vaults, fire hydrants, fittings, service connection renewals, pressure testing, disinfection, connection to existing water mains, and appurtenances at the locations shown on the Contract Drawings. As part of the work, all existing service connections that are currently served from the existing water main in Back River Neck Road (and side streets) shall be replaced from the new replacement water main to the existing meter boxes. The Engineer on the job site will determine whether to use the existing meter vault or replace it, depending on its condition. After the installation of the water main connections and services, the existing water mains in Back River Neck Road will be abandoned in place.

The site is located in the eastern part of Baltimore County along Back River Neck Road in the Essex area. The project includes, but is not limited to, the construction of the following water mains and appurtenances:

- 2.913 linear feet of 24-inch water main
- 2,325 linear feet of 16-inch water main
- 169 linear feet of 12-inch water main
- 533 linear feet of 8-inch water main
- 321 linear feet of 6-inch water main
- 22 linear feet of 4-inch water main
- Nine (9) 6-inch fire hydrants
- 4-inch thru 24-inch gate valves and vaults
- Fifty (50) 3/4-inch through 2-inch water service reconnections
- 1,036 linear feet of 3/4-inch copper water service pipe
- 125 linear feet of 1-inch copper water service pipe
- 81 linear feet of 1-1/2-inch copper water service pipe
- 149 linear feet of 2-inch copper water service pipe

All ductile iron water main pipe on this project will have bonded coatings and full cathodic protection. Cathodic protection shall be installed as shown on the plans. The cost for all coatings and cathodic protection shall be included in the prices bid for the proposed ductile iron water main pipe items.

All ductile iron water main pipe shall be special thickness class 54 in accordance with the latest ANSI/AWWA C151/A21.51. Ductile iron fittings shall meet the latest ANSI/AWWA C110/A21.10 and ANSI/AWWA C153/A21.53. Interior surfaces of all ductile iron pipe and fittings shall be cleaned and cement-mortar-lined at the pipe casting

facility with the double thickness cement-mortar lining applied in conformance with the ANSI/AWWA C104/A21.4, latest revisions.

External pipe surfaces (including all piping, joints, valves, fittings, hydrant piping, etc.) shall be coated in accordance with Section 1012 Corrosion Control.

Contract incorporates the use of insulating corporation stops for all service connections 3/4-inch through 2-inches in diameter.

# 2. Engineer

REMOVE the definition of "Engineer" in General Provision GP-1.03 "Organizational Definitions" listed in the Baltimore County Department of Public Works and Transportation September 2023 Standard Specifications for Construction and Materials and Standard Details for Construction and Materials" and REPLACE with the following:

**Engineer** - One of the following engineering executives:

Director of Public Works and Transportation Deputy Director of Public Works and Transportation Chief, Division of Construction Contracts Administration Chief, Bureau of Engineering & Construction

Any delegation of the Engineer's authority must be authorized in writing by any one of the above listed officials, and such delegation of authority will pertain only to the specific contract and/or contracts shown by the authorization. The title of the specific official will appear in those cases within these specifications where the word "Engineer" as defined herein is not sufficiently specific.

# 3. Contractor Staging Area(s)

All staging area(s) shall be obtained by the Contractor at his expense. No separate payment will be made for the costs associated with the Contractor staging area(s). All work, materials, labor, etc. required for this item will be considered incidental to the work required under this Contract.

# 4. Specifications

All water main and services work on this project shall conform to the Baltimore County Department of Public Works and Transportation September 2023 Standard Specifications for Construction and Materials and Standard Details for Construction and Materials" dated September 2023 and as amended, and the Standard Details for Construction, dated

September 2024 and as amended, and the Special Provisions included in this Contract book.

In any and all cases of conflict between the Standards and the Contract Documents, the Contract Documents shall govern but only to the extent of such conflict. Any reference in the water main portion of the Contract Documents made to a Standard Number shall refer to Baltimore County's Book of Standards unless otherwise noted.

Any discrepancies found between the Contract Drawings and the Specifications or any inconsistencies in the Contract Drawings or Specifications shall be reported immediately to the Engineer, in writing who promptly will correct such inconsistencies or ambiguities in writing. Work done by the Contractor after his/her discovery of such inconsistencies, discrepancies, or ambiguities prior to corrections directed by the Engineer, will be done at the Contractor's risk. In case of discrepancy or omission, the Engineer will determine the intent of the design in issuing clarifying or corrective instructions.

All materials and coatings that come in contact with drinking water shall be tested and certified to NSF/ANSI 61 Drinking Water System Components-Health Effects and certified to be lead free in accordance with NSF/ANSI 61 – Annex G.

# 5. Sheeting and Shoring

No separate payment will be made for the cost of furnishing, installing and removing build-in-place support of excavation system. All work, materials, labor, etc. associated with furnishing, installing and removing built-in-place support of the excavation system will be considered incidental to the work required under this Contract. Sheeting and shoring may be left in place at 2-feet below finished grade. In addition, no separate payment will be made for the cost of temporary or permanent supporting and/or protecting of any existing utilities within the excavation.

# 6. Construction Stakeout

The Contractor shall retain a surveyor licensed in the state of Maryland to furnish, set and maintain all construction stakeout associated with this project as required to establish proper line and grade for the proposed water mains and interconnections. Survey controls, survey control sketches, and stakeout data for the water main are to be provided upon the Engineer's request to the Contractor. A lump sum payment item is included in the proposal for Construction Stakeout.

Construction Stakeout will not be measured but will be paid for at the Contract lump sum price. The payment will be full compensation for all material, labor, equipment, tools, and incidentals necessary to complete the work. Payment of the Contract lump sum price will be prorated and paid in equal amounts on each monthly estimate. The number of months used for prorating will be the number estimated to complete the work.

## 7. Service Connections

At the beginning of the project, the Contractor shall coordinate with the Engineer to carry out a field survey of all existing water service connections as shown on the Contract Drawings. All existing water service connections which are non-copper including but not limited to lead, galvanized or brass shall be replaced in their entirety from the new service corporation on the new water main to the existing meter vault with copper pipe of like size (min. 3/4 – inch through 2 - inch), or ductile iron pipe of like size (4-inch through 8-inch). Existing meter vaults, frames and covers, and meter settings affected by the renewal of service connections shall be replaced only when directed by the Engineer. Existing water services shall be abandoned. Services may be renewed by either "open-cut" or "trenchless" construction methods. If the existing service from the corporation is copper, the Contractor shall tie into the existing copper as directed by the Engineer. Usually this will be at the closest copper tie-in location.

The costs associated with the abandonment of the existing water mains shall be considered incidental to this work, and shall be at no additional cost to the County. This shall include the abandonment of existing valves and vaults with compacted graded aggregate base (GAB) and surface restoration.

# 8. Sequence of Construction and Valve Shutdowns

A general sequence of operation is shown on the Contract Drawings. The Contractor shall submit a detailed sequence of construction operations for review and approval prior to the start of construction. All water valve closures must be coordinated with Baltimore City Department of Public Works and the City's current designated Contractor (i.e. Wachs Water Services). The Contractor must work with the Inspector and the Baltimore City inspector to complete the valve shutdown request form which is included as part of the Appendices for these Special Provisions.

Only Baltimore City or the City's current designated Contractor (i.e. Wachs Water Services) shall operate valves to shutdown water mains. The Contractor shall submit the "Contractor Shutdown Request Form" as per the instructions in the attached form, at least seven (7) working days in advance of any necessary valve operations.

The Contractor must be aware that the City of Baltimore cannot and will not guarantee a watertight shut down. It may be necessary for excavations to be pumped to maintain a reasonable amount of water, in the excavation, to allow the construction to take place. All costs associated with coordination with the City, Wachs, etc. and pumping/dewatering shall be included in the appropriate bid items, as it will be considered incidental to the work. All chlorinated water pumped out of any excavation must be routed to a sanitary manhole or de-chlorinated for disposal.

## 9. Maintenance of Traffic

The Contractor shall be responsible for the fabrication, installation, and maintenance of all traffic control devices. Said devices shall be in accordance with the Manual on Uniform Control Devices. The Contractor shall also be required to furnish additional signs should conditions warrant at no additional cost to the County. Regarding the control of traffic through the work areas in all Baltimore County roads, the Contractor shall follow the general guidance provided in the Traffic Control Plans included with the contract drawings.

The Contractor shall refer to the Traffic Control Plans, Notes and Details for the locations where night work, or daytime work is allowed and/or required. As stated in the Traffic Control Plans, lane closures in the Baltimore County roads are typically limited only to the hours of 9 AM to 3 PM. However, tie-in work shall be scheduled during night time hours. Contractor may also request to carry out night time work in commercial areas within the project limits. The Engineer will consider such requests in a case by case basis and if applicable approve or disapprove. No additional payment will be made to the Contractor for limited daytime hours, night time hours, or weekend hours.

Once the Contractor has received the Notice-to-Proceed, The Baltimore County Division of Traffic Engineering shall inventory the existing permanent traffic control devices throughout the construction area on Baltimore County roads. Should it be necessary for devices to be removed by Contractor's forces and/or his/her sub-contractor during construction, the Contractor shall be responsible for the storage of these devices. Should they become damaged, defaced, lost, etc. the Contractor will be billed for the replacement of these permanent devices. The Contractor will also be responsible for the re-installation of any permanent devices removed during construction.

The following conditions will apply to the project areas on all Baltimore County roadways during construction:

- a) A minimum single lane of traffic shall be maintained at all times.
- b) At the end of each workday, the Contractor is required to complete the following:
  - i. Backfill and/or plate over all open excavations so that two lanes of traffic are maintained.
  - ii. Remove all equipment and material from the traveled portion of the roadway. All equipment and materials shall be stored in such a manner as to not obstruct sight distance at any driveway or intersecting road.
  - iii. Cover or remove all signs referring to single-lane operation. It may be necessary for the Contractor to provide "STEEL PLATES AHEAD" signs on each approach to the construction area, if appropriate, or as directed by the inspector for the project.
- c) All steel plates must have identification on them.

- d) Within County's Right-of-Way, if steel plates are to be left in any roadway longer than seven (7) calendar days, the steel plates will be recessed as to be flush with the riding surface.
- e) If steel plates are laid side by side for any reason, they shall be tack welded together, as directed by the County Inspector.

All existing driveway access must always be maintained. Access to all businesses shall be maintained during the specific business hours for each one.

Unless otherwise noted and directed by the Engineer, all existing pavement markings shall remain in place during and after construction or it shall be replaced immediately in-kind. This will include both temporary and permanent pavement markings required. All costs associated with temporary markings are to be included in the bid item for Maintenance of Traffic. Permanent pavement markings are to be paid as separate bid items.

All traffic signal systems shall remain in place and operational during and after construction. Baltimore County shall operate and maintain the traffic signals, loop detectors and traffic cameras as required. Care shall be exercised when working adjacent to traffic signal facilities. The Baltimore County office of Traffic Engineering and Transportation Planning having jurisdiction over the traffic signals involved must be notified a minimum of three (3) business days before the start of construction work in order to coordinate any work to be performed near Baltimore County traffic signal facilities. The Contact number for the Baltimore County office of Traffic Engineering and Transportation Planning Section is 410-887-3554. All loop detectors shall be replaced once paving is complete by a qualified Baltimore County traffic signal contractor at no additional cost as this work is considered to be incidental to the item listed for Maintenance of Traffic.

# 10. Payment for Maintenance of Traffic

The Bid Item for Maintenance of Traffic (MOT) shall include all engineering and work which is related to the development and application of Traffic Control Plan(s) as well as all related items of work (including: furnishing, placement, maintenance, removal and relocation of devices and the necessary labor, tools, equipment, and incidentals such as lighting, drums, cones, barricades, STOP/SLOW paddles, flags, vest, and Traffic Manager) for which a specific Bid Item has not been established to ensure the desired result of a safe and efficient work zone area. Temporary traffic signs shall be included in the Bid Item for Maintenance of Traffic. All work associated with the pavement marking plan, removal of existing pavement markings, and temporary/permanent pavement markings shall be included in this Bid Item.

# a) <u>Traffic Manager</u>

The Contractor shall assign the foreman as Traffic Manager for this Contract. The Traffic Manager shall be responsible for properly implementing traffic control devices and for maintenance surveillance on all aspects of traffic control safety as directed by the Engineer and in accordance with the Traffic Control

Plans included with the Contract Drawings and the Maryland Manual on Uniform Traffic Control Devices (MD MUTCD) 2011 Edition and all supplements and revisions.

# 11. Trench and Paving Restoration

Refer to Standard Details G-6 and G-7. A copy of the Complete Authorized Utility Permit must always be on the job site during the performance of all work.

The Contractor shall carry out the following requirements while carrying out the Trench and Paving Restoration:

- Graded Aggregate Base (GAB) shall meet the Baltimore County Standard Specification for Construction and Materials Section 901 "Aggregate".
- Geotextile filter fabric shall be placed between the sub-base material and the GAB. Geotextile filter fabric shall be Class SE as specified in Section 921 "Geotextiles".
- Cold patch will not be allowed on this project, unless authorized by the Engineer.
- Place and compact temporary patching for maintenance of traffic on a daily basis except when otherwise directed to use methods judged reasonable by the Engineer. Give minimal regard to seasonal constraints, recognizing the nature of a temporary patch and its relation to the early restoration of traffic. All temporary repairs shall be maintained at the Contractor's expense until permanent pavement restoration is completed and accepted by the Engineer.
- All costs associated with handling, stockpiling, transporting, placing, and compacting all backfill materials (both GAB and native material around anodes) shall be considered incidental to all appropriate utility bid items in this Contract and no separate payment will be made.
- All costs associated with the furnishing and installation of Aggregate used for maintenance of traffic shall be considered incidental to all appropriate utility bid items in this Contract and no separate payment will be made.
- The Contractor shall obtain written approval from the Engineer prior to beginning any permanent patching.
- If pavement is wet, the Contractor shall work at his/her own discretion on Baltimore County roadways.
- The excavation and the refill required to locate a connection to an existing utility shall be paid for under the Contract Bid price/s for the contingent Test Pit Excavation item/s.
- For temporary trench repair the Contractor shall install Hot Mix Asphalt Superpave 19.0 mm PG64S-22, Level 2 Low ESALs. Depth of temporary repair shall be as shown on the Trench and Pavement Restoration Detail on the Contract Drawings.

- For permanent trench repairs the Contractor shall mill 2" and overlay with 2" of Hot Mix Asphalt Superpave 12.5 mm PG64S-22, Level 2 Low ESALs as shown on the details on Water Sheet No. 14 in the Contract Drawings.
- Asphalt pavement for Temporary Trench Repairs and Permanent Repairs with the Mill and Overlay will be measured and paid for at the Contract unit price per ton. The payment will be full compensation for saw cutting, milling, grinding, removal, disposal, trimming of the existing pavement, subgrade preparation, placing all materials including tack coat, steel plates, emergency filler, and for all material, labor, equipment, tools, and incidentals necessary to complete the work.
- No separate payment will be made for the removal of existing payment markings and placement of temporary payment markings associated with the water work. All costs associated with this work shall be considered incidental to the bid item for Maintenance of Traffic. Permanent payment markings are to be paid as separate bid items.
- Steel plates are considered incidental to any Contract Construction and/or Work and shall not be measured for payment. No payment shall be made to the Contractor for the use or installation of any steel plates and their support system or for any temporary or permanent trench or paving repair/s required by the County that is related to the use of steel plates.
- The County will not pay for saw cutting and removal of existing pavement, subgrade, and/or concrete base material beyond the limits shown on the Contract Documents, as applicable. In addition, there will be no additional payment for GAB material and asphalt pavement due to an increase in the limits of restoration caused by improper use of the Contractor's equipment and/or methods. However, subject to approval by the Engineer, the County will pay for these materials under Contingent Items (as applicable) only when there is no fault and/or or neglect by the Contractor.
- In cases where water service connections cannot be placed by trenchless methods and where any excavation that crosses more than one lane of traffic, the Contractor shall mill and over lay 20 feet on both sides of the trench. In cases where two or more road crossings are within 50 feet or less apart in the existing paved area, the Contractor shall mill and overlay the existing paved surface in a homogeneous area to encompass all such crossings.

## 12. Contingent Bid Items

Bid items that are identified as "Contingent Bid Items" are established for the sole purpose of obtaining unit costs on pay items that may be incorporated into the project. The Engineer shall have sole discretion in determining whether and to what extent such items will be incorporated into the project. The Engineer may order incorporation of such items at any location within the Contract and at any time during the work. Neither the Contractor nor his/her subcontractor shall make claims for additional compensation because of any increase/decrease in quantities, or the complete elimination of such items.

# 13. Contingent Bid Item for Class III Excavation

All existing soil (either suitable or unsuitable) shall be removed to a depth of 4-inches below the pipe invert elevation and be replaced with compacted Graded Aggregate Base (GAB) at no additional cost. This aggregate will not be a pay item. If unsuitable soil needs to be removed at greater depths at the direction of the Engineer, then the Contractor will be paid for Class III Excavation with Selected Backfill and proper disposal of excavated material at an approved offsite location. Class III Excavation with Select Backfill and Proper Offsite Disposal of Unsuitable Material will measured and paid at bid item price per cubic yard of material removed, on a contingent basis as directed by the Engineer.

# 14. Contingent Bid Item for Trench Rock Excavation with Proper Disposal

The Contractor shall consider the presence of rock materials when developing his/her bid prices. For the purposes of classified excavation, trench rock shall be defined as material encountered in trench excavation larger than 1 cubic yard that cannot be excavated in a trench using a Caterpillar Model 325D hydraulic excavator or equivalent with a rock bucket.

There is one (1) geotechnical report provided as part of the Contract Documents. Contractor shall make his/her own interpretation as to the presence of rock based on those reports. Contractor shall include the costs associated with the rock excavation as part of the water installation (as they are considered incidental to the Bid Item) in those areas identified in the Contract Documents. No separate payment will be made for the removal of rock where records indicate the presence of rock.

If the Contractor finds rock, as defined herein, at locations where no reasonable indication for the presence of rock exists as identified by the geotechnical reports, then the excavation, removal and disposal of the rock material will be paid under the Contingent Bid Item.

Trench rock excavation includes up to 6 inches over-excavation below the required excavation depth. Rock shall be quantified by measuring the extent of rock in the trench, not by measuring the volume of removed rock. This definition of trench rock does not include materials such as hardpan, loose rock, concrete or other materials that can be removed by means other than drilling and blasting, but which for reasons of economy in excavating the Contractor chooses to remove by drilling and blasting. In any event, the work will be performed only upon the written direction of the Engineer.

Trench Rock Excavation with Proper Disposal (Contingent) will measured and paid at the contingent bid item price per cubic yard of material removed and disposed of, on a contingent basis. Payment will be full compensation for material, equipment, and work

required for drilling, blasting, excavating, loading, hauling, and disposal of the rock material.

# 15. Estimated Quantities

With the exception of those items identified as "Contingent" Bid Items, the quantities shown for all unit bid items are based upon the best information at the time of bidding and are established for the purpose of obtaining a bid price. The quantities for all items may be increased or decreased or eliminated without any adjustments to the Contract unit price bid and shall not be considered as a basis of claim by the Contractor against Baltimore County resulting from any quantity changes.

# 16. Acceptable Resilient Wedge Gate Valves 4-inch through 12-inch

Manufacturer	Valve
American Flow	Series 2500
Kennedy Valve Co.	Ken-Seal NRS
M&H	Style 4067 NRS
Mueller	A-2361 Model
U.S. Pipe	A-USP2 NRS
Clow	F 6100 Series

# 17. Number of turns and orientation for Resilient Wedge Gate Valves

Valve Size	Number of Turns
4, 6, 8, 10 and 12-inches (Vertical)	Three (3) times the nominal diameter plus
	three (3) turns

# 18. Acceptable Coupling Manufacturers:

a) Krausz USA Hymax® Coupling (6"-12")

b) Mueller Co. MaxiFit – MFC Coupling (4"-12")

c) Smith-Blair, Inc. Quantum – 461 Series Coupling (4"-12")

# 19. Removal and Replacement of Concrete Sidewalk & Curb and Gutter

Concrete sidewalks & curbs and gutters shall be removed to the nearest contraction or expansion joint. Care shall be used to avoid damage to sidewalks & curbs and gutters that are to remain in place. All new concrete shall tie-in to the nearest joint or as directed by the Engineer.

Concrete sidewalks shall be replaced with the same material, construction, and finish as the originals. All disturbed sections shall be replaced in their entirety to the nearest joint. Any expansion joint material removed shall be replaced at the original locations. Existing concrete edges shall be cleaned prior to placement of concrete. The finished concrete elevation, texture, and color shall conform to the adjacent concrete surfaces.

Unless otherwise directed, curb and gutter shall be replaced with new concrete curb and gutter of the same cross-section and at the same top of curb elevation and flow line as that removed. Any expansion joint material removed shall be replaced at the original locations. Existing concrete edges shall be cleaned prior to placement of concrete. The finished curb

and gutter cross-section, elevations, texture, and color shall conform to the adjacent concrete surfaces.

Removal and replacement of concrete sidewalk will be measured for payment by the square foot, complete in place. Removal and replacement of concrete curb and gutter will be measured for payment by the linear foot, complete in place.

Sidewalk removal and replacement will be paid for at the contract unit price per square foot, which price will be full compensation for removal and disposal of existing concrete sidewalk; preparing the subgrade; and placing, finishing, curing and protection of concrete, complete in place.

Removal and Replacement of Concrete Curb and Gutter will be measured for payment by the linear foot, complete in place. Curb and gutter removal and replacement will be paid for at the contract unit price per linear foot, which price will be full compensation for removal and disposal of existing concrete curb and gutter; preparing the subgrade; and placing, finishing, curing and protection of concrete, complete in place.

# 20. Non-Detectable Tape for Restrained Joint Pipe

On all new ductile iron pipe with restrained joints, including any 6" hydrant lead line, the Contractor shall install new non-detectable tape on the top of pipe and in accordance with the following specifications and requirements. The Contractor must submit the shop drawings for approval prior to ordering.

All costs associated with the furnishing and installation of such non-detectable tape shall be considered incidental to all appropriate utility bid items in this Contract and no separate payment will be made.

# Restrained Joint Pipe Tape

# a) Description

- i. Material: Non-detectable type, low density, virgin grade polyethylene, acid and alkali resistant; minimum wetting tension: 35 dynes/cm, ASTM D2578.
- ii. Tape size: 6-inch width, 4 mils thickness.
- iii. Printing: Two lines with minimum 1-inch height letters with "No-Dig Symbol" following each cycle of text.
  - 1. First Line: "CAUTION-RESTRAINED JOINT PIPE" repeated every 20 to 24 inches.
  - 2. Second line: "CALL DPW AT 410-396-7870."

#### iv. Colors:

- 1. Tape: APWA Red.
- 2. Lettering: Permanent Black.

# b) Approved manufacturers:

i. Empire Level Manufacturing Corporation, Utility Products Division, Shieldtec Underground Warning Tape.

- ii. Blackburn Manufacturing Co., Inc., Non-Detectable Underground Utility Warning Tape.
- iii. Reef Industries Inc., Terra Tape Standard Non-Detectable.
- iv. Mutual Industries, Non-Detectable Underground Marking Tape.
- v. Pro-line Safety Products (A Division of Pro-Pak Ind., Inc.), Standard Non-Detectable.
- vi. Or Approved Equal.

# 21. Connections

The Contractor shall make connections to existing work when and as directed by the Engineer. Upon being notified by the Engineer, the Contractor shall notify the consumers in the area to be affected by the shut-off. Baltimore City forces shall operate all valves involved in the work. The Contractor must complete the connections with the greatest possible speed in order to minimize public inconvenience. When the Contract Documents require that connections be made at night and/or during the weekend, the costs to make such connections shall be included in the original Price Bid and no additional compensation will be provided. If the Contractor must remove existing buttresses in order to make connections, he/she shall do this work without additional compensation.

# 22. Buttresses, Anchorages and Thrust Blocks

Where restrained joints are not used, place buttresses behind all caps, horizontal bends and branches unless otherwise directed by the Engineer. Anchorages shall be placed beneath vertical bends. Buttresses, anchorages, and thrust blocks must be of concrete and steel, as required. Extend them to solid, undisturbed soil and construct in accordance with the Standard Details or as shown on the Contract Drawings.

The Contractor shall coat bare steel shapes, plates, and bars with two (2) coats of heavy mastic containing synthetic elastomeric additives in a mixed solvent. The mastic shall bond firmly to dry, clean and contaminant-free steel surfaces (to be wire brushed before coating) without the use of a primer; shall have high electrical resistance; and shall be totally resistant to aliphatic hydrocarbons. Apply the first coat of mastic to a dry film thickness of 10-12 mils. Allow this coat to dry for one hour, or until it is dry to the touch. Apply a second coat to the same dry coat thickness as the first. Backfill only after the second coat is dry to the touch.

# 23. Soil Borings

The Engineer has conducted subsurface test borings in the area where the work will be performed. Resultant data obtained from these borings along with the full geotechnical evaluation report is included as part of the Appendices for these Special Provisions.

It shall be understood that this information was obtained and prepared for design purposes and is not guaranteed to be more than a general indication of the material likely to be found adjacent to the bore holes, and that the County does not warrant that material encountered beneath the ground surface is homogenous or uniform. This report is for informational purposes only and shall not be considered as part of the contract documents. The data in this report may not be adequate for the Contractor's estimating purposes. All bidders are advised to independently evaluate, or to have the data and interpretations independently evaluated by someone qualified in this technical field before using for bidding purposes because the bidder is solely responsible for this evaluation. Conclusions and recommendations included in the geotechnical information are not intended to restrict the Contractor from selecting the methods for dewatering, excavating, removal of rock, refill and compaction and/or sheeting and shoring. The Contractor is solely responsible for selecting/utilizing the appropriate methods for this work.

Bidders shall determine to their own satisfaction the actual subsurface conditions including the character and type of soil, rock and other material he/she will encounter in the conduct of the work at no additional cost to the County. Information and data, and any reference to information and data, in these Contract Documents are available for the Contractor's information and for whatever use the Contractor may find therefore. The subsurface and other physical data, such as those mentioned herein and contained in the Contract Documents, or otherwise made available to the Contractor by the Engineer, are not intended as representations or warranties. It is expressly understood that neither the County nor the Engineer will be responsible for the completeness or accuracy thereof, or for any deductions, interpretations, or conclusions drawn thereof.

# 24. Existing Utilities

All known subsurface lines, pipes, conduits, and structures are shown on the Contract Drawings. These utilities are shown based upon the best available plans and maps. The locations have not all been verified by test pits and Baltimore County assumes no responsibility for the accuracy of the Contract Drawings. In any area where the Contractor must make connections to or cross existing subsurface facilities, it shall be his/her responsibility to test pit the utilities and verify the locations, sizes, clearances and elevations to his/her satisfaction. In the event that utilities are not found located as shown on the Contract Drawings, the Contractor shall notify the Engineer so that an evaluation can be made as to the magnitude and methods of any adjustments on the Contract Drawings. The Test Pit reports are included as part of the Appendices for these Special Provisions as information only, subject to field verification by the Contractor.

The Contractor shall be solely responsible for all damage to underground and aboveground utilities encountered in any manner during construction. When crossing and working near existing utilities, it shall be the Contractor's responsibility to properly support and maintain the operation of the utilities. Extreme care shall be exercised in excavation and backfill operations. The Contractor shall correct at his own expense all damage caused to existing utilities.

The Engineer may direct placement of additional fittings in addition to those shown on the Contract Drawings as required to avoid existing utilities or obstructions encountered when

opening the trench. Compensation for this work will be paid under the appropriate contingent bid items listed for each fitting. Restrained joints shall be included in these items. These items are for 45 degree bends, 22.5 degree bends, other degree bends, offset fittings, etc. which may become necessary to complete the installation.

# 25. Certification of Materials and Installations

The Contractor shall furnish certification for the following items:

- a) Gate valves
- b) Fire hydrants
- c) Pipeline Coating and/or wrapping

Certification shall be provided from each manufacturer, or from an approved testing laboratory, that all material used in the work is in accordance with these and all referenced specifications.

# 26. Existing Water Service Connection Pipe Materials

The Contractor shall document the existing pipe material (i.e. lead, galvanized steel, pvc, etc.) for all water service connections on the final as-built drawings. This work will be considered incidental to the preparation of the as-built documents.

# CATEGORY 300 DRAINAGE

# **SECTION 302 – SELECTED BACKFILL**

## 302.04 MEASUREMENT AND PAYMENT.

**INSERT:** The following:

Geotextile fabric for each type will be measured and paid for at the Contract unit price per square yard. Overlaps and seams will not be measured for separate payment. The accepted quantity of geotextile will be paid for at the contract unit price per square yard, which price shall be full compensation for furnishing, placing, lapping, or seaming material and for all materials, labor, tools, equipment, and incidentals necessary to complete the work.

# CATEGORY 300 DRAINAGE

# **SECTION 308 – EROSION AND SEDIMENT CONTROL**

## 308.04 MEASUREMENT AND PAYMENT.

**INSERT:** The Following:

**308.04.21** *Portable Sediment Tank* will be measured and paid for at the Contract unit price per each. The payment will also include pipe, geotextile, wire mesh, steel plate, hose, pump, and connections. No adjustments will be made for resizing or relocating portable sediment tanks to meet stream clarity discharge requirements.

**308.04.22** *Inlet Protection* will be measured and paid for at the Contract unit price per each.

# CATEGORY 300 DRAINAGE & UTILITY CONSTRUCTION

# **SECTION 351 – WATER MAIN CONSTRUCTION**

# **ADD** the following to section **351.04 MEASUREMENT AND PAYMENT**:

Concrete encasement of existing sanitary sewers (as shown on the Drawings) shall be paid for under the Item listed for contingent **Mix No. 1 Concrete for Miscellaneous Structures**. Price shall include excavation, backfill and compaction, dewatering, shoring/support of the existing sanitary sewer, formwork, concrete, finishing, restoration and all work necessary for the encasement of the existing sanitary sewer/s.

Furnishing and installation of Graded Aggregate Base (GAB) shall not be measured separately but will be considered incidental to the appropriate utility bid items in this Contract.

Restoration of the surface shall be paid under the items bid for seed and mulch, bituminous concrete for temporary trench repair, hot mix asphalt surface SF, concrete sidewalk, etc. as applicable.

Furnishing and installation of all corrosion components and full cathodic protection (as specified in Section 372) for new ductile iron pipe and fittings shall not be measured separately but will be considered incidental to the appropriate ductile iron pipe bid items in this Contract.

Page 1 of 1

# CATEGORY 300 DRAINAGE & UTILITY CONSTRUCTION

# SECTION 353 – WATER HOUSE SERVICE, WATER METER SETTING, AND VAULTS

ADD the following to section 353.01 DESCRIPTION.

All existing service connections that are currently served from the existing water main in Back River Neck Road (and side streets) shall be replaced from the new replacement water main to the existing meter boxes. The Engineer on the job site will determine whether to use the existing meter vault or replace it, depending on its condition.

# CATEGORY 300 DRAINAGE & UTILITY CONSTRUCTION

# **INSERT:** The following:

## **SECTION 372 - CORROSION CONTROL**

## **PART 1 - GENERAL**

#### 1.01 DESCRIPTION

- A. Installation of corrosion control components shall be in accordance with the following specifications and the details contained in the Contract Documents. All installation practices and components shall be approved by the Engineer.
- B. The corrosion control for all ductile iron pipe (this includes all piping, joints, valves, fittings, etc.) will include an external protective coating in accordance with the below specifications, electrical continuity (joint bonding), electrical isolation (insulating flanges, insulating couplings, linked rubber seals, and insulating corporation valves), sacrificial (magnesium) prepackaged anodes, and corrosion control test facilities.
- C. Upon completion of the work, the Engineer shall test, operate, inspect, and survey the installed work. Any and all repairs or replacement of defective or improperly installed corrosion control/corrosion monitoring systems shall be corrected by the Contractor at no additional cost to the Owner.

## 1.02 REFERENCES

The following is a list of the Standards referenced in this Section.

- A. American Society for Testing and Materials (ASTM)
  - 1. ASTM A48: Specification for Gray Iron Castings
  - 2. ASTM D149: Test Method for Dielectric Breakdown Voltage and Dielectric Strength of Solid Electrical Insulating Materials at Commercial Power Frequencies
  - 3. ASTM D257: Test Methods for D-C Resistance or Conductance of Insulating Materials
  - 4. ASTM D471: Test Methods for Rubber Property-Effect of Liquids
  - 5. ASTM D570: Test Method for Water Absorption of Plastics

- 6. ASTM D638: Test Method for Tensile Properties of Plastics
- 7. ASTM D1000: Test Methods for Pressure-Sensitive Adhesive-Coated Tapes
  Used for Electrical and Electronic Applications
- 8. ASTM D1505: Test Method for Density of Plastics by the Density-Gradient Technique
- 9. ASTM D4542: Test Method for Pull-Off Strength of Coatings Using Portable Adhesion Testers
- 10. ASTM E96: Test Methods for Water Vapor Transmission of Materials
- 11. ASTM F1249: Test Method for Water Vapor Transmission Rate Through Plastic Film and Sheeting Using a Modulated Infrared Sensor
- 12. ASTM G8: Test Method for Cathodic Disbonding of Pipeline Coatings
- 13. ASTM G14: Test Method for Impact Resistance of Pipeline Coatings (Falling Weight Test)
- 14. ASTN G17: Test Method for Penetration Resistance of Pipeline Coatings (Blunt Rod)
- 15. ASTM G95: Test Method for Cathodic Disbonding of Pipeline Coatings (Attached Cell Method)
- B. Society for Protective Coatings (SSPC)
  - 1. SSPC SP3: Surface Preparation Specification No. 3, Power Tool Cleaning
  - 1. SSPC SP5: Surface Preparation Specification No. 5, White Metal Blast Cleaning
- C. NACE International (NACE)
  - 1. RP0274: High-Voltage Electrical Inspection of Pipeline Coatings Prior to Installation
  - 2. SP0169: Control of External Corrosion of Underground or Submerged Metallic Piping Systems
  - 3. SP0188: Discontinuity (Holiday) Testing of Protective Coatings
- D. American Water Works Association (AWWA)

- 1. AWWA C209: Cold-Applied Tape Coating for the Exterior of Special
  - Sections, Connections, and Fittings for Steel Water Pipelines
- 2. AWWA C210: Liquid-Epoxy Coating Systems for the Interior and Exterior of Steel Water Pipelines
- 2. AWWA C214: Tape Coating Systems for the Exterior of Steel Water Pipelines
- 3. AWWA C216: Heat-Shrinkable Cross-Linked Polyolefin Coatings for the Exterior of Special Sections, Connections, and Fittings for Steel Water Pipelines
- 4. AWWA C222: Polyurethane Coatings for the Interior and Exterior of Steel Water Pipe and Fittings
- E. NSF International
  - 1. NSF 61 Drinking Water System Components Health Effects
- F. US Department of Transportation
  - 1. US DOT H-20: Roadway Delineation Practices Handbook

## 1.03 SUBMITTALS

- A. Catalog cuts of all materials to be installed shall be required and shall be submitted for approval.
- B. Pipe and casing pipe coating, handling and testing procedures, and quality assurance procedures shall be required and shall be submitted for approval.
- C. Test procedures for verifying electrical isolation at insulating flanges and insulating corporation valves shall be required and submitted for approval.

# 1.04 DOCUMENTATION OF CATHODICALLY PROTECTED WATER MAIN INSTALLATION

A. For this project the corrosion control for all ductile iron pipe (this includes all piping, joints, valves, fittings, etc.) will include an external protective coating in accordance with the specifications, electrical continuity (joint bonding), electrical isolation (insulating flanges, linked rubber seals, and insulating corporation valves), sacrificial (magnesium) prepackaged anodes, sacrificial zinc ribbon anodes, and corrosion control test facilities.

- B. It is important for the County to ensure that new cathodically protected water mains and service lines are constructed in strict accordance with the requirements and practices specified in the Contract Documents and as approved by the Engineer. Even small variations between the execution of the work and that which is specified could have detrimental effects on the cathodic protection system's ability to perform its designed function.
- C. Before any work is performed, the Contractor shall schedule a demonstration session of all cathodic protection practices to be implemented while executing the work. The demonstration session shall be scheduled during regular office hours and must include the personnel responsible for the work as assigned by the Contractor. All installation practices and components shall be witnessed, and approved by the Engineer and his/her designated representative. The demonstration session shall go over but not be limited to the following:
  - 1. Hoisting of pipe
  - 2. Holiday testing,
  - 3. Coating repair in pipe body,
  - 4. Bell and spigot joint field coating,
  - 5. Mechanical joint field coating,
  - 6. Insulating flange field coating,
  - 7. Polyethylene mesh separator pad,
  - 8. Thermite welds,
  - 9. <= 2-inches service connection coating,
  - 10. Insulating flange and insulating corporation electrical insulation test
- D. To verify that cathodically protected water mains have been properly installed, color photographs shall be taken by the Contractor to document the installation of cathodically protected water mains prior to backfilling operations. Each element shall have corresponding station marked up with light or dark colored crayon as applicable.

Separate photographs shall be provided for each of the following:

- 1. Push-on Joints:
  - a. One image taken above the joint after application of primer and filler material before application of first layer of tape and before installation of bond cables
  - b. One image taken below the joint after application of primer and filler material before application of first layer of tape and before installation of bond cables
  - c. Two images for each side of the joint after application of primer and filler material before application of first layer of tape and before installation of bond cables
  - d. One image taken above the coated joint complete with bond cables
  - e. One image taken below the coated joint complete with bond cables
  - f. Two images for each side of the coated joint complete with bond cables

#### 2. Mechanical Joints:

- a. One image taken above the joint after application of primer and filler material before application of first layer of tape and before installation of bond cables
- b. One image taken below the joint after application of primer and filler material before application of first layer of tape and before installation of bond cables
- c. Two images for each side of the joint after application of primer and filler material before application of first layer of tape and before installation of bond cables
- d. One image taken above the coated joint complete with bond cables
- e. One image taken below the coated joint complete with bond cables
- f. Two images for each side of the coated joint complete with bond cables

# 3. Flange Insulating Joints:

- a. One image taken above the joint after application of primer and filler material before application of first layer of tape and before installation of bond cables
- b. One image taken below the joint after application of primer and filler material before application of first layer of tape and before installation of bond cables
- c. Two images for each side of the joint after application of primer and filler material before application of first layer of tape and before installation of bond cables
- d. One image taken above the coated joint complete with bond cables
- e. One image taken below the coated joint complete with bond cables
- f. Two images for each side of the coated joint complete with bond cables

# 4. Service Connections (\*= 2-inches):

- a. One image taken above the service connection after application of primer and filler material and before application of first layer of tape
- b. One image taken below the service connection after application of primer and filler material and before application of first layer of tape
- c. Two images, one for each side of the service connection after application of primer and filler material and before application of first layer of tape
- d. One image taken above the coated service connection
- e. One image taken below the coated service connection
- f. Two images, one for each side of the coated service connection

## 5. Appurtenances:

- a. One image taken above the appurtenance after application of primer and filler material and before application of first layer of tape
- b. One image taken below the appurtenance after application of primer and filler material and before application of first layer of tape
- c. Two images, one for each side of the appurtenance after application of primer and filler material and before application of first layer of tape
- d. One image taken above the appurtenance complete with bond cables
- e. One image taken below the appurtenance complete with bond cables
- f. Two images for each side of the appurtenance complete with bond cables

# 6. Test Stations:

a. Two images showing the location of the test station as installed. One from above and the second one from a distance away that allows viewing of proximity features.

#### 7. Anode Stations:

a. Four images showing the location of the anodes and electrodes as installed to include the weld points to main.

#### 8. Structures:

- a. One image taken from above the structure showing the piping arrangement within the structure.
- b. Two images for each of the penetrations where the water main enters the structure.

Additionally, photographs shall be taken at 40-foot intervals (maximum) along pipe centerline (upstream or downstream) showing the progression of pipe laying operations immediately prior to backfilling.

In the event the photographs depict improper installation and/or a damaged coating, or missing images are not identified the Engineer will direct the Contractor to carry out repairs at the identified locations at no additional cost to the County.

Contract shall provide photographs as cut and paste files onto a Word document (maximum 4 images to a page). Digital photography shall be 2.1-megapixel density or greater. Contractor shall save digital page files in PDF format. On each page of photos, provide the following information:

- 1. Name of Project
- 2. Submittal Sequential Numbering (i.e. 20001 WX0 DWI 0001, 2000 I WX0 DWI 0002, etc.)
- 3. Station Range (water centerline stationing)
- 4. Orientation of View
- 5. Date & Time image was taken: unless otherwise indicated, date and time stamp each photograph as it is being taken so stamp is integral to photograph
- 6. Service size, station, and address (when applicable)
- 7. Type of appurtenance and station (when applicable)
- 8. Type of Fitting and station (when applicable)
- 9. Type of Joint and station (when applicable)
- 10. Name of individual who took photograph

<u>Frequency:</u> The Contractor shall take photographs daily while water line work is being carried out, with a cutoff date associated with each application for payment. No

payment will be processed without the submittal of applicable progress photographs for the corresponding period. Along each respective Application for Payment, the Contractor shall submit the following to the inspector:

- 1. A complete set of digital image electronic files of the Progress Record Documentation (PRD) on a CD-ROM corresponding for the payment period, identifying the electronic media with date photographs. (i.e. PRD 06.01.20 thru 06.30.20)
- 2. Two hard copies of files bound in two (2) 3-in three-ring binders each printout inside three-holed plastic sleeves.

<u>Measurement and Payment:</u> There will be no separate measurement or payment for the Documentation of Water Main Installation. The cost will be incidental and shall be included in the unit prices bid per linear foot of the various sizes of pipe laid as provided for in the Bid Schedule for this Contract.

#### PART 2 - EXTERNAL COATING SYSTEMS FOR DUCTILE IRON PIPE

#### 2.01 GENERAL

- A. External pipe surfaces (including all piping, joints, valves, fittings, hydrant piping, etc.) shall be coated. Predominant method to be shop application. The piping shall receive an exterior coating in the pipe manufacturer's shop or at a separate applicator's facility.
- B. All components of the coating system shall be manufactured by a single supplier to assure compatibility of individual components.
- C. Field applied coatings to be limited to repairing damage to shop coating; coating exposed metal at joints, fittings, valves, bond and test wire connections; and other appurtenances that are not shop coated.
- D. Extent of piping to be shop coated and extent to be field coated shall be clearly identified in Contractor's material and quality assurance submittals. Quality assurance submittals shall include pipe coating, handling and testing procedures.
- E. All coatings used on project shall be as specified herein, unless otherwise approved by the Engineer prior to bidding. All products comprising completed coating system to be compatible and the same products to be used throughout the project. Pipe surfaces that will come in contact with potable water inside the pipeline (e.g. spigot ends of bell and spigot joints) to be coated with materials having NSF-61 certification.

#### 2.02 SHOP APPLIED MATERIALS FOR DUCTILE IRON PIPE

The external coating for ductile iron pipe shall comply with one of the following coating systems:

- A. 100 percent solids polyurethane, with the following minimum properties, or approved equal:
  - 1. Adhesion to steel (SSPC SP5): 1,300 to 1,800 psi.
  - 2. Cathodic disbondment (ASTM G8 or G95): <10 mm rad.
  - 3. Resistivity:  $1 \times 10^{14}$  ohms per cm<sup>2</sup> minimum.
  - 4. Dielectric strength (ASTM D149): > 200 volts per mil.
  - 5. Water Absorption (ASTM D471): < 3% (no absorption below surface).
  - 6. Solids Content (Solids by Volume): 99%.
  - 7. Volatile Organic Compounds (VOC's): 0.08 lbs. per US gallon.
  - 8. Final coating shall have a nominal dry film thickness of 35 mils with a minimum dry film thickness of 30 mils.
  - 9. Coating shall be Corropipe II TX-15 as manufactured by Madison Chemical Industries or approved equal.
- B. Three-layer tape wrap system with the following minimum properties, or approved equal:
  - 1. Primer: A liquid primer composed of butyl, tackifiers, and other ingredients to protect against soil oxidation and bacteria growth. Total solids shall be 20% (plus or minus 2%) by weight.
  - 2. Innerwrap: A two component extruded black tape consisting of polyethylene and butyl rubber adhesive specially designed to conform to the particular pipe material being coated. The innerwrap shall have the following properties:
    - a. Thickness: 20 mils (9 mils polyethylene backing, 11 mils butyl rubber adhesive).
    - b. Adhesion to primed steel: 20 oz/in width (ASTM D1000).
    - c. Tensile strength: 30 lbs./in width (ASTM D1000).
    - d. Water vapor transmission rate: <0.2 gm/100 in<sup>2</sup>/24 hr.
    - e. Dielectric strength: 21 kV (ASTM D149).
    - f. Insulation resistance: 1,000,000 M Ohms (ASTM D257).
    - g. Tape width: As recommended by coating manufacturer.
  - 3. Middlewrap: A two component extruded grey tape consisting of polyethylene and butyl rubber adhesive. The middlewrap shall contain stabilizers and

inhibitors to resist the destructive effects of ultra-violet light. The middlewrap shall have the following properties:

- a. Thickness: 30 mils (25 mils polyethylene backing, 5 mils butyl rubber adhesive).
- b. Adhesion to backing: 45 oz/in width.
- c. Tensile strength: 60 lbs./in width (ASTM D1000).
- d. Abrasion resistance: Excellent (ASTM D1000).
- e. Water vapor transmission rate:  $<0.2 \text{ gm}/100 \text{ in}^2/24 \text{ hr}$ .
- f. Dielectric strength: 23 kV (ASTM D149).
- g. Insulation resistance: 1,000,000 M Ohms (ASTM D257).
- h. Tape width: As recommended by coating manufacturer.
- 4. Outerwrap: A two component extruded white tape consisting of polyethylene and butyl rubber adhesive. The outerwrap shall contain stabilizers and inhibitors to resist the destructive effects of ultra-violet light. The outerwrap shall have the following properties:
  - a. Thickness: 30 mils (25 mils polyethylene backing, 5 mils butyl rubber adhesive).
  - b. Adhesion to backing: 45 oz/in width.
  - c. Tensile strength: 60 lbs./in width (ASTM D1000).
  - d. Abrasion resistance: Excellent (ASTM D1000).
  - e. Water vapor transmission rate:  $<0.2 \text{ gm}/100 \text{ in}^2/24 \text{ hr}$ .
  - f. Dielectric strength: 23 kV (ASTM D149).
  - g. Insulation resistance: 1,000,000 M Ohms (ASTM D257).
  - h. Tape width: As recommended by coating manufacturer.
- 5. Coating system shall be YGIII as manufactured by Polyken Technologies or approved equal.
- C. Polyolefin (extruded butyl rubber adhesive with polyethylene top coat) system with the following minimum properties, or approved equal:
  - 1. Compounded butyl rubber adhesive coating with less than 0.1% water absorption. Nominal thickness 10 mils.
  - 2. Top coat: High density polyethylene resin top coat that is spirally extruded onto adhesive coating in multiple layers to form a seamless bonded coating. The polyethylene top coat shall have the following properties:
    - a. Nominal thickness: 40 mils.
    - b. Density: >0.95 (ASTM D1505).
    - c. Elongation: >600% (ASTM D638).
    - d. Tensile strength: <2800 psi (ASTM D638).
  - 3. Total coating system shall have the following properties:

- a. Thickness: 50 mils (40 mils polyethylene top coat, 10 mils butyl rubber adhesive).
- b. Impact resistance: >60 inch lbs. (ASTM G14).
- c. Cathodic disbondment: 6 mm radius (ASTM G8 OR G95).
- d. Water absorption: 0.06% (ASTM D570).
- 4. Coating system shall be Pritec as manufactured by Bredero Price Company or approved equal.

#### 2.03 APPLICATION OF SHOP APPLIED MATERIALS TO DUCTILE IRON PIPE

The coating applicator, regardless of the location where the coating is applied, shall be certified as qualified by the coating manufacturer. The coating applicator must abide by and follow all manufacturer's application specifications for the coating system. All components of the coating system shall be manufactured by a single supplier to assure compatibility of individual components.

#### 2.04 SURFACE PREPARATION PRIOR TO COATING

The exterior surface of the piping shall be cleaned in accordance with the coating manufacturer's recommendations.

#### 2.05 CERTIFICATION OF EXTERNAL COATING

The pipe or fitting manufacturer or coating applicators, as appropriate, will test and certify the exterior coating prior to shipping to the project site. When the pipe or fitting arrives at the job site, the Contractor shall visually inspect the pipe or fitting, and repair any and all damage as directed by the coating manufacturer and in accordance with these specifications.

#### 2.06 INSPECTION OF EXTERNAL COATING

- A. Immediately prior to installation of the pipe or fitting, the Contractor shall perform ALL of the following:
  - 1. Step One Visually inspect all exterior coatings on pipe, fittings, specials, and closures for holidays and other defects.
  - 2. Step Two All visual holidays and defects if any, shall be repaired by the Contractor as directed by the coating manufacturer and in accordance with this specification and to the satisfaction of the Engineer.
  - 3. Step Three The coating must be tested, REGARDLESS if there are no visual defects, with a holiday detector by the Contractor. This electrical holiday test shall be in accordance with NACE RP0274 or SP0188 as recommended by the coating manufacturer and must be witnessed by the

County Inspector. Holiday detectors shall be manufactured by Tinker and Razor or approved equal.

- 4. Step Four If any holidays are detected by the required holiday test than they shall be immediately repaired as mentioned in step two.
- 5. Step Five Repeat the holiday test after the coating is repaired.
- 6. Step Six Repeat step four and five until there are no holidays detected. Enter in a log that this pipe has successfully passed the holiday test on the date and time it was successfully performed. Each pipe should be assigned a number that corresponds to the stationing on this project. The County Inspector must approve the successful holiday testing and sign off on the log sheet.
- 7. Step Seven Once the coating on the pipe or fitting is free of holidays and the Holiday Testing Log has been signed off by the County Inspector, the piping or fitting may be installed in the trench.
- B. In addition, the County Inspector at any time after the pipe has passed the above required holiday testing, may order additional holiday testing should he suspect or visually see defects in the coating caused by the actions of the Contractor during the handling or installation of the pipeline.
- C. The Contractor shall ensure that he coordinates with the County Inspector to complete the Holiday Detection Daily Field Report for each segment of pipe to be tested. Failure to do so may result in the stoppage of the Work. The Holiday Detection Daily Field Report is included at the end of this Section.
- D. All costs associated with holiday testing shall be incidental and be included in the unit price bid for each sized pipeline.

#### 2.07 FIELD APPLIED MATERIALS FOR COATING REPAIRS

Shop applied coatings that are damaged in transit or during handling shall be repaired prior to backfilling. The field applied repair coatings shall be as recommended by the shop applied coating manufacturer and shall be entirely compatible with the original coating system. The field coating repairs shall be performed in accordance with all recommendations of the coating manufacturer.

#### 2.08 FIELD APPLIED MATERIALS FOR COATING DUCTILE IRON PIPE JOINTS

- A. Joint Wrap and Repair Tape: A two component extruded tape consisting of polyethylene and butyl rubber adhesive in accordance with AWWA C209. The tape shall contain stabilizers and inhibitors to resist the destructive effects of ultra-violet light. The joint wrap and repair tape shall have the following properties:
  - 1. Thickness: 35 mils (6 mils polyethylene backing, 29 mils butyl rubber adhesive).
  - 2. Adhesion: 12 lb-ft/in width (ASTM D1000).
  - 3. Tensile strength: 27 lbs./in width (ASTM D1000).
  - 4. Water vapor transmission rate:  $<0.2 \text{ gm}/100 \text{ in}^2/24 \text{ hr}$ .
  - 5. Dielectric strength: 26 kV (ASTM D149).
  - 6. Insulation resistance: 1,000,000 M Ohms (ASTM D257).
  - 7. Tape width: As recommended by the coating manufacturer.

#### 2.09 PROTECTION OF COATING SYSTEMS DURING CONSTRUCTION

- A. At all times during construction of the pipeline, the Contractor shall take every precaution to prevent damage to the protective coating. No metal tools or heavy objects shall be permitted to come into contact unnecessarily with the finished coating. Workmen shall not be permitted to walk on the coating, except when absolutely necessary and approved by the Engineer, in which case, they shall wear shoes with rubber or composition soles and heels or other suitable footwear which will not damage the coating.
- B. Externally coated pipe shall be hoisted from the trench side to the trench by means of a minimum of two 18-inch wide belt slings of sufficient strength to handle the weight of the piping safely.
- C. Any and all coating damage shall be repaired with specified coating repair materials prior to installation.

#### 2.10 TRANSPORTATION, HANDLING AND STORAGE OF COATED PIPE

A. Pipe shall be handled in accordance with AWWA C214 and in such a manner as to protect the pipe and the coating from damage.

- B. At the pipe coating plant, if forklifts are used, all bearing surfaces of a forklift apparatus shall be padded with suitable padding material. Web slings may also be used at the pipe manufacturer's plant.
- C. At the project site, the pipe shall only be handled with slings. Metal chains, cables, tongs, forklifts or other equipment likely to cause damage to the coating, will not be permitted. Web slings shall be a type that will not damage the coating. When pipe is handled with slings, there shall be a minimum of two slings. Slings shall be a minimum of 18 inches wide and of sufficient strength to handle the weight of the pipe safely. Slings shall not pass through the pipe. Hooks on the end of the pipe shall not be allowed. Handling equipment, materials, and procedures shall be submitted to the Engineer for approval. If possible, the pipe should be handled from cutback ends.
- D. Storing of the coated pipe shall be on padded 12-inch wide (minimum) skids or select loamy or sand dirt berms, or suspended from cutback ends, where possible. In urban areas, the pipe shall be suspended on padded skids or skids placed at cutback areas. Where skid chucks are used in contact with coated pipe, they shall be padded with several layers of carpeting. Padded chucks shall be placed such that coated pipe is nested on the skid rather than the chuck. Coated pipe shall not be laid on pavement without benefit of padding at contact points. In preparation for transporting pipe, the use of web slings is necessary for tie downs.
- E. If cables or chains are used during transportation, they shall be properly padded with approved, suitable material as required to protect the coating from damage while in transit. Use of a padded horizontal separator strip between successive rows of pipe is necessary to prevent damage to the pipe coating, i.e.: strips of rug material over all contact areas where pipe will rest.

#### PART 3 – CORROSION CONTROL MATERIALS

#### 3.01 PREPACKAGED MAGNESIUM ANODES

- A. Each anode shall have a nominal weight of 20 pounds, excluding backfill. The anode shall be 56.75 inches long by 2.75 inches wide by 2.75 inches high.
- B. Composition of the anode shall be as follows:

Aluminum 0.010% Maximum Manganese 0.50 to 1.30% Copper 0.02% Maximum Nickel 0.001% Maximum Iron 0.03% Maximum Silicon 0.05% Maximum 0.05% Each Other Remainder Magnesium

- C. The 20-pound anodes shall be vibratory packaged in permeable cardboard boxes that shall be 71 inches long by 4.5 inches wide by 4.5 inches tall.
- D. The cardboard box shall contain a minimum of 45 pounds of backfill for 20-pound anodes. The backfill material shall have the following composition:

Hydrated Gypsum 75% Bentonite 20% Sodium Sulfate 5%

E. The anode and backfill shall be prepackaged into a single unit, in a vibrated cardboard box as described above. The box shall contain centering devices to maintain the anode in a centered position surrounded fully by the special backfill. A minimum of 10 feet of AWG No. 12 solid copper wire with TW insulation (black) shall be attached to the anode. Wire to anode attachment shall be by silver solder and sealed to prevent any moisture penetration. The anode system shall be as manufactured by Stuart Steel Protection Company or approved equal.

#### 3.02 TEST BOXES

The flush mount test box shall consist of a nonconductive terminal board mounted in a locking cast iron lid and collar (suitable for placement in heavy traffic areas) and a plastic shaft. The test box shall pass U.S. DOT H-20 roadway load test. The cast iron of the lid and collar shall meet or exceed ASTM A48 Class 25 specification. The test box lid to be made of cast iron with B-DPW cast into the lid design and painted yellow. The lid shall feature a cast-in pentagonal bolt to lock into the cast iron cover. The cast iron collar to be at least 2.75 inches high with lugs cast inside to accept the locking lid and to accept a 1-inch cast iron repaving adapter with original lid. The plastic shaft is to be made of ABS (acrylonitrile butadiene styrene), 18 inches long with a flared bottom to resist sinking in soil. The plastic shaft shall have a 5-inch inner diameter. The plastic shaft is to be riveted to the cast iron collar. The test block shall be made of nonconductive PVC (polyvinyl chloride) plastic. The terminal board shall contain a minimum of seven terminals, using 0.25 inch by 20 thread nickel-plated machine screws and nuts. The terminal board shall fit into the lid using hangers cast inside the lid. (C.P. Test Services, Inc. or approved equal).

#### 3.03 TEST STATION CONCRETE

Concrete for the flush-mounted test station slabs shall be Baltimore County Mix No.2 in accordance with the Standard Specification, Section 902, Table 902A.

#### 3.04 TEST STATION TERMINAL LUGS

Test station terminal lugs shall be one-hole, compression terminal lugs for 0.25-inch bolt size.

#### 3.05 CURRENT MEASURING SHUNT

Test station shunts shall be constructed to fit the terminal posts for the specified test station. The resistance shall be 0.01 ohm with a current capacity of 8 amperes. The shunt shall be as manufactured by Cott Manufacturing Company Model "Yellow" or approved equal.

#### 3.06 REFERENCE ELECTRODES

The reference electrode shall be a permanent copper/copper sulfate reference electrode designed for a minimum life of 20 years. The electrode shall have a 2-inch diameter by 8 inches long, schedule 80 PVC body or a 2-inch diameter by 7 inches long, high impact resistant Lexan tube, and a minimum overall package size of 6-inch diameter by 10 inches long. The reference electrode shall be prepackaged in a permeable cloth bag with special copper/copper sulfate reference electrode backfill. Lead wire shall be of sufficient length to reach the test station terminals without splicing. The lead wire shall be AWG No. 14 stranded copper wire with either HMWPE or RHH-RHW insulation. The wire insulation shall be black. The lead wire shall be attached to the electrode core with the manufacturer's standard connection. The connection shall be stronger than the wire. Splicing of the reference electrode lead wire shall not be permitted under any circumstances.

#### 3.07 WIRE

- A. All wiring, excluding wire provided with the magnesium anodes or reference electrodes, shall be stranded copper wire of the AWG wire size and color shown in the Details.
- B. Wire for bonded joints shall be single conductor, stranded copper with high molecular weight polyethylene (HMWPE) insulation (black). Wire size shall be AWG No. 2 for piping larger than 36-inch, AWG No. 4 for 16-inch through 36-inch piping, and AWG No. 6 for piping smaller than 16-inch.
- C. Wire for test stations shall be single conductor, stranded copper wire with 600-volt HMWPE or THWN insulation as required (colors as shown on the Details).
- D. Anode header cables shall be single conductor, stranded copper with high molecular weight polyethylene (HMWPE) insulation (black). Wire size shall be AWG No. 8.

#### 3.08 THERMITE WELD EQUIPMENT

Thermite weld molds and charges shall be suitable for the sizes and types of materials and shapes encountered. Adapter sleeves shall be utilized for all thermite welds. Pin brazing shall not be used to attach bond wires and/or test wires to the piping.

#### 3.09 COATING FOR THERMITE WELDS

- A. Thermite welds to steel casings, and cast and/or ductile iron pipe are to be coated with a prefabricated assembly specially designed for covering cathodic protection wire connections to piping and fittings. The prefabricated assembly shall consist of the following components:
  - 1. Top plastic sheet formed with an igloo shaped dome and entry tunnel for the lead wire:
  - 2. A special elastomeric compound in the plastic dome firm enough to resist flow at normally encountered application and operating temperatures, but soft enough to mold itself around and completely cover the irregular welded profile;
  - 3. A double row of parallel, flexible serrations on either side of the dome to assist with conforming around small diameter pipe;
  - 4. A base of black unbacked elastomeric tape with exceptional adhesive properties for bonding firmly to a surface when used with the appropriate primer.
  - 5. Caps shall be as manufactured by Royston Laboratories Division, Model Handy-Cap or approved equal. The appropriate primer as required by the elastomeric cap manufacturer shall be used. Primer for the Royston Handy-Cap shall be as manufactured by Royston, Model Roybond 747 Primer.

#### 3.10 INSULATING FLANGE COMPONENTS

Insulating materials shall include an insulating gasket, insulating sleeves and insulating washers. The insulating gasket shall be "Linebacker" Type "E" with a G-10 retainer and nitrile "quad" ring seal. The insulating sleeves shall be 1/32 inch thick spiral wound mylar nitrile "quad" ring seal. The insulating washers shall be G-10 and installed on both sides of the flange. Steel washers shall also be used between the insulating washers and the bolts and nuts and between the insulating washers and the flange. The pressure rating for the insulating flange materials shall be greater than the design pressure of the piping.

#### 3.11 INSULATING CORPORATION VALVES

The insulator for water services less than 4 inches in diameter shall consist of a brass fitting with a nylon insulator. The insulating corporation valve shall be as manufactured by Mueller Company, Insulated Model 300 Corporation Ball Valve or approved equal.

## 3.12 EXTERNAL COATING SYSTEM FOR INSULATING FLANGES, INSULATING COUPLINGS, AND INSULATING CORPORATION VALVES

A. Insulating flanges, insulating couplings, and insulating corporation valves shall receive an

exterior tape wrapping in the field. The coating applicator must abide by and follow all manufacturer's application specifications for the coating system. All components of the coating system shall be manufactured by a single supplier to assure compatibility of individual components. The coating system shall be manufactured by Trenton Corporation, Denso North America, or an approved equal. The coating materials shall include:

- 1. Primer: A blend of microcrystalline wax, plasticizer, and corrosion inhibitors having a paste-like consistency, designed to displace moisture, penetrate rust and wet the surface, ensuring adhesion of the tape. The primer shall be Trenton Wax-Tape Primer or approved equal.
- 2. Filler Putty: A cold applied anti-corrosive moldable filler material used to even the contours of irregular fittings and surfaces. The filler putty shall have the following properties:
  - a. Specific gravity: 1.15.
  - b. Density: 24 cu in/lb.
  - c. The filler putty shall be Trenton Fill-Putty or approved equal. Filler putty shall be used at all irregular surfaces to provide a smooth surface for the application of the innerwrap and outerwrap.
- 3. Innerwrap: A non-woven, non-stitch bonded synthetic fabric saturated with a blend of microcrystalline wax, plasticizer, and corrosion inhibitor (no clay fillers). The inner tape shall have the following properties:
  - a. Thickness: 70 to 90 mils.
  - b. Dielectric strength: 170 volt/mil.
  - c. The innerwrap shall be Trenton #1 Wax-Tape or approved equal.
- 4. Outerwrap: A white, resin coated, woven fiberglass fabric. The outerwrap shall have the following properties:
  - a. Thickness: 0.005 inch.
  - b. Tensile strength (per one-inch width): 85 lb. min.
  - c. Tape width: 6 inches.
  - d. The outerwrap shall be Trenton Glas-Wrap or approved equal.

#### 3.13 POLYETHYLENE MESH SEPARATOR PAD

The mesh separator pad shall be a medium density flexible polyethylene mesh pattern webbing pad, nominal thickness 160 mils. Separator pad shall be as manufactured by Stuart Steel Protection Company Model Stuart Diamond Rockstop or approved equal.

#### 3.14 MASTIC

- A. The field applied external coating shall be applied mastic with the following properties:
  - 1. Composition: A pyrobituminous resin processed by homogenization with inhibitive pigments and aromatic solvents.
  - 2. Electrical volume resistivity: 2.12 X 373 ohms-cm.
  - 3. Percent solids: 58.6% by volume, 68.2% by weight.
  - 4. Service temperature:  $0 \text{ to } 250^{0} \text{ F}$ .
  - 5. Weight per gallon: 9.42 pounds.
  - 6. Specific gravity: 1.13.
  - 7. Flash point:  $44^{0}$  F seta closed cup.
  - 8. Color: black.
- B. The mastic coating shall be applied only where specifically required by the specifications. The mastic coating shall be used for field coating ductile iron pipe that will be in direct contact with poured concrete. The mastic coating shall be Roskote R28 Rubberized Mastic or approved equal.

#### 3.15 COMPRESSION CONNECTORS

Compression connectors shall be specially manufactured for splicing copper cables together. the connectors shall be copper and shall be Type YC-C as manufactured by Burndy Corporation or approved equal.

#### 3.16 ELECTRICAL TAPE

Conformable watertight sealant having a dielectric strength not less than 15kV for a 1/8 inch thick layer. Tape shall be Scotch 88 Vinyl Tape and Scotch C130 Rubber Tape or approved equals.

#### 3.17 ELECTRICAL COATING COMPOUND

The electrical coating compound shall be brush applied material formulated for sealing vinyl tape. The electrical coating compound shall be Scotchkote Electrical Coating as manufactured by 3M Company or approved equal.

#### 3.17 LINKED RUBBER SEAL

The linked rubber seal shall consist of a belt of interconnected rubber links connected together with zinc plated carbon steel hardware. The linked rubber seal shall be manufactured by Thunderline Corporation or an approved equal.

#### **PART 4 - EXECUTION**

#### 4.01 THERMITE WELDING

- A. All thermite welds shall be made as shown on the Drawings and in accordance with the manufacturer's recommendations using the proper combination of equipment for the pipe and wire size being welded. All welding materials and equipment shall be the product of a single manufacturer.
- B. Assure that the area where the attachment is to be made is absolutely dry. Remove mill coating, dirt, grime and grease from the pipe or fitting surface at the weld location by wire brushing or by the use of suitable safety solvents. Clean a 2.5-inch square area of the pipe or fitting surface at the weld location to a bright shiny surface, free of all serious pits and flaws by use of a mechanical grinder.
- C. Prepare the wire for welding by assuring that the cable is absolutely dry. The cable shall be free of dirt, grease and other foreign products. Cut the cable in such a way as to avoid flattening or forcing out of round. To prevent deformation of the cable, cut the cable with cable cutters. Remove the insulation in a manner that will avoid damage to strands. Install adapter sleeves for all bonds and test wires prior to welding. Either prefabricated factory sleeved joint bonds or bond wire with formed sleeves made in the field are acceptable. Hold the cable at an approximate 30-degree angle to the pipe surface when welding.
- D. When the weld has cooled, remove the weld slag and test the weldment for strength by striking a sharp blow with a two-pound hammer while pulling firmly on the wire. Reweld unsound welds and retest weldments. Thoroughly clean mold and mold covers after completion of each weld to assure that no slag will penetrate into the next weld.
- E. After soundness of the weld has been verified, thoroughly clean with a stiff wire brush and coat. Thermite welds to ductile iron pipe shall be coated with a plastic cap filled with elastomeric material. The elastomeric cap shall extend on all four sides beyond the cleaned area. Apply primer over the entire weld area and over the entire area where the elastomeric cap will be placed. Push the dome of the prefabricated cap containing elastomeric material firmly into weld area. Lift the wire away from the pipe and apply the elastomeric material completely around and underneath the wire. Push the wire back down on the pipe. Follow all manufacturer's instructions for installing prefabricated caps. Repair pipe coating as recommended by the pipe coating

manufacturer.

F. Pin brazing is not an acceptable alternative to thermite welding.

#### 4.02 BONDED JOINTS

- A. All new ductile iron pipe joints, including those on pipe, fittings, valves and branch connections, except those specified to be insulated, shall be bonded with insulated copper cables as shown on the Drawings. All bond cables shall be thermite welded to the pipe or fitting as described above.
- B. All joints shall be bonded with two HMWPE insulated copper cables. Wire size shall be AWG No. 2 for piping larger than 36-inch, AWG No. 4 for 16-inch through 36-inch piping, and AWG No. 6 for piping smaller than 16-inch.

#### 4.03 PREPACKAGED MAGNESIUM ANODES

- A. Prepackaged magnesium anodes shall be installed where indicated. Prior to installation, remove all shipping covers from the anode (the prepackaged cardboard box shall not be removed). Install the anodes in existing soils (free from rocks, roots, organic material, trash or other debris) and backfill with a minimum of 6 inches of existing soil (as described above). Do not install the anode in sand, rock or gravel backfill. Provide a minimum anode spacing of two feet from other pipelines. Pre-soak the anode with 5 gallons of water after placement, but prior to backfilling.
- B. At anode test stations and anode lead wires shall be buried a minimum of two feet below grade. Handle wire with care. Splice the AWG No. 12 solid copper wire supplied with the anode to an AWG No. 8 HMWPE stranded copper cable through the use of a compression connector as shown. Tape the splice with three layers of high voltage rubber splicing tape (50% overlap), followed by three layers of vinyl electrical tape (50% overlap). Terminate the ends of the AWG No. 8 anode header cable in the test boxes utilizing the terminal lugs and shunts as indicated.
- C. At fire hydrant test stations, anode lead wires shall be buried a minimum of two feet below grade. Handle wire with care. Route the AWG No. 12 solid copper wire supplied with the anode to the test box as shown. Terminate the ends of the anode lead wires in the test boxes utilizing the terminal lugs and shunts as indicated.

#### 4.04 TEST STATIONS

- A. Install test stations at the locations indicated. Test boxes are to be located directly over the pipeline except in areas that would place the test station in a roadway. Locate these test stations to the closest point just off the edge of the road.
- B. Attach test wires as indicated using the proper thermite welding equipment and

charges specified for the wire size and respective pipe material. Follow all procedures as outlined in 4.01 above.

- C. All test station wires shall be routed a minimum of two feet below finished grade. Maintain sufficient slack in the test wires so that the wires can extend a minimum of 18 inches from the test box. Connect the test wires to the test station terminal block with one-hole, compression terminal lugs for 0.25-inch bolt size. Install a shunt and a copper shorting strap to connect the anode leads to the pipe lead where indicated on the Drawings.
- D. Test boxes shall be set in poured concrete, two feet on each side and six inches thick reinforced with 4 inch by 4 inch W2.1 by W2.1 welded wire fabric. The flush mounted test box lids shall be free of concrete and not cemented over.
- E. Test wires shall be routed under the roadway to the test box through conduit.

#### 4.05 REFERENCE ELECTRODESS

Install reference electrodes at the test stations indicated. The reference electrodes shall be installed at an approximate depth of six inches below the bottom of the pipe trench. Native trench material shall be used to backfill the reference electrode for a minimum of six inches. Prior to installation, remove the plastic shipping cover from the reference electrode. The cloth bag containing the special backfill shall remain intact.

#### 4.06 CLEARANCE TO OTHER STRUCTURES

Twelve inches of natural clearance shall be maintained to other structures, where possible. When 12 inches of clearance cannot be maintained, install a flexible polyethylene mesh webbing pad around the new piping and secure with non-metallic tape.

#### 4.07 INSULATING FLANGES AND INSULATING CORPORATION VALVES

A. Insulating flanges, insulating couplings, and insulating corporation valves shall be installed where shown on the Drawings. The CONTRATOR shall carefully align and install the insulating components according to the insulator manufacturer's instructions. Before backfilling, the Contractor shall test each insulator for electrical isolation. If the insulator is not properly isolated, the Contractor shall, at his expense, repair or replace all defective components. The Contractor shall test the repaired insulator. This process will continue until the insulator is tested to be properly isolated. The insulator shall then be coated as described in 4.08 below. After coating, the Contractor shall test each insulator for electrical isolation. If the insulator is not properly isolated, the Contractor shall, at his expense, repair or replace all defective components. The Contractor shall test the repaired and recoated insulator. This process will continue until the coated insulator is tested to be properly isolated.

- B. If the insulator is not immediately backfilled after verification of effective isolation of the coated insulator, it shall be retested for effective isolation immediately prior to backfilling. If the insulator is not properly isolated, the Contractor shall, at his expense, repair or replace all defective components. The Contractor shall test the repaired and recoated insulator. This process will continue until the coated insulator is tested to be properly isolated. The properly isolated insulator shall then be immediately backfilled.
- C. The Contractor shall retest the insulating flanges and insulating couplings for effective isolation immediately after backfilling. If the insulator is not properly isolated, the Contractor shall, at his expense, expose and repair or replace all defective components. The Contractor shall test the repaired and recoated insulator. This process will continue until the coated insulator is tested to be properly isolated. The properly isolated insulator shall then be immediately backfilled. The Contractor shall retest the insulator for effective isolation immediately after backfilling. This process will continue until the coated insulator is tested to be properly isolated.
- D. The coated insulator shall be tested for electrical isolation as part of the final acceptance testing conducted by the Engineer. Any and all insulators that fail the final acceptance test for isolation shall be excavated and repaired by the Contractor at no additional cost.

## 4.08 COATING OF INSULATING FLANGES AND INSULATING CORPORATION VALVES

- A. Insulating flanges, insulating couplings, and insulating corporation valves, including all isolation components, shall be fully coated for a minimum of 12 inches on either side of the flange, coupling, or corporation valve. The insulator shall be coated after verification of proper electrical isolation. The insulator shall be coated as described below.
  - 1. Clean the surface of the insulator, and all of its components by power tool cleaning in accordance with the SSPC SP3. Follow all surface preparation recommendations of the coating manufacturer.
  - 2. Apply a uniform coat of the primer to the external surface of the insulator, and all of its components including; bolts, nuts, etc. The primer shall extend a minimum of twelve inches on either side of the insulator.
  - 3. Apply filler mastic to all irregular surfaces of the insulator to assure a smooth profile for application of the inner tape coating.
  - 4. Apply innerwrap to the insulator, and its components in a spiral fashion with a minimum overlap of 55%. The innerwrap shall extend a minimum of twelve inches on either side of the insulator.

5. Apply outerwrap to the insulator, and its components in a spiral fashion with a minimum overlap of one inch. The outerwrap shall be applied with sufficient tension to provide continuous adhesion of the outerwrap tape. Install test facilities at the insulating flanges as shown on the Drawings.

## 4.09 INSULATING FLANGES AND INSULATING CORPORATION VALVES ISOLATION EFFECTIVENESS TESTING

A. Test electrical effectiveness of each dielectric insulator after installation and before coating and after coating as required in 4.07 and 4.8 above. Testing of insulating flanges and insulating couplings shall also be conducted immediately after backfilling. All data shall be recorded and submitted to the Engineer for approval before the insulator is backfilled and immediately after it is backfilled. THE ELECTRICAL ISOLATION TESTING DESCRIBED HERE IS CRITICAL AND MUST BE PERFORMED AS DESCRIBED AND AT THE TIMES REQUIRED BY THIS SPECIFICATION.

#### 1. Insulator Tests:

- a. Use a high-frequency isolation tester (Gas Electronics Insulator Tester (TM) Model 601 or 702) manufactured specifically for this purpose, <u>AND</u>
- b. Measuring electrical potential across and on both sides of the insulator before, during and immediately after application of a direct test current to the pipe on one side of the insulator of no less than 0.5 ampere. Documented data for test b shall include all potentials and applied test current.
- c. Acceptance Criteria:
  - 1) High frequency isolation tester: "Acceptable", "Satisfactory" or other similar direct meter reading, <u>AND</u>
  - 2) Electrical potential/applied current: Static potential difference across insulator of no less than 0.1 volt before application of test current; a positive potential shift on the side of the insulator where current is applied, and a negative potential shift on the side of the insulator opposite of where current is applied.

## 4.10 CONCRETE BUTTRESSES, SUPPORT BLOCKS, ANCHOR BLOCKS, AND OTHER CONCRETE STRUCTURES

Position reinforcing steel used in the construction of support blocks, anchor blocks, and any and all other concrete structures so that they are not in contact with the piping. Maintain a minimum of 2 inches of clearance between the piping and all reinforcement steel or other

metallic components. Under no circumstances shall metallic pipe be in contact with reinforcing steel.

#### 4.11 PENETRATION OF CONCRETE STRUCTURES

When penetrating a concrete slab (wall or floor), install a linked rubber seal between the pipe and the concrete slab sleeve. Install the linked rubber seal in accordance with the manufacturer's recommendations. The linked rubber seal is to be installed to isolate the piping from direct contact to the concrete and to seal the area of the pipe penetration from water intrusion. Under no circumstances shall metallic pipe be in contact with reinforcing steel. Linked rubber seals are not required for prefabricated "dog house" vaults.

#### **PART 5 - POST INSTALLATION TESTING**

#### 5.01 TESTING

- A. Prior to substantial completion, the Engineer will perform post installation testing of all corrosion control components.
- B. Defective or Improperly Installed Components
  - 1. Insulating flanges, insulating couplings, and insulating corporation valves that test effective by the Contractor prior to backfilling and immediately after backfilling that are not effective isolators during the post installation testing shall be excavated and repaired by the Contractor at no additional cost to the Owner.
  - 2. The repair or replacement of any defective or improperly installed systems shall be the sole responsibility of the Contractor. Any and all repairs or replacement of defective or improperly installed corrosion control systems shall be performed by the Contractor at no additional cost to the Owner.



# BALTIMORE COUNTY DEPARTMENT OF PUBLIC WORKS HOLIDAY DETECTION DAILY FIELD REPORT

DOLECT	Back River Neck Road 24-inch and 16-inch Water Main Replacement				TEST DATE:	
		- 1			CONTRACT #	Y 33 00 00 00 00 00 00 00 00 00 00 00 00
			PIPE MATERIAL:			G:
	8.75	344 37	(MILS) CO			
DIVINIAN	1 01 11313.					
PIPE	9878.0%	ATION	INITIAL TEST RESULTS (# OF	RETEST REQUIRED	RETEST RESULTS (# OF	SKETCH
NUMBER	FROM	ТО	HOLIDAYS)	(Y/N)	HOLIDAYS)	
1011	1					
	-	1				
		-		L	4	
NAME OF	TESTER:					

119

## CATEGORY 300 DRAINAGE & UTILITY CONSTRUCTION

#### **INSERT:** The following:

#### **SECTION 373 - TEMPORARY WATER BYPASS**

#### 373.01 Materials

- (a) Temporary Water Bypass Pipe, Hose, Fittings and Valves:
  - 1. Withstand working pressures up to 125 psi.
  - 2. Follow NSF Standard 14 or 61 for potable water.
  - 3. Not impart objectionable color, taste, or odor to water being supplied.
  - 4. Temporary fire hydrant:
    - a. Consist of 4 inch by 4 inch tee or 4 inch 90° bend, with ball valve or equal, connected to end of the tee or bend and operating nut to control the valve.
    - b. Equipped with 4-1/2 inch diameter National Standard threaded nozzle with hydrant cap installed.

#### **373.01 Construction**

- (a) Provide telephone numbers to Engineer for designated after hours emergency work crew before installation of bypass system.
- **(b)** Remove no more than 5,000 feet of existing main from service at one time unless Engineer approves otherwise.
- (c) Before water main to be replaced or cleaned and lined is shut down, ensure the materials necessary to perform the work approved for use, and all necessary materials to perform the work are on site or are scheduled for delivery in accordance with the approved project schedule. Provide temporary bypass piping system of adequate size to provide water service and fire protection to affected properties as required herein and as directed by the Engineer:
  - 1. Notify Engineer:
    - a. At least 24 hours in advance for installation of temporary connections.
    - b. When additional bypass services are made.
    - c. When problems develop with any meters or services.
- (d) Use nearest available fire hydrant for connection to temporary bypass system.
  - 1. Where fire hydrants cannot be used, excavate and tap existing water main at Engineer's direction.
  - 2. Provide backflow preventers on temporary bypass piping at connection to source.
  - 3. Make temporary bypass service attachments to fire hydrants in a manner that will allow removal with minimum effort in case of emergency.
  - 4. Provide temporary fire hydrants;
    - a. Provide markers that are clearly visible from street. b.

Brace hydrants.


- c. Spacing as follows;
  - 1) Single family residential area.
    - a) Spacing maximum 500 feet apart measured along an improved roadway and within 400 feet from the most distant corner of any dwelling.
  - 2) Townhouses and garden apartments.
    - a) Spacing maximum 250 to 300 feet apart measured along an improved roadway and within 300 feet from the most distant corner of any building.
  - 3) Commercial, industrial, high-rise, and elevator type apartments.
    - a) Spacing maximum 250 to 300 feet apart measured along an improved roadway.
- (e) Provide temporary service connection for existing water services less than 2 inch diameter affected by required water main shutdowns.
  - 1. Existing inside meters:
    - a. Connect temporary service using temporary curb stop following Detail W/5.16a (see section 373.04).
    - b. When temporary service is no longer required, reconnect water service and provide new curb stop and curb box assembly.
  - 2. Existing outside meters:
    - a. Connect temporary service to existing meter following Detail W/5.16 (see section 373.04).
    - b. Use notched meter covers when temporary services are connected.
    - c. Angle ball valves improperly connected to existing meter will be removed and correctly install by the County, and the County will charge the expense to the Contractor and will retain same out of any monies due or to become due to him under the contract.
    - d. When temporary service connection is no longer required:
      - 1) Reconnect water service and provide new meter assembly.
      - 2) Reset existing meter in new assembly.
      - 3) Meters improperly installed will be removed and correctly installed by the the County, and the County will charge the expense to the Contractor and will retain same out of any monies due or to become due to him under the contract.
- **(f)** Placement and protection of temporary bypass piping system.
  - 1. Do not install between November 15 and March 1.
  - 2. Remove by November 15.
  - 3. Do not place during freezing weather and if already installed, protect from freezing.
  - 4. Provide cap and sampling connection at downstream end of each separate bypass piping segment.
    - a. Do not loop downstream end of segment back to or near inlet of segment.
  - 5. Cover sections of temporary bypass lines that cross driveways or sidewalks and


- ramp with bituminous cold mix.
- 6. Protect concrete and brick driveways to prevent discoloration from bituminous material.
- 7. Place bypass lines at road crossings below the existing road surface.
- 8. Place sections of bypass or services that cross sidewalks with barricades, ramps, and fluorescent paint.
- 9. Place crossings of bypass lines parallel and/or perpendicular to handicap ramps, below existing grade.
- 10. Install and support temporary bypass piping at storm drain inlet crossing so that piping and supports do not impede storm water from entering storm drain inlet.
- (g) House to house connections are prohibited.
- **(h)** Temporary bypass piping for existing service connections 3 inch and larger diameter and temporary fire protection: Minimum 4 inch diameter.
- (i) Disinfect temporary bypass piping, including temporary house services, utilizing distribution system residual.
  - 1. The County will take bacteriological samples within 3 working days after receipt of written notification from Contractor that disinfection is complete.
  - 2. Results of sample analysis will be available within 3 working days after sampling.
  - 3. If samples are not approved, chlorinate and notify the Engineer to take new samples for testing.
  - 4. Cost of the additional disinfection, samples and testing: Contractor's expense.
  - 5. After samples are approved by the County, place bypass piping in service.
- (j) Maintenance or repair of temporary bypass piping system.
  - 1. Respond to the County's notification within 30 minutes and arrive at work site within 2 hours of notification.
  - 2. Provide adequate equipment, materials, and labor to take remedial actions within 1 hour of arrival at site in order to restore temporary bypass system in a timely manner at no cost to the County.
  - 3. Notify the Engineer immediately after arriving at the work site and after work has been completed.
  - 4. Failure to respond back to the County within 30 minutes, failure to arrive at work site within 2 hours or failure to take remedial action within 1 hour of arrival on site will result in the County taking action to restore service and cost incurred by the County to restore service and will be assessed to Contractor and deducted from payments.

#### 373.03 Measurement and Payment

- (a) Measurement: By linear foot of mainline to be bypassed. Measured horizontally along the mainline from point of bypass connection at mainline to opposite end of bypass at mainline.
- (b) Payment: At unit price for each linear foot listed in Bid Schedule.
  - 1. Payment includes provision and installation of bypass piping, hoses, corporation stops, valves, fire hydrants, fittings and appurtenances, disinfecting and maintaining bypass line (including all repairs), connection and disconnection to mainline.

#### **373.04 Details**





### **373.05** Temporary Bypass Schedule

		Comments												
		Minimum Bypass	Size Required	4" Line	4" Line	4" Line	4 Line	4" Line	4" Line	4" Line	4 Line	4" Line	4" Line	
DULE	PLACEMENT	Existing Main to be bypassed	Length (ft.)	1,840	1,085	1,435	1,395	392	1,400	715	265	3,600	3,020	15,520
<b>SSS SCHE</b>	<i>w</i> ater main rei	Existing Main t	Size	ŧ.	ь	80	80	20		æ	80	16"/12"	24"	ain to be bypassed:
TEMPORARY BY-PASS SCHEDULE	BACK RIVER NECK ROAD 24" AND 16" WATER MAIN REPLACEMENT	ssa	01	1660 Hopewell Avenue	1637 Howard Avenue	1655 Frenchs Avenue	1709 Williams Avenue	1560 Tripgate Road	1699 Poles Road	1656 Riverwood Road	216 Cove Road	215 Back River Neck Road	215 Back River Neck Road	Total Length of existing main to be bypassed:
TEN	BACK RI	Address	From	1609 Hopewell Avenue	1600 Howard Avenue	1608 Frenchs Avenue	1610 Williams Avenue	1550 Tripgate Road	1633 Poles Road	1600 Riverwood Road	200 Cove Road	104 Back River Neck Road	104 Back River Neck Road	
		Type of Customer	Residential or Commercial	Residential	Residential	Residential	Residential	Residential	Residential	Residential	Residential	Residential/Commercial	Residential/Commercial	

#### CATEGORY 500 PAVING

**INSERT:** The following:

#### **SECTION 554**

#### THERMOPLASTIC PAVEMENT MARKINGS

All other references in this section refer to the Maryland State Highway Administration's 2019 MDOT SHA Standard Specifications for Construction and Materials.

https://www.roads.maryland.gov/mdotsha/Pages/sscm.aspx?PageId=853&lid=SSP

#### 554.01 DESCRIPTION

Furnish and apply thermoplastic pavement marking material to roadway surfaces as specified and as directed. The requirements noted in the Baltimore County Utility Permit shall take precedence in cases of any conflict with these Special Provisions.

#### 554.02 MATERIALS

Thermoplastic is a durable material. Select thermoplastic pavement markings from the Qualified Products List (QPL).

Thermoplastic Pavement Markings <u>951.04</u>
Glass Beads <u>951.09</u>

#### 554.03 CONSTRUCTION.

Refer to 549.03.

**554.03.01 Quality Control.** Refer to 549.03.01.

**554.03.02 Quality Assurance.** Refer to 549.03.02.

554.03.03 Cleaning Pavement Surfaces. Refer to 549.03.07.

**554.03.04 Quality Control Test Strip.** Refer to <u>549.03.09</u>.

#### 554.03.05 Application Equipment.

- (a) Kettles. Use equipment that has oil or air jacketed kettles for uniform melting and heating of the thermoplastic material, is equipped with an automatic thermostatic device to provide positive temperature control, and conforms to the requirements of the National Board of Fire Underwriters (NBFU), the National Fire Protection Association (NFPA), and State and local authorities.
- **(b) Agitation.** Use equipment that provides continuous mixing and agitation of the material in the kettle, constructed so that all mixing and conveying parts, (including the application apparatus) maintains the material at the specified temperature and constructed to prevent clogging of the applicator conveying parts between the reservoir and the application apparatus.
- (c) Capacity. Use vehicle mounted equipment capable of holding a minimum of 600 lb. of molten thermoplastic material for longitudinal line application.
- (d) **Temperature Gauges.** Use temperature gauges that have been calibrated every six months and submit a copy of the calibration certification per the QCP.
- (e) Footage Counters. Use calibrated footage counters to measure pavement markings and submit notarized calibration certification per the QCP.

- **(f) Usage Counters.** Use equipment that is equipped with material usage counters and printers or measure tanks manually using equipment manufacturer certified tables. Use beginning and ending quantities to calculate thickness of applied lines and record daily.
- (g) Bead Dispenser. Use a pressurized bead dispenser or other mechanical conveying method not dependent upon gravity for uniform application of glass beads for each material dispenser.
- (h) Material Dispenser. Use a material dispenser that can apply all longitudinal markings at multiple width settings ranging from 5 to 12 in. as demonstrated by the quality control strip and as specified. Reconduct the quality control strip whenever the guns are repositioned or adjusted after the initial quality control strip.
- (i) Maneuverability. Use a vehicle that is mobile and maneuverable to produce straight lines, standard curves in true arcs, and capable of cleanly cutting off the ends of markings.
- (j) Cleanliness. Thoroughly clean all parts of the equipment of foreign or different colored material prior to the introduction of a new batch of material.

**554.03.06 Application.** Use vehicle mounted equipment to apply markings at the location, width, and type of marking specified and as directed. Apply to bare pavement or over existing thermoplastic per the manufacturer's recommendations. Do not place thermoplastic material over longitudinal joints; offset 2 in. or as directed.

Use small equipment capable of heating, agitation and applying glass beads to apply thermoplastic markings to gore areas, crosswalks, small intersections, roundabouts, wide markings, transverse markings and other areas that preclude the use of vehicle mounted equipment.

- (a) Ambient Conditions. Apply material when ambient and surface temperatures are at least 50 F and rising at the time of application.
- **(b) Moisture in Pavement.** MSMT 729. Do not apply material if test is positive for moisture.
- (c) **Temperature.** Apply thermoplastic material when the molten material temperature is between 400 and 440 F unless otherwise recommended by the manufacturer, and approved.
- (d) **Primer.** Use a primer that is compatible with the thermoplastic material and recommended by the thermoplastic manufacturer when thermoplastic material is applied to portland cement concrete surfaces.
- (e) Thickness. MSMT 729. The pavement markings shall yield a solid of 90 mils above the roadway surface. Variation from this range will be used for the price adjustment specified herein.
- (f) Glass Beads. MSMT 729. Apply standard glass beads to the surface of the molten thermoplastic at the minimum rate of 7 to 9 lbs. per 100 square feet.
- (g) Color. MSMT 729.
- (h) Retro reflectance. MSMT 729. The minimum retro reflectance shall be 150 millicandelas/lux/square meter for yellow and 250 millicandelas/lux/square meter for white.
- (i) Widths. Refer to 549.03.04.
- (j) **Alignment.** Refer to 549.03.05.
- (k) Layout Markings. Refer to 549.03.06.

**554.03.07 Curing.** Refer to 549.03.10.

**554.03.08 Observation Period.** Refer to 549.03.11.

**554.03.09 Submittals.** Supply MSDS, Product Data Sheets, and QCPs.

#### 554.04 MEASUREMENT AND PAYMENT.

Refer to <u>549.04</u>. Payment will be full compensation for all pavement preparation, furnishing and placing of markings, testing, and for all material, labor, equipment, tools, and incidentals necessary to complete the work.

Thermoplastic Pavement Marking lines will be measured and paid for at the Contract unit price per linear foot for the color and width specified.

Thermoplastic Pavement Marking Legends (letters and numbers) and Symbols will be paid for at the Contract unit price per square feet.

**554.04.01 Price Adjustment for Film Thickness.** The unit price for Thermoplastic Pavement Markings will be per striped linear foot based on MSMT 729 calculations for thickness, and will be adjusted in conformance with the following:

MIL THICKNESS*	PERCENT OF PAYMENT - UNIT PRICE
90- (a)(b)	100
80-89	90
70-89	80
Less than 70	Retrace to achieve a thickness of 90 mils.

<sup>(</sup>a) The Engineer may require the removal of excess material thickness.

#### 951.04 THERMOPLASTIC PAVEMENT MARKINGS.

Thermoplastic pavement markings shall be homogeneously composed of pigment, filler, resins, glass beads and conform to the following.

#### **951.04.01** Composition.

COMPONENT	TEST METHOD	CO	LOR
		WHITE	YELLOW
Binder, % min	Certified	18.0	18.0
Premixed Reflective Beads, % min	MSMT 614	30.0	30.0
Titanium Dioxide, % min	X-Ray Fluorescence	10.0	N/A
Calcium Carbonate Inert fillers, % max	D 34	42.0	*
Yellow Pigment, % —	_	N/A	*

<sup>\*</sup> Amount of yellow pigment, calcium carbonate and filler shall be at the option of the manufacturer.

- (a) **Restrictions.** Thermoplastic pavement markings shall not contain any hazardous material listed in <u>CFR 40</u>, <u>Section 261.24</u>, <u>Table 1</u>. Diarylide type pigments shall only be used when the pavement marking material application temperature does not exceed 392 F.
- **(b) Binders.** Binder shall be alkyd consisting of maleic modified glycerolester of resin and other plasticizers.

<sup>(</sup>b) Removal of excess material and retracing pavement markings shall be performed at no additional cost to the Owner.

<sup>\*</sup>Material thickness less glass bead allowance.

- (c) Titanium Dioxide. Rutile type.
- (d) Inner Mix Glass Beads. Refer to 951.09. Glass beads shall not contain more than 200 parts per million when tested in accordance with EPA Methods 3052, 6010B and 6010C.

#### 951.04.02 Properties.

(a) Physical Properties.

TEST PROPERTY	TEST METHOD	SPECIFICATION LIMITS				
Bond Strength, psi min.	T250	180				
Softening Point, F	1230	215 ± 15				
Low Temperature Stress Resistance	T 250	No Cracks				
Abrasion Resistance	MSMT 614	0.5 g. Loss, max				

- **(b) Specific Gravity.** The specific gravity of the white and yellow pavement marking material shall be 1.7 to 2.2 when tested per MSMT 614.
- (c) Color. After heating for  $4 \pm 0.5$  hours at  $425 \pm 3$  F, the thermoplastic shall meet E 1347 and the following.
  - (1) **Production.** The color of the cured thermoplastic material film shall match the Federal Standard 595 Color chips when compared by instrumental measurement.
  - (2) Control. Control color matching determinations will be made using a Pacific Scientific Color Machine, and an observation angle of 2°, and the CIE Chromaticity Coordinate Color Matching System under light source Illuminate C, with the following tolerances permitted between the standard chip and the cured thermoplastic film sample.

		ITE r No. 925	YEL Colo 389	r No.
	X	Y	X	Y
Standard Chip	0.310	0.330	0.480	0.450
Delta Tolerance	± 0.020	± 0.020	± 0.030	± 0.030

#### (d) Reflectance.

COLOR	TEST METHOD	DAYLIGHT REFLECTANCE at Degree	PERCENT Min.
White	Fed Std 595 No. 37925	45 - 0	80
Yellow	Fed Std 595 No. 38907	45 - 0	50

(e) Yellowing Index. E 313. The yellowing index of the white material shall not exceed 8 prior to QUV and 15 after QUV.

**951.04.03 Qualification.** Manufacturers desiring to have their products approved for SHA's use shall have their products evaluated on the NTPEP North Test Deck. Materials meeting the requirements and performing satisfactorily throughout the evaluation period will be placed on SHA's Qualified Products List. Only NTPEP evaluated products will be considered candidates for selection, unless otherwise waived. The Office of Materials Technology will determine qualification.

**951.04.04 Material Acceptance.** The manufacturer shall provide access to Baltimore County's representative for collecting samples from each production batch prior to shipment. The samples shall be sent for QA testing. Each sample shall be accompanied by certification per <u>TC-1.03</u>. Production batch samples will be subject to random tests, such as but not limited to, X-ray spectroscopy, infrared spectroscopy, ultraviolet spectral analysis, and atomic absorption spectroscopy. Baltimore County will determine conformity with the requirements. Approval is required before a batch or a portion of a batch is shipped.

Random samples may be taken on the project and tested for conformance with these specifications. Nonconformance may result in the suspension from the certification program until qualification is reestablished.

**951.04.05 Certification.** TC-1.03. The manufacturer shall certify that any pavement marking batch supplied conforms to all applicable specifications and shall provide a statement certifying that any material supplied is identical in composition to the material submitted for NTPEP testing. The same code name used in the published report from the test deck must identify the product. Failure to certify will be grounds for batch rejection. Certification shall also contain the following.

- (a) Manufacturer's name.
- **(b)** Manufacturer's address.
- (c) Material color.
- (d) Manufacture date (mm-dd-yy).
- (e) Lot or batch identification number.
- **(f)** Lot/batch size.
- (g) Material Safety Data Sheets.

#### 951.04.06 Production Facility.

- (a) The manufacturer shall provide a facility capable of producing thermoplastic pavement markings in the quantity and quality specified; subject to approval.
- **(b)** The manufacturer shall provide a laboratory capable of performing the required tests, subject to approval.

**951.04.07 Packaging.** Label each container with the following information.

- (a) Manufacturer's Name and Address.
- (b) Material color and component type, if applicable.
- (c) Manufacture date (mm-yy).
- (d) Lot or batch identification number.

#### 951.05 THERMOPLASTIC PAVEMENT MARKINGS - 40-mil HIGH BINDER.

Thermoplastic material shall be composed of a homogeneous mixture of pigment, filler, resins and glass beads and shall conform to the following.

#### 951.05.01.

(a) Composition.

COMPONENT	TEST METHOD	C	OLOR
		WHITE	YELLOW
Binder, % min	Certified	25.0	25.0
Premixed Reflective Beads, % min	MSMT 614	25.0	25-40 MIL.0
Titanium Dioxide, % min	X-Ray Fluorescence	10.0	N/A
Calcium Carbonate Inert fillers, % max	D 34	42.0	*
Yellow Pigment, % —	<del>_</del>	N/A	*

- **(b) Restrictions.** Pavement marking paint shall not contain any hazardous material listed in <u>CFR 40, Section 261.24, Table 1</u>. Diarylide type pigments shall only be used when the manufacturer or pavement marking material application temperature does not exceed 392 F.
- (c) Binders. The binder shall be alkyd consisting of maleic modified glycerolester of resin and other plasticizers.
- (d) **Titanium Dioxide.** Rutile type.
- **(e) Inner Mix Beads.** Refer to 951.09. Glass beads shall not contain more than 200 parts per million when tested in accordance with EPA Methods 3052, 6010B and 6010C.

#### **951.05.02** Properties.

(a) Physical Properties.

TEST PROPERTY	TEST METHOD	SPECIFICATION LIMITS
Bond Strength, psi min.	T250	180
Softening Point, F	1230	215 ± 15
Low Temperature Stress Resistance	T 250	No Cracks
Abrasion Resistance	MSMT 614	0.5 g max. loss

(b) Specific Gravity.  $\underline{\text{MSMT 614}}$ . The specific gravity of the white and yellow pavement marking material shall be 1.7 to 2.2.

- (c) Color. E 1347. After heating for  $4 \pm 0.5$  hours at  $425 \pm 3$  F, the thermoplastic shall be as specified and the following.
  - (1) **Production.** The color of the cured thermoplastic material film of the production sample shall match the Federal Standard 595 Color chips specified when compared by instrumental measurement.
  - (2) Control. Control color matching determinations will be made using a Pacific Scientific Color Machine, and an observation angle of 2°, and the CIE Chromaticity Coordinate Color Matching System under light source Illuminate C, with the following tolerances permitted between the standard chip and the cured thermoplastic film sample.

		ITE r No. 925		LOW r No. 907
	X Y		X	Y
Standard Chip	0.310	0.330	0.480	0.450
Delta Tolerance	± 0.020	± 0.020	± 0.030	± 0.030

#### (3) Reflectance.

COLOR	TEST METHOD	DAYLIGHT REFLECTANCE at Degree	PERCENT MIN
White	Fed Std 595 No. 37925	45 - 0	80
Yellow	Fed Std 595 No. 38907	45 - 0	50

(d) Yellowing Index. E 313. The yellowing index of the white material shall not exceed 8 prior to QUV and 15 after QUV testing.

**951.05.03 Qualification.** Manufacturers desiring to have their materials approved shall have their products evaluated on the NTPEP North Test Deck unless otherwise waived. Materials meeting the requirements and performing satisfactorily throughout the evaluation period will be placed on SHA's Qualified Products List. The Office of Materials Technology will determine qualification.

**951.05.04 Material Acceptance.** The manufacturer shall provide access to Baltimore County's representative for collecting samples from each production batch prior to shipment. The samples shall be sent for QA testing. Each sample shall be accompanied by certification per <u>TC-1.03</u>. Production batch samples will be subject to random tests, such as but not limited to, X-ray spectroscopy, infrared spectroscopy, ultraviolet spectral analysis, and atomic absorption spectroscopy. Random samples may be taken on the project in conformance with the Sample Frequency Guide and tested for conformance with these specifications. Nonconformance may result in the suspension from the certification program until qualification is reestablished.

**951.05.05 Certification.** The manufacturer shall certify in accordance with <u>TC-1.03</u> that any pavement marking batch supplied complies with all applicable specifications and conforms to the formulation identified by the same product code or name placed on the NTPEP test deck from which it was approved. The same code or name as used in the published report from that test deck must identify the product. Failure to certify will be considered grounds for product batch rejection.

554 – THERMOPLASTIC PAVEMENT MARKINGS

Certification shall also include the following.

- (a) Manufacturer's name.
- **(b)** Manufacturer's address.
- (c) Material color.
- (d) Manufacture date f (mm-dd-yy).
- (e) Lot or batch identification number.
- (f) Lot/batch size.
- (g) Material Safety Data Sheets.

#### 951.05.06 Production Facility.

- (a) The manufacturer shall provide a facility capable of producing thermoplastic pavement markings in the quantity and quality specified.
- (b) The manufacturer shall provide a laboratory capable of performing the required tests.

#### **951.05.07 Packaging.** Label each container with the following information.

- (a) Manufacturer's Name.
- **(b)** Place of Manufacture.
- (c) Color of Material and Component Type, if applicable.
- (d) Date of Manufacture (month-year).
- (e) Batch or Lot Identification Number.

#### 951.06 PREFORMED THERMOPLASTIC PAVEMENT MARKINGS.

The material shall be highly durable retroreflective polymeric materials designed for use as transverse lines, numbers, legends, symbols and arrow markings subjected to high traffic volumes and severe wear conditions such as shear action from crossover or encroachment.

- (a) The material shall adhere to all asphalt pavement and portland cement concrete (PCC) pavement surfaces and any existing pavement markings when applied per the manufacturer's recommendations.
- (b) The material shall be capable of conforming to pavement contours, breaks and faults, shall not be affected by weather conditions, and shall remain in place on pavement surfaces without being displaced by traffic.
- (c) The material shall have a minimum shelf life of one year. The material shall conform to the requirements of the MdMUTCD and the following:
- (a) Composition. Refer to the relevant sections of M 249. The material shall consist of polymeric materials, pigments, binders and glass beads distributed throughout the entire cross-sectional area. **Restrictions.** The combined total of lead, cadmium, mercury and hexavalent chromium shall not exceed 100 ppm when tested by X-ray diffraction, ICP, or comparable method capable. Non-leachable lead-based pigments will not be permitted. Diarylide type pigments shall only be used when the manufacturer's recommended application temperature does not exceed 392 F.
- **(b) Color.** Federal Standard 595 color chip Nos. 17886 for white and 13538 for yellow.
- **(c) Frictional Resistance.** E 303. The surface of the applied material shall provide a minimum average skid resistance value of 50 BPN when tested as specified.
- (d) Patching. The material shall be capable of use for patching worn areas of the same type.
- (e) **Thickness.** The minimum thickness without adhesive shall be 120 mils.
- **(f) Adhesion.** C 666, Method B. The material shall retain a minimum of 65 percent adhesive bond after 100 freeze-thaw cycles.
- (g) **Beads.** M 247, Type I.
- (1) Refractive Index. MSMT 211.

(2) Acid Resistance. MSMT 211. 15 percent of the beads (maximum) shall show formation of a distinct opaque white layer on the entire surface.

**Field Testing.** Materials selected for use on SHA's roads shall be field tested for performance at AASHTO regional test facilities, such as National Transportation Product Evaluation Program (NTPEP). The materials shall meet a minimum retained reflectance of 100 mcd/m²/lux after evaluation testing.

Materials performing satisfactorily throughout the test period will be placed on the <u>Qualified Products List (QPL)</u> maintained by the Office of Materials Technology.

Certification. TC-1.03. Samples submitted for testing shall be accompanied by the manufacturer's certified analysis. Any marking materials supplied shall be identical in composition to the material submitted for initial testing.

#### CATEGORY 900 MATERIALS

#### **SECTION 921 – MISCELLANEOUS**

**INSERT**: The following:

#### 921.14 PITCHER FILTERS:

Pitcher filters and replacement cartridges shall be provided to customers where a non-copper (lead, brass, galvanized, etc.) water service is replaced and comply with the following requirements:

- a) Water pitchers must be at minimum two (2) quart volume for home use with internal water filtration system with replaceable filter cartridges.
- b) Water pitcher must have a minimum of a six (6) month limited warranty.
- c) Water pitcher must have a built-in filter change indicator.
- d) Filter must have a minimum of forty (40) gallon filter life.
- e) Water pitcher and filter must be Certified NSF/ANSI Standard 53: Cadmium, Lead, Mercury and VOCs and Standard 42: Aesthetic Effects (class I particulate removal)

#### 921.14.01 MEASUREMENT AND PAYMENT

#### PITCHER FILTER WITH SIX MONTHS OF REPLACEMENT CARTRIDGES – will

be measured and paid for at the Contract unit price per each. The payment will be full compensation for all material, labor, equipment, tools, and incidentals necessary to complete the work. This includes reproducing and distributing the educational materials to be provided to the customer. All items shall be provided to customers at the same time and neatly in an appropriate bag or box.

# **APPENDICES**

## **APPENDIX A**

# **Geotechnical Evaluation Report**



#### THE ROBERT B. BALTER COMPANY®

July 15, 2015

Jeffrey Ziegenfuss, P.E. Senior Associate The Wilson T. Ballard Company 17 Gwynns Mill Court Owings Mills, MD 21117

Re: Geotechnical Evaluation

16-inch and 24-inch Water Main Replacement

Back River Neck Road from East Homberg Avenue to Mizells Road

Baltimore County, Maryland RBB Project No. 16613-0 MD

Baltimore County Project No. 2010-05

WTB Project No. 800-100.04

Dear Mr. Ziegenfuss:

In accordance with your authorization, The Robert B. Balter Company (Balter) has completed our geotechnical evaluation for the subject project. The following report describes our procedures, provides our estimate of the subsurface conditions, and presents our geotechnical evaluation and recommendations for the project.

Project information provided to us helped form the basis for our recommendations. If any of the project information discussed in this report differs from the actual proposed construction, we should be contacted to re-evaluate the recommendations provided herein and provide revisions, if necessary.

We appreciate this opportunity to be of service. If you have any questions regarding this report, or if you would like any additional services, please do not hesitate to call our office.

Sincerely,

#### THE ROBERT B. BALTER COMPANY

Professional Certification. I hereby certify that these documents were prepared or approved by me, and that I am a duly licensed professional engineer under the laws of the State of Maryland. License No. 4/3/2, Expiration Date: 1/5/2016

Kristopher M. Crist, P.

Senior Geotechnical Engine

Joseph F. Whittle Jr.

Chief Engineer

gineer while

Headquarters: 18 Music Fair Road - Owing Mills, Maryland 21117 · 410-363-1555 · 410-363-8073 (Tourne Wall E www.ba/750c.com

GEOTECHNICAL EVALUATION
WATER MAIN REPLACEMENT
BACK RIVER NECK ROAD
EAST HOMBERG AVENUE TO MIZELLS ROAD
RBB CONTRACT NO. 16613-0 MD

#### TABLE OF CONTENTS

1.0		INTRODUCTION
	1.1	General
	1.2	Authorization
	1.3	Scope
2.0		PROJECT INFORMATION
	2.1	Project Description
	2.2	
3.0		METHODS OF EVALUATION
	3.1	Subsurface Explorations
	3.2	<u> •</u>
4.0		SUBSURFACE CONDITIONS
	4.1	Subsurface Materials
	4.2	Standard Penetration Resistances
	4.3	Laboratory Test Results
	4.4	Ground Water Conditions
5.0		EVALUATIONS AND RECOMMENDATIONS
	5.1	General
	5.2	Trench Excavation
	5.3	
	5.4	Bearing Pressures
	5.5	Lateral Pressures for Structure Design
	5.6	
	5.7	Lateral Pressures for Sheeting Design
	5.8	
	5.9	Pavement Repairs
6.0		GEOTECHNICAL OBSERVATION AND TESTING 11
7.0		GENERAL COMMENTS

#### **TABLES**

- Table 1 Measured Pavement Thicknesses
- Table 2 Laboratory Test Results
- Table 3 Soil Lateral Load Parameters
- Table 4 Estimated Soil Parameters for Preliminary Shoring Design

#### **FIGURES**

Figure 1 – Standard Penetration Resistances

#### **PLATES**

Plate 1 – Site Vicinity Map

Plates 2 to 10 – Boring Location Plan

## **APPENDICES**

Appendix A – Boring Logs

Appendix B - Laboratory Test Results

Appendix C – Pavement Core Photographs

#### 1.0 INTRODUCTION

#### 1.1 General

The proposed project consists of the replacement of an existing 16-inch and 24-inch water main with a new 24-inch main within Back River Neck Road between East Homberg Avenue and Mizells Road in Baltimore County, Maryland. The purpose of our work was to perform a geotechnical evaluation of the subsurface conditions to provide geotechnical related recommendations for construction of the new water main.

#### 1.2 Authorization

This work was authorized by Mr. Jeffrey Ziegenfuss, The Wilson T. Ballard Company (WTB), in an email dated May 5, 2015. This work was performed in general accordance with the scope, terms and conditions described in our proposal dated April 16, 2014.

#### 1.3 Scope

The scope of the geotechnical evaluation includes the following: site reconnaissance, subsurface sampling and testing, geotechnical laboratory testing, engineering evaluation and report preparation.

#### 2.0 PROJECT INFORMATION

#### 2.1 Project Description

The subject site is located along Back River Neck Road between East Homberg Avenue and Mizells Road in Baltimore County, Maryland. The project consists of the construction of a new 16,000 foot long 24-inch water main which will replace the existing 16-inch and 24-inch mains. The new main will be constructed at a depth between 4 feet and 8 feet below the existing ground surface generally near the center of the roadway. The project location is shown on **Plate 1, Site Vicinity Map.** 

#### 2.2 Site Geology

The Geologic Map of the Middle River Quadrangle, MD (1977) indicates that Back River Neck Road is mostly underlain by clay facies soils of the Patapsco Formation. The road is underlain by sand facies soils of the Patapsco Formation between Tripgate Road and Alconbury Road. Generally, the Patapsco Formation is part of the Cretaceous age Potomac Group.

The clay facies soils generally consist of gray, brown, black, or red kaolinitic and illitic Clay with local pods and lenses of quartz Sand. The clay is typically poorly bedded to massive with occasional color mottling. It can contain sparse to abundant, irregular siderite concretions and lignitized wood.

The sand facies generally consists of well-sorted, fine- to medium-grained quartz Sand with locally abundant quartz gravel and clay clasts. The sands are commonly planar to high-angle cross-bedded and in places exhibit a fining-upward sequence.

#### 3.0 METHODS OF EVALUATION

#### 3.1 Subsurface Explorations

**Geotechnical** - Balter's subsurface exploration program for this study included (37) Standard Penetration Test (SPT) borings, numbered B-1 through B-37. The study also included (18) pavement cores (PC-1 to PC-18). Due to time and budget constraints; however, only 11 of the 18 pavement cores were completed.

The boring and core locations were selected and marked in the field by WTB. Utilities were cleared by Miss Utility and the use of Ground Penetrating Radar. Borings were offset as needed to avoid underground utilities or obstructions.

Once the utility locating services were completed, the soil borings were advanced to a maximum depth of 12 feet below the existing ground surface utilizing a truck-mounted CME 45 drill rig equipped with conventional 3.25-inch I.D. hollow stem augers with a 7.25-inch diameter carbide drill head bit. The borings were drilled under restricted work hours between June 4 and 12, 2015. Traffic control was provided by Allied Contractors, Inc. The attached **Boring Location Plans, Plates 2 to 10,** indicate the approximate drilled locations of the borings performed along the roadway. Surface elevations were estimated using in-house topographic maps.

Standard Penetration Testing (SPT) and sampling were performed through the auger stem continuously at 2-foot intervals to the full boring depth. The testing and sampling procedures were performed in accordance with ASTM D-1586 procedures, using a standard 2-inch O.D. sampling spoon, driven by a 140 pound hammer freely falling 30 inches. The drill rig was equipped with an automatic hammer which requires an approximate correction factor of x1.3 to the recorded N-Values. This correction factor is a conservative assumption based on our review of available literature. This allows comparison to "standard" N values for a less-efficient manual hammer (N60 values, for 60% energy efficiency). Corrected values (N60) are not shown on the boring logs, but were used in any analyses.

Bulk samples of representative soils were recovered from the auger flights for laboratory evaluation of compaction. Upon completion, the boreholes were backfilled with drill spoils, and the pavement opening sealed with cold patch asphalt for safety reasons. The collected pavement cores were returned to our laboratory for photo-documentation. The field work was periodically supervised by a qualified Geotechnical Engineer.

The subsurface data obtained from the explorations are presented in log form in **Appendix A**. Photographs of the cores are provided in **Appendix C**. The numeric values (N-values) shown within the individual boring columns on the Boring Logs indicate the standard penetration resistances, in blows per foot (bpf), or as otherwise noted. N-values are used to provide a quantitative indication of in-place density of non-cohesive soil and the consistency of cohesive soils.

The depths at which water was observed in the uncased holes were recorded during drilling, and upon completion of drilling. Longer term water readings were not feasible as the holes

were immediately backfilled to allow for traffic. The method of classification used in preparing the strata descriptions is based on our interpretation of the Unified Soils Classification System (USCS) and the AASHTO soil classification system. The boring logs show soil classifications and boundaries between soil types. Actual conditions and soil boundaries between boreholes may vary significantly from those assumed. The subsurface data shown on the figures are integral to this report. Separation of the logs from the remainder of the report may lead to misinterpretation of the data by others.

#### 3.2 Laboratory Testing Program

Recovered samples were subjected to laboratory testing to estimate their classifications according to the Unified Soils Classification System and AASHTO Classification System. This testing included sieve gradation analyses and Atterberg limits determinations. Visual classifications of the recovered soil samples were also performed. Pocket penetrometer tests were performed on cohesive samples. In addition, bulk samples from the subject site were evaluated for their compactive properties by Modified Proctor (AASHTO T-180) compacted density versus moisture content relationship tests.

Split spoon samples collected at the proposed invert depths from 16 of the 37 of the borings were collected for corrosion testing. Russell Corrosion selected the borings and depths that required sampling. The collected samples were submitted by Balter to Russell Corrosion for testing. Those test results will be submitted directly to WTB by Russell Corrosion. Tests for natural moisture contents of SPT and bulk samples were performed.

The results of our laboratory testing are presented in **Appendix B** and are summarized in **Table 1** of this report. Moisture testing, pocket penetrometers, percent passing #200 sieve and Atterberg limit test results are included on the boring logs for the subject materials.

#### 4.0 SUBSURFACE CONDITIONS

#### 4.1 Subsurface Materials

The following layering represents the generalized subsurface stratigraphy as noted in our borings:

#### **Layer 1 – Surficial Materials**

Pavement Materials – The existing pavement consisted of bituminous concrete overlying aggregate base at all 37 boring locations and 11 pavement core locations. Table 1 below provides the pavement layer thicknesses measured at each location. The results are listed from north to south along Back River Neck Road.

**Table 1 – Measured Pavement Thicknesses** 

Boring	Total Pavement Thickness (in)	Bituminous Concrete (in.)	Concrete (in)	Aggregate Base (in)
B-1	36.0	12.0		24.0
B-2	36.0	12.0		24.0
PC-1	23.0	13.0		10.0
B-3	36.0	12.0		24.0
B-4	22.0	12.0	10.0	
B-5	30.0	18.0		12.0
PC-2	18.0	10.0	8.0	
B-6	30.0	12.0		18.0
PC-3*	19.0	13.0		6.0
B-7	27.0	21.0	6.0	
B-8	18.0	8.0		10.0
B-9	20.0	8.0		12.0
B-10	28.0	10.0	7.0	11.0
PC-4	22.0	12.0		10.0
B-11	31.0	28.0		3.0
PC-5	20.0	13.0		7.0
B-12	25.0	14.0		11.0
PC-6	22.0	14.0		8.0
B-13	16.0	8.0		8.0
B-14	16.0	8.0		8.0
PC-8	15.0	8.0		7.0
B-15	23.0	9.0		14.0
B-16	22.0	9.0	6.0	7.0
PC-10	16.0	9.0		7.0
B-17	16.0	10.0		6.0
B-18	15.0	8.0		7.0
B-19	12.0	9.0		3.0
PC-12	14.0	9.0		5.0
B-20	12.0	8.0		4.0
B-21	17.0	9.0		8.0
B-22	14.0	8.0		6.0
B-23	15.0	7.0		8.0
B-24	12.0	5.0		7.0
B-25	20.0	10.0		10.0
B-26	21.0	15.0		6.0
B-27	20.0	14.0		6.0
B-28	16.0	11.0		5.0
PC-14	17.0	10.0		7.0
B-29	21.0	14.0		7.0
B-30	21.0	13.0		8.0
B-31	19.0	10.0		9.0
B-32	13.0	7.0		6.0
PC-17	10.0	3.0		7.0
B-33	24.0	9.0		15.0
B-34	20.0	5.0		20.0
B-35	9.0	5.0		4.0
B-36	14.0	5.0		9.0
B-37	14.0	8.0		6.0

<sup>•</sup> No photograph, core in poor condition

Note that two boring locations (B-10 and B-16) exhibited a pavement section of bituminous concrete over an aggregate base over concrete. This section could be present elsewhere; including at the pavement core locations; however, the overlying layers prevented collection of the lowest concrete layer. Detailed information documenting the pavement cores is located in Appendix C.

#### Layer 2 – Fill and Possible Fill Soils

Fill soils were encountered below the pavement materials in 26 of the 37 borings to depths ranging from 4.0 to 10.0 feet below the existing ground surface (elevations EL 32.0 to EL 7.0). Generally, if the soils displayed typical characteristics of fill (i.e., unnatural layers, trash and debris, etc.) then the soils were labeled as fill. If, however, the surficial soils <u>did not</u> have the "typical" appearance of fills, but appear to have different characteristics (color, texture, etc) than the natural soils, then they are referred to as "possible fills." It should also be noted that fill soils can be difficult to identify, and detection may not be possible in the field during construction.

The fill soils generally consisted of Sand (SM, SC, SP-SM), Silt (ML), and Clay (CL, CH). Per AASHTO, the fill soils can be classified as A-2, A-4, A-6, and A-7-6. The fill layer generally displayed SPT N-Values from 2 blows per foot (bpf) to 27 bpf. Pocket penetrometer values collected in the fine-grained soils ranged from 0.5 tons per square foot (tsf) to 4.5 tsf.

One boring, B-11, exhibited a chemical odor (ie, mothballs), which typically indicates the presence of naphthalene, or other petroleum based contaminant or Volatile Organic Compounds (VOCs). The samples were screened with a Photo Ionization Detector (PID) which indicated no detection (ie, PID=0.0 ppm). As directed by WTB, environmental testing of the samples was not performed. The main concerns of the presence of potentially contaminated soils are the potential temporary exposure to the site workers during construction, particularly in a confined space condition (ie, trench), and the need for special techniques and disposal, at additional cost.

#### **Layer 3 – Patapsco Formation Soils**

Natural soils of the Patapsco Formation (sand and clay facies) were encountered in all 37 of the borings underlying the pavements and fills to the maximum explored depth. The natural Patuxent Formation soils generally consisted of Sand (SM, SC), Silt (ML) and Clay (CL). Per AASHTO, these soils consist of A-2, A-2-4, A-4, A-6, and A-7-6. SPT N-values ranged from 2 bpf to 30 bpf. Penetrometer values ranged from 0.2 tsf to 4.5 tsf.

#### 4.2 Standard Penetration Resistances

**Figure 1** shows the distribution of the collected  $N_{60}$ -values, of fill, residual soils, and decomposed rock versus depth across the site.

N<sub>60</sub> Values (blows per foot) 0 10 25 35 40 45 50 0 15

Figure 1 - Standard Penetration Resistances

◆ Fill × Patapsco Formation

#### 4.3 Laboratory Test Results

The completed laboratory tests performed on samples of the subsurface materials are summarized on the following Table 2 - Laboratory Test Results. The full laboratory results are presented in graphic form in Appendix B. The corrosivity tests are being performed and submitted to WTB by Russell Corrosion.

Table 2 - Laboratory Test Results

					, I Cot	Itcourt						
	Ca1a				In-	Atterberg Limits		Atterberg Limits		Passing		ed Proctor -180)
Boring No.	Sample Depth (ft)	Soil Type <sup>(1)</sup>	USCS Class.	AASHTO Class.	Place <sup>(2)</sup> Moisture (%)	LL	PL	PI	# 200 Sieve (%)	Max Dry Density (pcf)	Opt Moisture Content (%)	
B-1	3-6	F	CL	A-6	13.6	33	17	16	71.4	130.7	9.8	
B-2	4.5-6	F	CL	A-6	28.3	32	18	14	82.2			
B-5	8-10	F	CL	A-7-6	31.6	45	19	26	80.1			
B-7	0-5	F	CL	A-6	19.1	31	18	13	84.6	124.6	11.6	
B-13	8-10	A	SM	A-2-4	17.3	$NP^3$	NP	NP	13.9			
B-17	8-10	A	CL	A-4	26.8	28	18	10	96.3			
B-21	3-6	F	CL	A-6	17.5	29	17	12	69.2	128.9	9.9	
B-24	6-8	A	CL-ML	A-4	24.5	21	17	4	75.6			
B-27	4-6	A	CL-ML	A-4	28.7	28	21	7	71.4			
B-35	2-5	A	CL	A-6	18.5	29	17	12	73.4	127.1	9.8	

- **Notes:** (1) F = Fill, A = Alluvial
  - (2) Refer to Boring Logs for additional Soil Moisture Contents.
  - (3) NP = Non-Plastic

Natural moisture contents were performed on selected soil samples obtained from the borings. The moisture contents ranged from approximately 5.2 to 31.6 percent. The optimum moisture content of the samples tested ranged from 9.8 to 11.6 percent.

#### 4.4 Ground Water Conditions

Because the fieldwork involved lane closures, all 37 borings were immediately backfilled on completion; therefore, stabilized borehole observations could not be made. Based on measurements at completion, groundwater was encountered in 6 of the 37 borings (B-8, B-10, B-29, B-30, B-34, and B-35) at depths ranging from 3.0 feet to 8.2 feet below the existing ground surface (approximate elevations EL 23.4 to EL 8.0). Stabilized water levels would be different than the at-completion levels. The remaining borings were dry at completion which does not suggest that water is not present, but that it was not encountered in the boring.

The presence of the water in the borings at-completion suggests that ground water could affect future construction of the new water main. The contractor should anticipate shallow water conditions and be prepared to dewater during construction.

Ground water levels generally fluctuate with rainfall and runoff, and may be affected by rainfall, construction, utility leaks, and other natural and unnatural causes. For these reasons, the ground water levels across the site at later dates will vary from those noted during the recent exploration program.

#### 5.0 EVALUATIONS AND RECOMMENDATIONS

#### 5.1 General

The proposed construction addressed in this report includes the excavation of the water pipe trench, preparation of the water main subgrades, and trench backfill. Pavement design is not a part of the scope of this work. The geotechnical design and construction implications for the proposed construction are in the sections below.

#### 5.2 Trench Excavation

We have assumed that all of the water main will be installed utilizing the open trench method. The anticipated water line will be installed between 4.0 and 8.0 feet below the existing ground surface. Based on the conditions encountered in the soil borings we anticipate that the trench can be excavated to the anticipated depths utilizing standard excavation equipment.

It must be noted that a chemical odor (mothballs) was noted in boring B-11 in the upper 7.0 feet. The soil samples were screened with a PID, which did not indicate any level of contamination (ie, PID=0.0 ppm). As directed by WTB, no laboratory testing was performed on the noted samples. In our experience, a mothball odor typically suggests the presence of petroleum-based contaminants (ie, naphthalene, etc.), or possible volatile organic compounds (VOCs). The main concern with the presence of any level of contamination is the impact to the site workers during construction. Appropriate personnel protection equipment and techniques should be considered. Another concern is the suitability of the soils for reuse as

backfill, or appropriate disposal, if required. WTB's environmental professional should review the collected data and determine the appropriate course of action.

#### 5.3 Ground Water Control

Based on the measured at-completion water levels recorded in the borings, ground water was encountered in 6 of the 37 borings at depths ranging from 3.0 feet to 8.2 feet below the existing ground surface (approximate elevations EL 23.4 to EL 8.0). It should be noted; however, that no long term stabilized ground water data could be collected, as the borings were backfilled within 0.5 hours after drilling. The measured water levels are generally within the proposed excavation and pipe zone; therefore, it should be anticipated that water will impact the construction of the water main.

At the boring locations that indicated dry conditions, many of the subsurface soils exhibited very high natural moisture contents at the invert depths (up to 32%). These very high natural moistures are located in fine-grained soils and could represent perched water conditions. Because of the fine-grained nature of many of these soils, if the water is perched, or trapped, in these soil layers, seepage may occur very slowly into the excavation.

Depending on the construction methods utilized and conditions at the time of construction, water could accumulate in the trench or manhole excavations and may require sump pits and pumping, well pits or other water control measures. The contractor must be prepared to dewater if necessary.

#### 5.4 Bearing Pressures

Based on the conditions encountered in the soil borings, the water main subgrades are expected to consist of very soft to very stiff Silt and Clay, and loose to medium dense Sand throughout the section. These soils consist of both existing fills and natural alluvial soils. The natural and fill soils encountered along the majority of the water main alignment are expected to be able to support the proposed water main; however, undercutting may be necessary at some locations, including near borings B-24, B-27, and B-34.

In the event that soft or yielding soils are encountered along the water main, localized undercutting may be required. Unsuitable soils that require undercut should be replaced with suitable imported granular materials, such as a MDSHA #57 stone or CR-6 protected with a geotextile. It must be noted that undercuts could be affected by ground water. The contractor must be prepared to dewater in the event ground water is encountered. If encountered, we recommend that the backfill consist of MDSHA #57 stone.

For those structures that will bear within the underlying fills, or natural alluvial soils (including manholes, valve structures, etc.), an allowable bearing pressure of 2,000 PSF may be used in design.

#### 5.5 Lateral Pressures for Structure Design

The design of the subsurface structures associated with the water main, including manhole structures, valve structures, etc. must consider the effects of lateral earth pressures. Although



Coefficient of Base Sliding Friction

no groundwater was encountered in the borings in the proposed water main invert zone, seepage of water downward and along the pipeline must be taken into account. For design of the subsurface structures, the following soil lateral load parameters may be used.

 $\begin{array}{ll} \mbox{Internal Angle of Friction} & \Phi = 28^{o} \\ \mbox{Compacted soil moist unit weight} & \gamma_{t} = 140 \ pcf \\ \mbox{Buoyant soil unit weight} & \gamma_{b} = 78 \ pcf \\ \mbox{Active Pressure Coefficient (deflection-allowed)} & K_{a} = 0.36 \\ \mbox{At-rest Pressure Coefficient (restrained)} & K_{o} = 0.53 \\ \mbox{Passive Pressure Coefficient} & K_{p} = 1.38^{(1)} \\ \end{array}$ 

**Table 3 – Soil Lateral Load Parameters** 

**Notes:** (1) Due to the large amount of movement necessary to mobilize the maximum passive resistance, we have applied a reduction factor of 0.5 to the passive parameters, to limit movements.

0.39

Backfill of the structures should be performed as described below in Section 5.6. It is important to properly backfill around all subsurface structures as required by MDSHA and Baltimore County.

#### 5.6 Earthwork

In accordance with Baltimore County Department of Public Works Standard Specification for Construction and Materials (February 2000), the water main is to rest on undisturbed earth at the bottom of the trench. The remainder of the trench is to be backfilled with suitable compacted soils.

The soils expected along the water main generally consist of SM, SC, CL, ML, and CL-ML. The fine-grained soils that will be excavated from the trench generally have liquid limits less than 40 and plastic indexes less than 15. The laboratory determined natural moistures indicate that these soils have natural moisture contents from 5.2% to 31.1%, with an average of 20.4%. The average natural moisture is approximately 10% over the average optimum moisture content of these soils, as determined by AASHTO T-180. In our opinion, these soils could be reused for controlled backfill, provided they can be dried. If drying of the soils is not feasible, then imported soils will be required. Another option could be to modify them by mixing a low percentage of cement or lime (3-5%) into them, if space allows for this operation onsite. This would reduce the moisture content for reuse as backfill material.

The presence of the contamination odor in boring B-11 is a concern. The odors and potential contamination encountered could affect site workers during construction. Even if these soils are removed from the site, it does not remove the potential for harmful vapors that could remain within the trench. Environmental recommendations are not a part of our scope. Therefore, the reported data should be reviewed by an environmental professional to develop appropriate safety recommendations for working in the trench as well as suitability of these soils for reuse as compacted backfill in the trench.

According to Baltimore County specifications, any imported borrow material used in trench backfill shall be a granular soil with a maximum of 35% passing the No. 200 sieve. Balter would also recommend that any imported borrow material have a liquid limit less than 40 and a maximum plasticity index of 10.

The imported borrow soils should be placed around the pipe in maximum 6-inch layers to a depth of 2 feet over the pipe and compacted to a minimum of 92% of the maximum dry density as determined by AASHTO T-180. Backfill should then be placed in maximum 8-inch layers and compacted to a minimum of 92% of AASHTO T-180 to within the top 1.0 foot of subgrade. The top 1.0 foot should be compacted to a minimum of 95% of the maximum dry density as determined by AASHTO T-180.

As per Baltimore County standard specifications, prior to placing any base course material and after the in-situ material has been properly compacted the sub-grade shall be inspected. If additional subgrade preparation is required then the following procedures may be used:

- 1. Undercut the trench backfill 1.0 foot.
- 2. Place soil reinforcing fabric, such as Mirafi 500X or equal over the undercut and replace with a compacted Aggregate Base Course.

#### 5.7 Lateral Pressures for Sheeting Design

Temporary shoring will be necessary to support the side walls of the water main trench. The sheeting system will be subject to lateral earth pressures, which will vary depending on the shoring type, water conditions, and backfill materials utilized. We recommend the following soil parameters be used for <u>preliminary</u> design of all temporary earth support. Hydrostatic pressures and any surcharge loads must also be included in the shoring design. *Note that the contractor must be responsible for the final design of such systems*.

Table 4 - Estimated Soil Parameters for Preliminary Shoring Design

Layer	Soil Type	Cohesion (psf)	Ф (°)	Moist Unit Weight (pcf)	Buoyant Unit Weight (pcf)
Silt/Clay/Sand Soils	ML/CL/SM/SC	0	28	140.0	78.0

#### 5.8 Corrosion Potential

For corrosion testing, SPT samples were collected from the proposed pipe depths between 4 and 8 feet below the existing ground surface. A total of 33 samples from 16 borings were provided to Russell Corrosion for corrosion testing. They will provide an evaluation of the corrosion potential in a separate report. Balter was solely responsible for providing the corrosion samples to Russell. The corrosion results were not provided to us.

### 5.9 Pavement Repairs

No pavement design analyses or CBR testing have been performed. We have assumed that the existing pavement will be matched after trench backfill is complete. All materials and methods used in the pavement repairs should conform to the appropriate Maryland State Highway Administration and Baltimore County requirements.

#### 6.0 GEOTECHNICAL OBSERVATION AND TESTING

As variations in soil conditions can be expected to some degree on any project, it is important that The Robert B. Balter Company provide full time, on-site observation and testing of all soil related aspects of construction. This is to assure compliance with design concepts and recommendations, and to verify that the subsurface conditions are consistent with those anticipated prior to construction. The services shall include observation and testing of all undercutting, utility backfill, placement of pavement materials, and any other soil related activities.


Additionally, in accordance with good construction practice and continuity of inspection, it is recommended that the on-site construction monitoring services also encompass the structural aspects of the project, such as concrete placement and paving procedures.


#### 7.0 GENERAL COMMENTS

The evaluations and recommendations contained in this report were based upon the finite data obtained from the borings that are presented within this report. Although we have described typical variations that may affect the project, there is the possibility that significant unanticipated conditions may be present outside the specific boring locations. The nature and extent of differing subsurface conditions, as well as their impact on the proposed construction, will most likely not be evident until the time of construction. If significant differences are discovered in the field during construction, it may be necessary for us to re-evaluate and revise the contents of this report.

Our recommendations and conclusions are based upon the limited project parameters provided to us at the time of this report. We reserve the right to modify our conclusions and recommendations if substantial changes are incorporated into the project. Further, it is essential that we be provided the opportunity to review appropriate sections of the plans and specifications for the project before they are finalized to assure that our recommendations have been appropriately applied to the design.

This report specifically excludes exploration, sampling, testing, evaluation and recommendations relating to the presence of hazardous materials or other environmental concerns that could affect future development of the site. The Robert B. Balter Company performs these services and would be pleased to provide a proposal to address your needs.








**Geotechnical Evaluation Back River Neck Road Main Replacement Baltimore County, Maryland** 


Boring Loca	Project No. 16613-0	
<sub>91</sub> Scale: 1" ~ 70'	Date: July 2015	PLATE 2



THE ROBERT B. BALTER COMPANY®
Geotechnical and Geo-environmental Engineers

Geotechnical Evaluation
Back River Neck Road Main Replacement
Baltimore County, Maryland


Boring Loca	Project No. 16613-0	
<sub>92</sub> Scale: 1" ~ 70'	Date: July 2015	PLATE 3



THE ROBERT B. BALTER COMPANY® Geotechnical and Geo-environmental Engineers

**Baltimore County, Maryland** 


Boring Loca	Project No. 16613-0	
93 Scale: 1" ~ 70'	Date: July 2015	PLATE 4





Back River Neck Road Main Replacement
Baltimore County, Maryland


Boring Loca	Project No. 16613-0	
94 Scale: 1" ~ 70'	Date: July 2015	PLATE 5




THE ROBERT B. BALTER COMPANY® Geotechnical and Geo-environmental Engineers

**Baltimore County, Maryland** 

95 Scale: 1" ~ 70' Date: July 2015 PLATE 6







THE ROBERT B. BALTER COMPANY® Geotechnical and Geo-environmental Engineers

**Back River Neck Road Main Replacement Baltimore County, Maryland** 

97 Scale: 1" ~ 70' Date: July 2015 PLATE 8








Geotechnical Evaluation
Back River Neck Road Main Replacement
Baltimore County, Maryland

Boring Loca	Project No. 16613-0	
98 Scale: 1" ~ 70'	Date: July 2015	PLATE 9



THE ROBERT B. BALTER COMPANY® Geotechnical and Geo-environmental Engineers

**Baltimore County, Maryland** 

99 Scale: 1" ~ 70' Date: July 2015 PLATE 10

## APPENDIX A – BORING LOGS

## THE ROBERT B. BALTER COMPANY IDENTIFICATION OF SOIL SAMPLES

Soils are described in the boring logs according to the following criteria with the principal constituents written in capital letters. Other constituents are preceded by descriptive terminology that is used to denote the percentage of weight of each component. Soil descriptions are determined visually except where laboratory classification test data are available. Classifications are based on The Robert B. Balter Company's interpretation of ASTM D 2487-00.

		0 to 50/ Finas	Well Graded		GW	GRAVEL
		0 to 5% Fines	Poorly Graded		GP	GRAVEL
			City Divers	Well Graded	GW-GM	GRAVEL with Silt
	EL	6 to 12% Fines	Silty Fines	Poorly Graded	GP-GM	GRAVEL with Silt
. , e	AV	6 to 12% Fines	Classes Finan	Well Graded	GW-GC	GRAVEL with Clay
OII Siev	GRAVEL		Clayey Fines	Poorly Graded	GP-GC	GRAVEL with Clay
COARSE GRAINED SOIL > 50% Retained on No. 200 Sieve	•		Silty Fines		GM	Silty GRAVEL
Ze. 2		13 to 50% Fines	Silty Clay Fines	S	GC-GM	Silty, Clayey GRAVEL
AII on A			Clayey Fines		GC	Clayey GRAVEL
GR ned (		0 to 5% Fines	Well Graded		SW	SAND
SE estair		0 to 3/6 Filles	Poorly Graded		SP	SAND
<b>4 R</b> 6		6 to 12% Fines	Silty Fines	Well Graded	SW-SM	SAND with Silt
3 <b>0</b> /	Ω		Sitty Filles	Poorly Graded	SP-SM	SAND with Silt
_ ^	SAND		Clayey Fines	Well Graded	SW-SC	SAND with Clay
			Clayey Filles	Poorly Graded	SP-SC	SAND with Clay
		13 to 50% Fines	Silty Fines		SM	Silty SAND
			Silty, Clayey Fines		SC-SM	Silty, Clayey SAND
		Clayey Fines			SC	Clayey SAND
, e		Low Plastic Fines, PI<4	Plots below "A	" line	ML	SILT
OII Siev	SILT & CLAY (ILL<50)	Low Plastic Fines, 4≤PI≤7	Plots on or above	ve "A" line	CL-ML	Silty CLAY
003 000	LT	Plastic Fines, PI>7	Plots on or above	ve "A" line	CL	Lean CLAY
VEI Io. 2		Significant Organics, PI<4	Plots below "A	" line	OL	Organic SILT
AIN ng N		Significant Organics, PI≥4	Plots on or above	ve "A" line	OL	Organic CLAY
FINE GRAINED SOIL	.» . e	Elastic Fines	Plots below "A	" line	MH	Elastic SILT
IE (	SILT & CLAY (LL≥50)	Plastic Fines	Plots on or above	ve "A" line	СН	Fat CLAY
FIN 50%	i di	Significant Organics	Plots below "A	" line	ОН	Organic SILT
		Significant Organics	Plots on or above	ve "A" line	ОН	Organic CLAY
HIGHLY ORGANIC SOIL		Dark, highly organic, decomp	posed vegetative t	issue	PT	PEAT

#### ADDITIONAL TERMINOLOGY:

**Descriptive Components** 

Descriptive Terms	Proportions
Trace	1 - 5%
Little (Sand, Gravel)	6 - 14%
With (Sand, Gravel)	15 – 30%
With (Silt, Clay)	6 – 12%
Adjective Form (Sandy, Gravelly)	31 - 50%
Adjective Form (Silty, Clayey)	13 - 50%

**Density or Consistency** 

SAND	and GRAVEL	SILT and CLAY		
N-Value	N-Value Density		Consistency	
0-4	Very Loose	0-1	Very Soft	
5-10	Loose	2-4	Soft	
11-30	Medium Dense	5-8	Medium Stiff	
31-50	Dense	9-15	Stiff	
> 50	Very Dense	16-30	Very Stiff	
		> 30	Hard	

**Fill** materials are placed by man, and may be identified by unnatural artifacts, unnatural mixed grain sizes or layering, or trustworthy documentation of fill placement.

Possible Fill materials are difficult to distinguish from natural soils, exhibiting minor distinctions.

**Decomposed Rock** consists of residual soil with SPT N-values between 50 blows per foot and blows per 4 inches (50/4"). **Highly Weathered Rock** consists of residual soil with SPT N-values between 50/3" and 50/1".

#### The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

#### **BORING LOG**

**BORING B-1** 

PAGE 1 OF 1

**CLIENT** The Wilson T. Ballard Company PROJECT NAME Back River Neck Road Water Main Replacement PROJECT LOCATION Baltimore County, Maryland PROJECT NUMBER 16613-0: MD **DATE TESTED** 6/26/2015 **METHOD** Hollow Stem Auger **RIG** Truck CME 45 SAMPLER: 2-in OD SS HAMMER: 140# FALL: 30" AUTO? Yes WATER LEVELS **DATE STARTED** 6/4/15 COMPLETED 6/4/15 WATER DEPTH (ft) ELAPSED HOLE WATER CASING DATE TIME DEPTH (ft) DEPTH (ft) HOURS ELEV (ft) DRILLER Dennis Strawderman **HELPER** Dustin Hurd 6/4/15 0 🗸 8.0 Dry **REVIEWED BY** Kristopher Crist SITE DELAYS LOCATION As Staked BULK SAMPLES 3-6' STRATUM CHANGE DEPTH/EL (ft) SAMPLE TYPE AND NUMBER SPT BLOWS/6" OR REC IN/IN 9 GRAPHIC LOG **WATER LEVEL** N VALUE OR CORE RQD **MATERIAL** REMARKS DEPTH (ft) DESCRIPTION (tst) **ATTERBERGS** USCS - #200 NMC SURFACE EL = 28.0 ft ы PΙ Bituminous Concrete (12-inches) 1.0 27.0 Aggregate Base (24-inches) 3.0 14 71 17 33 16 S1 11-7-9 16 25.0 Moist, Medium Dense, Brown to Red-Brown Silty, Clayey SM SAND (Fill) [A-2] 5 4-4-9 24.0 Moist, Stiff, Brown Sandy CLAY (Fill) [A-6] S2 13 CL 4.50 8 6.0 22.0 Moist, Very Stiff, Brown-Gray to Brown Sandy CLAY 10-12 S3 24 4.10 [A-6] 12-14 4-8-CL 4.50 S4 18 10-12 10 (1) 5-10-S<sub>5</sub> 22 4.00 12-14 12.0 16.0 Terminated at 12 0 feet **REMARKS**: (1)Boring Backfilled at completion for safety purposes

**BORING B-2** 

PROJECT NAME Back River Neck Road Water Main Replacement

PAGE 1 OF 1

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**CLIENT** The Wilson T. Ballard Company

PROJ	ECT LOC	ATION	Baltir	more (	County	, Mary	/lan	d	PROJECT N	NUMBER	16613-0: N	ID DA	TE T	ESTE	6/2	6/2015	5	
RIG _	IG Truck CME 45 METHOD Hollow Stem Auger SAMP							Stem Auger SAMPLE	<b>R:</b> 2-in OD	SS	HAI	/MER: _	140#	FAL	L: _30	) <u>"</u> Al	JTO?	Yes
DATE	DATE STARTED         6/4/15         COMPLETED         6/4/15										WA ELAPSED	TER LEV	ELS	UOI E	100	/ATER	10/4	ATER
DRILL	ER Den	nis Stra	awdern	nan	HE	ELPE	<b>ર</b> _[	Dustin Hurd	DATE	TIME	HOURS	CASING DEPTH (	ft) DE	PTH (f	t) DE	PTH (ft	ELE	EV (ft)
REVIE	WED BY	Kristo	opher C	Crist	SI	TE DE	LA	YS	6/4/15		0 ∑			8.2		Dry		
LOCATION As Staked								ULK SAMPLES										
DEPTH (ft)	SAMPLE TYPE AND NUMBER	SPT BLOWS/6" OR REC IN/IN %	N VALUE OR CORE RQD	STRATUM CHANGE DEPTH/EL (ft)	GRAPHIC LOG	nscs	WATER LEVEL	SURFACE EL = 25.0 f		l		PP (tsf)	NMC %	- #200	ATT PL	ERBEI LL	RGS Pl	REMARKS
 				1.0 24.0 3.0				Bituminous Concrete (1 Aggregate Base (24-inc	ches)	AND (FIII)								
 5	S1	10-7-9	16	22.0 4.5	F	SM		Moist, Medium Dense,		, ,			11					
	S2	1-1-1	2	20.5	F	CL		Wet, Soft, Gray-Brown		, ,	[A-6]	0.70	28	82	18	32	14	
	S3	3-5-5	10	19.0		SM		Moist, Loose, Brown Sil	ity SAND [A	\-2]			15					
10	S4	5-9- 11-13	20	17.0		SC		Moist, Medium Dense,					16					(1)
	S5	5-10- 12-14	22	15.0 12.0		CL		Moist, Very Stiff, Red-B fragments [A-6]	rown Sandy	/ CLAY, tra	ace rock	4.50	18					(1)
				13.0				Termin	nated at 12.	0 feet								

**REMARKS**: (1)Boring backfilled at completion for safety purposes.

NEW GEOTECH BH LOG 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/14/15

103

# The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com **BORING LOG**

BORING B-3
PAGE 1 OF 1

CLIENT _The Wilson T. Ballard Company	PROJECT	NAME Ba	ck River Ne	ck Road	Wate	er Mair	n Repla	aceme	nt	
PROJECT LOCATION Baltimore County, Maryland	PROJECT	NUMBER	16613-0: N	ID DA	ATE T	ESTE	D			
RIG Truck CME 45 METHOD Hollow Stem Auger SAMPLE	<b>ΞR</b> : <u>2-in Ο</u> [	O SS	HAN	MER: _	140#	FAL	. <b>L</b> : _30	<u> </u>	TO?	Yes
<b>DATE STARTED</b> 6/4/15 <b>COMPLETED</b> 6/4/15		I	WA <sup>*</sup> ELAPSED	TER LEV	ELS	HOI E	\ \ \	ATER	WATE	
DRILLER         Dennis Strawderman         HELPER         Dustin Hurd	DATE	TIME	HOURS	CASING DEPTH (	ft) DE		- 1	PTH (ft)	ELE	V (ft)
REVIEWED BY Kristopher Crist SITE DELAYS	6/4/15		0 ∑			8.4		Dry		
LOCATION As Staked BULK SAMPLES 3-6'										
BULK SAMPLES 3-6'	MATERIAL ESCRIPTION  ft (12-inches) nches) own Sandy Communication of the second standard second sec	CLAY, trace CLAY, trace y CLAY [A	e broken [A-6]	2.50 1.50 1.40 3.90 4.20	NMC %	- #500		ERBEF	RGS PI	(I) REMARKS
DEMARKS: (4) Devines healifilled at accordation for a fet and										
REMARKS: (1)Boring backfilled at completion for safety purp	oses.									

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-4** 

PAGE 1 OF 1

CLIEN	T The \	Wilson 1	T. Balla	ard Co	mpany	У			PROJECT	NAME Ba	ack River Ne	ck Road	Wat	er Mai	n Repl	aceme	ent	
PROJE	ECT LOC	ATION	Baltir	more C	County	, Mar	ylan	<u>d</u>	PROJECT	NUMBER	16613-0: M	<u>D</u> <b>D</b> /	ATE I	ESTE	D			
RIG _1	Truck CN	1E 45		_ ME	THOE	Hol	low	Stem Auger SAMPLE	<b>R</b> : 2-in OE	) SS	HAM	IMER:	140#	FAL	L: _3	<u>0"</u> Al	JTO?	_Yes
DATE	STARTE	<b>D</b> 6/4	/15		_ c	OMPL	ETE	<b>ED</b> 6/4/15			WAT	ER LEV	ELS			ED		
DRILLI	ER Der	nnis Str	awdern	nan	_ н	ELPE	R _I	Dustin Hurd	DATE	TIME	ELAPSED HOURS	CASING DEPTH (	ft) D	HOLE EPTH (1	t) DE	VATER PTH (ft	) ELI	ATER EV (ft)
REVIE	WED BY	Kristo	opher C	Crist	S	ITE DI	ELA	YS	6/4/15		0 ∑			8.4		Dry		
	TION A							SULK SAMPLES										
				ш			П											
DEPTH (ft)	SAMPLE TYPE AND NUMBER	SPT BLOWS/6" OR REC IN/IN %	N VALUE OR CORE RQD	STRATUM CHANGE DEPTH/EL (ft)	GRAPHIC LOG	nscs	WATER LEVEL		MATERIAL SCRIPTION ft	1		PP (tsf)	NMC %	- #200	ATT PL	ERBE	RGS PI	REMARKS
				1.0				Bituminous Concrete (	12-inches)									
L ↓				37.0 1.8	PAA		Н	Concrete (10-inches)	. OU.T.(E''	1) [A 4]		_						
	S1	4-4-6- 7	10	36.2		ML		Moist, Stiff, Brown Sar	idy SILT (Fil	I) [A-4]		2.50						
┝╶╂	<del></del>	-		4.0 34.0			Н	Moist, Stiff, Dark Gray-	Brown Sand	HV CLAY (F	-iII) [Δ_6]							
5	S2	4-4-7- 9	11		F	CL		Wolst, Othi, Dark Oray	Diowii Gan	ay OLAT (I	III) [A-0]	3.00						
┞	7	7-8-8-		6.0 32.0				Moist, Very Stiff to Med	dium Stiff, G	ray Sandy	CLAY [A-6]							
	S3	10	16					•				2.30						
	S4	4-4-5-	9			CL						1.70						
10	<u> </u>	6						1944 1 1 + 40	•									(1)
	S5	3-3-3- 4	6	12.0				little sand lenses at 10				1.00						
				26.0	<i>2.77.77</i>			Term	inated at 12	.0 feet								
REM/	ARKS: (1	l)Borii	ng ba	ckfill	with	drill s	spo	ils at completion fo	r safety p	urposes								

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-5** 

PAGE 1 OF 1

CLIEN	The \	Wilson '	T. Balla	ard Co	mpany	У			PROJECT	NAME Ba	ack River Ne	ck Road	l Wate	er Maii	n Repl	aceme	ent	
PROJ	ECT LOC	ATION	Baltir	more (	County	, Mar	ylan	<u>d</u>	PROJECT NUMBER 16613-0: MD DATE T						TESTED 6/26/2015			
RIG _	Truck CN	1E 45		_ ME	THOE	Hol	low	Stem Auger SAMPL	<b>ER</b> : 2-in O[	O SS	HAN	MER:	140#	FAL	L: <u>3</u>	<u>)"</u> A	JTO?	Yes
DATE	STARTE	<b>D</b> 6/5	/15		_ c	OMPL	ETE	<b>ED</b> <u>6/5/15</u>		I	WA <sup>-</sup> ELAPSED	TER LEV	/ELS	HOLF	V	VATER	□ w	ATER
DRILL	.ER Der	nnis Str	awdern	nan	_ н	ELPE	R _I	Oustin Hurd	DATE	TIME	HOURS	CASING DEPTH	(ft) DE		t) DE	PTH (ft	) ELÍ	EV (ft)
REVIE	WED BY	Kriste	opher C	Crist	S	ITE DI	ELA	YS	6/5/15		0 ∑			7.6		Dry		
LOCA	TION A	s Stake	ed				Е	BULK SAMPLES 3-6'	-									
DЕРТН (ft)	SAMPLE TYPE AND NUMBER	SPT BLOWS/6" OR REC IN/IN %	N VALUE OR CORE RQD	STRATUM CHANGE DEPTH/EL (ft)	GRAPHIC LOG	nscs	WATER LEVEL	DE SURFACE EL = 36.0	MATERIAL ESCRIPTION	N		PP (tsf)	NMC %	- #200	ATT PL	ERBE	RGS PI	REMARKS
				1.5				Bituminous Concrete	(18-inches)									
				34.5				Aggregate Base (12-ir	nches)									
-	S1	5-6-6	12	33.5	F			Moist, Stiff to Medium Sand (Fill) [A-6]	Stiff, Gray C	Gravelly CL	AY with		24					
5	S2	4-4-4	8			CL		cana (i iii) į v oj					19	-				
	A 9-			6.0														
 	S3	5-4-3- 2	7	30.0	F	SM		Moist, Loose, Tan Gra					11					
 _ 10	S4	1-2-2- 2	4	28.0	F	CL		Wet, Soft, Gray-Brown	n CLAY with	Sand (Fill)	[A-7-6]		32	80	19	45	26	(1)
	S5	2-2-3- 3	5	26.0		CL		Wet, Medium Stiff, Bro	own-Gray Sa	andy CLAY	[A-7-6]	1.00	30					(1)
				24.0				Term	ninated at 12	.0 feet								
REM	ARKS: (1	l)Borii	ng ba	ckfille	ed wi	th dr	⊔ ill s	poils at completior	n for safet	y purpos	es.			1				

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-6** 

PAGE 1 OF 1

	CLIEN	The \	Wilson '	T. Balla	ard Co	mpan	у			PROJECT NAME Back River Neck Road Water Main Replacement									
	PROJ	ECT LOC	ATION	Baltir	more (	County	, Mar	ylan	nd	PROJECT									
	RIG _	Truck CN	1E 45		_ ME	THO	Hol	llow	Stem Auger SAMPLE	<b>R</b> : 2-in Ol	D SS	HAI	MMER:	140#	FALL	.: <u>30</u>	) <u>"</u> AU	ITO?	_Yes
	DATE	STARTE	<b>D</b> 6/5	/15		c	OMPL	ETI.	<b>ED</b> <u>6/5/15</u>			WA ELAPSED	TER LEV	/ELS	HOLE	l w	ATER	W	ATER
	DRILL	<b>ER</b> Der	nis Str	awdern	nan	_ н	ELPE	R _	Dustin Hurd	DATE	TIME	HOURS	DEPTH	(ft) D	EPTH (ft)	DE	PTH (ft)	ELI	EV (ft)
	REVI	EWED BY	Kriste	opher (	Crist	s	ITE DI	ELA	YS	6/5/15		0 ∑			8.2		Dry		
	LOCA	TION A	s Stake	ed				E	BULK SAMPLES										
5 16613-0 BACK RIVER NECK ROAD WATER MAIN. GPJ MTA REDLINE, GDT 7/14/15	DEPTH (ft)	SAMPLE TYPE  SAMPLE TYPE  AND NUMBER  S2  S3  S4  S2  S2  S3  S4  S5	"9/SMAT BLOWS/15 A	9 9 14 7 CORE ROD	1.0 32.0 30.5 5.0 28.0 12.0 21.0 12.0 21.0	GRAPHIC LOG	SDSN CL CL CL	WATER LEVEL	Bituminous Concrete (*Aggregate Base (18-in: Moist, Stiff, Gray Sand Moist, Stiff, Gray-Brow fragments, little plastic Moist, Stiff, Gray-Brow Slightly Wet, Medium S [A-6] Moist, Stiff, Red-Brown	n Sandy CL fragments n Sandy CL fragments	AY, trace (Fill) [A-6] AY [A-6] Brown Sand		2.50 2.70 1.00 4.50	NMC %	#50	ATTE	ERBEF	RGS PI	(L) REMARKS
NEW GEOTECH BH LOG	REM	ARKS: (1	)Borii	ng ba	ckfille	ed wi	th dri	ill s	spoils at completion		y purpos	ees.	•		<u>'</u>	'	<u> </u>		

**BORING B-7** 

PAGE 1 OF 1

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**CLIENT** The Wilson T. Ballard Company PROJECT NAME Back River Neck Road Water Main Replacement PROJECT LOCATION Baltimore County, Maryland PROJECT NUMBER 16613-0: MD **DATE TESTED** 6/30/2015 **METHOD** Hollow Stem Auger SAMPLER: 2-in OD SS **RIG** Truck CME 45 HAMMER: 140# FALL: 30" AUTO? Yes WATER LEVELS **DATE STARTED** 6/5/15 COMPLETED 6/5/15 WATER DEPTH (ft) ELAPSED HOLE WATER CASING DATE TIME DEPTH (ft) DEPTH (ft) ELEV (ft) HOURS DRILLER Dennis Strawderman **HELPER** Dustin Hurd 6/5/15 0 🗸 8.6 Dry **REVIEWED BY** Kristopher Crist SITE DELAYS LOCATION As Staked BULK SAMPLES 3-6' STRATUM CHANGE DEPTH/EL (ft) SAMPLE TYPE AND NUMBER SPT BLOWS/6" OR REC IN/IN 9 GRAPHIC LOG **WATER LEVEL** N VALUE OR CORE RQD MATERIAL REMARKS DEPTH (ft) **DESCRIPTION** % (tst) **ATTERBERGS** USCS - #200 NMC Ы SURFACE EL = 37.0 ft ы 19 85 Bituminous Concrete (21-inches) 18 31 13 1.8 35.3 Concrete (6-inches) 2.2 MLMoist, Stiff, Brown Sandy SILT (Fill) [A-4] S1 4.50 5-5-6 11 34.8 4.0 Moist, Stiff to Very Stiff, Brown Sandy CLAY (Fill) [A-6] 33.0 5 5-6-7 S2 13 2.70 6 CL 8-9-9 S3 18 3.00 8.0 29.0 Moist, Stiff, Gray-Brown Sandy CLAY [A-6] 5-6-8 CL 2.50 S4 14 7 10 10.0 (1) Slightly Wet, Medium Stiff, Gray-Brown Sandy CLAY 27.0 3-3-3-S<sub>5</sub> 6 CL 1.20 [A-6] 3 12.0 Terminated at 12.0 feet

REMARKS: (1)Boring backfilled with drill spoils at completion for safety purposes.

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-8** 

PAGE 1 OF 1

	The \								PROJECT	NAME Ba	ack River Nec	k Road	Wate	er Mair	n Repl	aceme	ent	
	ECT LOC		Baltir	nore C	County	, Mar	/lan	<u>d</u>	PROJECT	NUMBER	16613-0: ME	<u>D</u>	ATE T	ESTE	<b>_</b>			
RIG _	Truck CN	1E 45		_ ME	THOE	Hol	low	Stem Auger SAMPL	ER: 2-in O	O SS	·	MER: _		FAL	. <b>L</b> : _30	<u>"</u> Al	JTO?	_Yes
DATE	STARTE	<b>D</b> 6/5	/15		_ C	OMPL	ETE	<b>ED</b> <u>6/5/15</u>			WATI	ER LEV	ELS	HOLE	V	/ATER	W	ATER
DRILL	ER Der	nnis Str	awdern	nan	_ н	ELPE	R _	Dustin Hurd	DATE	TIME		CASING DEPTH (	ft) DE		t) DE	PTH (ft	) ELI	EV (ft)
REVIE	WED BY	Kriste	opher C	Crist	SI	TE D	ELA	YS	6/5/15		0 ⊼			8.6		7.6	2	23.4
LOCA	TION A	s Stake	ed				E	BULK SAMPLES										
DEРТН (ft)	SAMPLE TYPE AND NUMBER	SPT BLOWS/6" OR REC IN/IN %	N VALUE OR CORE RQD	STRATUM CHANGE DEPTH/EL (ft)	GRAPHIC LOG	nscs	WATER LEVEL		MATERIAL ESCRIPTION	N		PP (tsf)	NMC %	- #200	ATT	ERBE LL	RGS PI	REMARKS
				0.7 30.3			$\perp$	Bituminous Concrete										
L _				1.5	F		$\vdash$	Aggregate Base (10-ir Moist, Stiff, Brown Sa		AV (Fill) [	Δ_61							
	S1	4-5-7- 9	12	29.5	F	CL		Moist, Still, Diowil Sa	idy, Silty OL	(I III) [/	A-0]	4.20						
 _ 5	S2	2-4-7- 9	11	4.0 27.0 5.5	F	SC		Moist, Medium Dense [A-4]	, Brown Silty	, Clayey S	AND (Fill)							
- 	S3	8-8- 10-11	18	25.5		CL	\ \ \	Moist, Stiff to Very Sti	ff, Brown Sa	ndy CLAY	[A-6]	3.80						
  10	S4	8-18- 12-6	30	8.0 23.0			<u>-</u>	Moist, Medium Dense fragments [A-2]	, Red-Brown	Silty SAN	D, trace rock							
	S5	8-10- 13-9	23	12.0		SM												(1)
				19.0				Term	inated at 12	.0 feet								
REM	ARKS: (1	⊥ I)Boriı	⊥ ng ba	∟ ckfille	ed wi	∟ th dri	⊔ II s	poils at completior	n for safety	y purpos	es.							

NEW GEOTECH BH LOG 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/14/15

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-9** 

PAGE 1 OF 1

	The \								PROJECT	NAME Ba	ack River Ned	k Road	Wate	er Mair	n Repl	aceme	ent	
	ECT LOC		Baltir	more (	County	, Mar	ylan	<u>d</u>	PROJECT	NUMBER	16613-0: MI	<u>D</u> <b>D</b> A	ATE T	ESTE	D			
RIG _	Truck CN	/IE 45		_ ME	THOE	<u> Hol</u>	low	Stem Auger SAMPL	ER: 2-in O[	O SS	<u> </u>	MER: _		FAL	. <b>L</b> : _30	<u>"</u> Al	JTO?	_Yes
DATE	STARTE	<b>D</b> 6/5	/15		c	OMPL	ETE	<b>ED</b> 6/5/15		I		ER LEV		HOI F	\ \	/ATER	W	ATER
DRILL	ER Der	nnis Str	awdern	nan	_ н	ELPE	R _I	Dustin Hurd	DATE	TIME	ELAPSED HOURS	CASING DEPTH (	ft) DE	PTH (f	t) DE	PTH (ft	) ELÍ	EV (ft)
REVIE	WED BY	Kriste	opher C	Crist	s	ITE DI	ELA	YS										
LOCA	TION A	s Stake	ed .				В	SULK SAMPLES 3-6'	-									
DЕРТН (ft)	SAMPLE TYPE AND NUMBER	SPT BLOWS/6" OR REC IN/IN %	N VALUE OR CORE RQD	STRATUM CHANGE DEPTH/EL (ft)	GRAPHIC LOG	nscs	WATER LEVEL		MATERIAL ESCRIPTION	٧		PP (tsf)	NMC %	- #200	ATT	ERBE LL	RGS PI	REMARKS
				0.7 25.3			П	Bituminous Concrete	<u> </u>									
				1.7			$\vdash$	Aggregate Base (12-iii) Wet, Loose, Tan Pool		AND with 9	Cilt little	-						
	S1	3-3-3- 2	6	24.3	' ,	SP- SM		gravel (Fill) [A-2]	iy-Graded Si	AND WILL	Jiit, iittie							
┝╶┤	+			4.0 22.0	F		Н	Wet, Medium Stiff, Re	d-Brown to (	Grav Sand	v CLAY (Fill)							
5	S2	2-3-3- 2	6	6.0	F	СН		[A-7-6]		J. a., Jan.a.	)	0.50						
	S3	3-3-3- 4	6	20.0				Moist, Medium Stiff, G [A-6]	ray to Gray-	Brown Sar	ndy CLAY	1.00						
10	S4	2-2-3- 5	5			CL						1.00						(1)
	S5	4-3-5- 7	8															(.,
		<u>'</u>		12.0 14.0		1		Tern	ninated at 12	.0 feet		+						
REMA	ARKS: (1	1)Borii	ng ba	ckfille	ed wi	th dr	ill s	poils at completion	ı for safet	y purpos	es.							

NEW GEOTECH BH LOG 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/14/15

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-10** 

	The \								PROJECT	NAME Ba	ack River Ne	ck Road	Wate	er Mair	Repla	aceme	nt	
PROJ	ECT LOC	ATION	Baltir	more (	County	, Mary	/lan	<u>d</u>	PROJECT	NUMBER	16613-0: M	<u>D</u> <b>D</b> /	ATE T	ESTE	)			
	Truck CN			_				Stem Auger SAMPL	ER: 2-in Ol	D SS		MER: _		FAL	L: _30	<u>"</u> Al	JTO?	_Yes
DATE	STARTE	<b>D</b> 6/8/	/15		_ C	OMPL	ETE	<b>ED</b> <u>6/8/15</u>			WA <sup>*</sup> ELAPSED	FER LEV	/ELS	HOLE	W	ATER	W	ATER
DRILL	.ER Der	nis Str	awdern	nan	_ н	ELPEI	<b>R</b> _[	Dustin Hurd	DATE	TIME	HOURS	CASING DEPTH (	ft) DE			PTH (ft	ELI	EV (ft)
REVIE	WED BY	Kristo	opher C	Crist	SI	TE DE	ELΑ	YS	6/8/15		0 ∑			8.6		8.2	1	5.8
LOCA	TION A	s Stake	d				В	BULK SAMPLES	-									
DEРТН (ft)	SAMPLE TYPE AND NUMBER	SPT BLOWS/6" OR REC IN/IN %	N VALUE OR CORE RQD	STRATUM CHANGE DEPTH/EL (ft)	GRAPHIC LOG	nscs	WATER LEVEL		MATERIAL ESCRIPTION	N		PP (tsf)	NMC %	- #200	ATTE	ERBEI	RGS PI	REMARKS
				0.8 23.2	1940		Ц	Bituminous Concrete	• •									
				1.8				Aggregate Base (11-in Concrete (7-inches)	nches)									
	S1	2-4-6	10	2.3	F	ML		Moist, Stiff, Gray San	dy SILT, orga	anic odor (I	Fill) [A-4]		19					
 5	<del>-</del>	2-2-2-		4.0	F			Moist, Soft to Stiff, Gr	ay Sandy, Si	Ity CLAY,	slight							
	S2	3	4	20.0	F	CL		organic odor (Fill) [A-	6]	•		1.30	22					
 	S3	4-5-6- 17	11	7.0 17.0			$\nabla$	Wet, Medium Dense,	Tan-Gray Si	Ity SAND	[A-2]		18					
 _ 10	S4	10-11- 16-12	27	10.0		SM	<u>-</u>						21					(1)
	S5	4-8-7- 9	15	14.0		CL		Moist, Very Stiff, Red	dish Brown S	Sandy CLA	Y [A-6]	4.50	19					(1)
	•			12.0				Term	ninated at 12	.0 feet								
									iniated at 12	.o reet								
REM	ARKS: (	l)Borii	ng ba	ckfille	ed wi	th dri	ill s	poils at completion	n for safet	y purpos	es.							

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-11** 

PAGE 1 OF 1

CLIENT The Wilson T. Ballard Company	PROJECT	NAME Ba	ıck River Ne	ck Road	Wate	er Mair	n Repl	aceme	nt	
PROJECT LOCATION Baltimore County, Maryland	PROJECT	NUMBER	16613-0: M	<u>D</u> <b>D</b>	TE T	ESTE	D			
RIG _Truck CME 45	ER: 2-in O[	o ss	HAN	IMER:	140#	FAL	L: _30	)"_ <b>A</b> l	JTO?	Yes
<b>DATE STARTED</b> 6/8/15 <b>COMPLETED</b> 6/8/15			WAT	ER LEV	ELS					
DRILLER Dennis Strawderman HELPER Dustin Hurd	DATE	TIME	ELAPSED HOURS	CASING DEPTH (	ft) DE	HOLE EPTH (f	t) DE	/ATER PTH (ft)		ATER EV (ft)
REVIEWED BY Kristopher Crist SITE DELAYS	6/8/15		0 ∑			5.5		Dry		
LOCATION Offset 10'S BULK SAMPLES 3-6'										
CL   CL   CL   CL   CL   CL   CL   CL	MATERIAL ESCRIPTION  ft (28-inches) ches) , Brown Silty A-2] andy CLAY, "I	v SAND, "m Mothball" o A-6]	nothball"	4.50 - 3.30 2.20 1.20	NMC %	- #500		ERBER	RGS	(1) (EMARKS (4)
REMARKS: (1)PID reading = 0.0 ppm (2)PID reading = 0.0 p	pm (3)PIE	) reading	g = 0.0 ppi	n (4)B	oring	bac	kfille	d with	n drill	

NEW GEOTECH BH LOG 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/14/15

spoils at completion for safety purposes.

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-12** 

	The \								PROJECT	NAME Ba	ack River Ne	ck Road	l Wate	er Maiı	n Repl	aceme	ent	
PROJ	ECT LOC	ATION	Baltir	nore (	County	, Mar	/lan	d	PROJECT	NUMBER	16613-0: M			ESTE				
RIG _	Truck CN	1E 45		_ ME	THOE	Hol	low	Stem Auger SAMPL	. <b>ER</b> : 2-in Ol	D SS	HAN	MER: _	140#	FAL	. <b>L</b> : _3	<u>D"</u> A	JTO?	_Yes
DATE	STARTE	<b>D</b> 6/8	/15		_ C	OMPL	ETE	<b>ED</b> 6/8/15		T	WAT ELAPSED	CASING	/ELS	HOI F	V	/ATER	W	ATER
DRILL	.ER Der	nnis Str	awdern	nan	_ н	ELPE	<b>R</b> _[	Dustin Hurd	DATE	TIME	HOURS	CASING DEPTH (	ft) DE		t) DE	PTH (ft	) ELÍ	EV (ft)
REVIE	WED BY	Kriste	opher C	Crist	SI	ITE DE	ELA	YS	6/8/15		0 ∑			5.7		Dry		
LOCA	TION A	s Stake	ed				В	BULK SAMPLES	_									
DЕРТН (ft)	SAMPLE TYPE AND NUMBER	SPT BLOWS/6" OR REC IN/IN %	N VALUE OR CORE RQD	STRATUM CHANGE DEPTH/EL (ft)	GRAPHIC LOG	nscs	WATER LEVEL		MATERIAL ESCRIPTION	N	'	PP (tsf)	NMC %	- #200	ATT	ERBE LL	RGS PI	REMARKS
				1.1				Bituminous Concrete	(14-inches)									
								Aggregate Base (11-i										
_	S1	5-7-9	16	21.0	H F	SM		Moist, Medium Dense	e, Brown Silty	/ SAND (Fi	II) [A-2]							
	31		10	4.0 19.0				Moist, Very Stiff, Brow	un Sandy Cl	^∨ /Eill\ [/	۸ 61							
5	S2	5-7-8- 9	15		F	CL		Wolst, very Still, Brow	vii Sandy CL	A ( ( I III ) [ A	<b></b> 0j	3.80						
-	♥	10-11-		6.0 17.0			Н	Moist, Stiff to Very St	iff, Grayish T	an Sandy (	CLAY [A-6]							
-	S3	12-12	23					•				3.30						
	S4	4-4-6-	10			CL						1.00						
10	34	6	10	10.0								1.00						(1)
	S5	4-5-5- 6	10	13.0		CL		Wet, Stiff, Brown-Gra layers of SAND, trace	y Sandy CLA rock fragme	AY interbed ents [A-6]	lded with	0.70						(1)
	•			11.0				Terr	ninated at 12	2.0 feet								
REM	ARKS: (1	∟ I)Boriı	⊥ ng ba	∟ ckfille	ed wi	th dri	ш iII s	poils at completio	n for safet	y purpos	es.							

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-13** 

CLIEN	T The \	Vilson	T. Balla	ard Co	mpan	У			PROJECT	NAME Ba	ack River Ne	ck Road	Wate	er Maii	n Repl	aceme	ent	
PROJI	ECT LOC	CATION	l Baltii	more (	County	, Mar	ylan	d	PROJECT	NUMBER	16613-0: M	<u>D</u> <b>D</b> /	ATE T	ESTE	D 6/2	26/201	5	
RIG _	Truck CN	/IE 45		_ ME	THO	Hol	low	Stem Auger SAMPL	ER: _2-in O[	O SS	HAN	MER: _	140#	FAL	L: _3	O"_ A	UTO?	Yes
DATE	STARTE	<b>D</b> 6/8	/15		_ c	OMPL	ETE	<b>ED</b> <u>6/8/15</u>		I	WAT ELAPSED	CASING	/ELS	HOLF	V	VATER	W	ATER
DRILL	ER Der	nnis Str	awdern	nan	_ н	ELPE	R _I	Dustin Hurd	DATE	TIME	HOURS	CASING DEPTH (	ft) DE		t) DE	PTH (ft	.) EĽÍ	EV (ft)
REVIE	WED BY	Krist	opher (	Crist	s	ITE DI	ELA	YS	6/8/15		0 ∑			5.5		Dry		
LOCA.	TION A	s Stake	ed				E	BULK SAMPLES 3-6'										
DЕРТН (ft)	SAMPLE TYPE AND NUMBER	SPT BLOWS/6" OR REC IN/IN %	N VALUE OR CORE RQD	STRATUM CHANGE DEPTH/EL (ft)	GRAPHIC LOG	nscs	WATER LEVEL	SURFACE EL = 21.0		N		PP (tsf)	NMC %	- #200	ATT	ERBE LL	RGS PI	REMARKS
_				0.7 20.3		9	$\vdash$	Bituminous Concrete	· , ,			-						
				1.3	F		$\Box$	Aggregate Base (8-ind Moist, Medium Stiff, B		CLAY (Fill	) [A-6]							
	S1	8-3-3- 3	6	4.0		CL		Wolst, Wediam Cam, E	rown oanay	OLYTT (TIM	) [/ O]	0.70	26					
5	S2	3-6-8- 10	14	17.0	MF	ML		Moist, Stiff, Brown Sa	ndy, Clayey	SILT (Fill)	[A-5]		20					
	S3	7-8-8-	16	6.0 15.0				Moist, Medium Dense [A-2-4]	to Loose, B	rown Silty	SAND		26					
	S4	1-2-6-	8	-		SM							17	14	NP	NP	NP	
10	<b></b>	9 4-6-8-		10.0 11.0				Wet, Medium Dense,	Red-Brown S	Silty SAND	[A-2-4]			'				(1)
	S5	10	14	12.0		SM							21					
				9.0				Term	ninated at 12	.0 feet								
		L		L	L	L								L		L		
REMA	ARKS: (1	1)Bori	ng ba	ckfille	ed wi	th dr	ill s	poils at completion	n for safet	y purpos	es.							

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-14** 

	CLIEN	IT The \	/Vilson	T. Balla	ard Co	mpan	у			PROJECT	NAME Ba	ack River Ne	eck Road	d Wat	er Main	Repla	aceme	nt	
	PROJ	ECT LOC	ATION	Baltii	more (	County	, Mary	ylan	ıd	PROJECT	NUMBER	16613-0: N	<u>1D</u> <b>D</b>	ATE 1	ESTED				
	RIG _	Truck CN	/IE 45		_ ME	ETHO	Hol	low	Stem Auger SAMPLE	<b>R:</b> 2-in Ol	D SS	HAI	MMER:	140#	FALL	.: <u>30</u>	<u>"</u> Al	JTO?	Yes
	DATE	STARTE	<b>D</b> 6/8	/15		c	OMPL	ETE	ED <u>6/8/15</u>	DATE		FLAPSED	TER LEY		HOLE	W	ATER	W	ATER
	DRILL	.ER Der	nnis Str	awdern	nan	_ н	ELPE	R _	Dustin Hurd	DATE	TIME	HOURS	DEPTH	(ft) D	EPTH (ft)	DEI	PTH (ft)	ELI	EV (ft)
	REVIE	WED BY	Kriste	opher (	Crist	s	ITE DE	ELA	YS	6/8/15		0 ∑			5.6		Dry		
	LOCA	TION A	s Stake	ed				E	BULK SAMPLES										
	(#) HLd=30	SAMPLE TYPE SAMPLE TYPE AND NUMBER S3	% IN	14 18 22 6	0.7 22.3 1.3 21.7 4.0 19.0 15.0	GRAPHIC LOG	SOSN CL CL	WATER LEVEL I	N	3-inches) nes) dy CLAY (F	Fill) [A-6] dy CLAY [	-	(J\$) dd 4.50 4.50 3.30 1.50	NMC %	- #200	ATTE	ERBEF	RGS PI	(L) REMARKS
16613-0 BACK RIVER NECK ROAD WATER MAIN. GPJ MTA REDLINE. GDT 7/14/15		<b>S</b> 5	2-3-3-2	6	12.0				Termi	nated at 12	2.0 feet								
NEW GEOTECH BH LOG	REM	ARKS: (1	I)Borii	ng ba	ckfille	ed wi	th dri	ill s	spoils at completion		y purpos	es.							

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-15** 

		IT <u>The \</u>										ck River Ne					aceme	ent	
ŀ							-		id										
									Stem Auger SAMPLE	<b>R</b> : 2-in OL	) SS		MER: _		FAL	<u>-: 30</u>	<u>)"</u> Al	JTO?	_Yes
									ED <u>6/12/15</u>	DATE	TIME	ELAPSED	CASING	G	HOLE		ATER	WA	ATER
									Dustin Hurd	6/12/15		HOURS 0 ∑	DEPTH (	(tt) Di	6.2	- 1	PTH (ft Dry	) ELE	EV (ft)
									YS	0/12/10		0 -			0.2		Diy		
	LOCA	TION A	s Stake	d				Е	BULK SAMPLES <u>3-6'</u>										
NEW GEOTECH BH LOG 16613-0 BACK RIVER NECK ROAD WATER MAIN GPJ MTA REDLINE GDT 7/14/15	LOCA (#) HI (#) DEPTH (#) 10	SAMPLE TYPE SAMPLE TYPE SAMPLE TYPE S2 S3 S4 S2 S2 S2 S2 S2 S3 S4 S2 S2 S2 S2 S2 S2 S2 S3 S4 S2 S2 S2 S2 S2 S3 S4 S2 S2 S2 S2 S3 S4 S2 S2 S2 S2 S3 S4 S5 S5	**Stake**  **JSWOOTB LAGS  4-2-2-2 3-6-8-11 10-15-17 7-8-8-9 9-10-10-11	4 14 30 16 20	0.7 0.7 12.0 9.0 12.0	GRAPHIC LOG	SOSU CL CL MT	WATER LEVEL <b>m</b>	SURFACE EL = 21.0  Bituminous Concrete (9) Aggregate Base (14-index) Moist, Soft, Gray Sand  Moist, Stiff, Reddish Br  Moist, Stiff, Brown Sand	9-inches) ches) y CLAY, littl own Sandy	e organics  CLAY [A-6  SILT [A-4]	6]	0.70 4.50	NMC %	- #200	ATTI PL	ERBE	RGS PI	(I) REMARKS
3 1661,																			
EW GEOTECH BH LOG	REM	ARKS: (1	)Borir	ng ba	ckfille	ed w	ith dri	ill s	spoils at completion		y purpose	es.							
岁																			

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-16** 

	The \								PROJECT	NAME Ba	ick River Ne	ck Road	l Wat	er Maiı	n Repl	aceme	ent	
PROJ	ECT LOC	CATION	Baltir	nore C	County	, Mary	/lan	<u>d</u>	PROJECT	NUMBER	16613-0: M	<u>D</u> <b>D</b> .	ATE T	ESTE	<u> </u>			
RIG _	Truck CN	/IE 45		_ ME	THOE	Hol	low	Stem Auger SAMPL	ER: 2-in O	) SS	HAN	IMER:	140#	FAL	L: _30	<u>)"</u> Al	JTO?	_Yes
DATE	STARTE	<b>D</b> 6/1	2/15		C	OMPL	ETE	<b>ED</b> 6/12/15			WA1 ELAPSED	CASIN	/ELS	HOLF	V	VATER	W	ATER
DRILL	.ER Der	nnis Str	awdern	nan	_ н	ELPEI	<b>R</b> _[	Dustin Hurd	DATE	TIME		CASIN DEPTH	(ft) D		- 1	PTH (ft	) ELÍ	EV (ft)
REVIE	WED BY	Kriste	opher C	Crist	SI	ITE DE	ELΑ	YS	6/12/15		0 ∑			6.6		Dry		
LOCA	TION A	s Stake	ed				В	ULK SAMPLES	_									
DЕРТН (ft)	SAMPLE TYPE AND NUMBER	SPT BLOWS/6" OR REC IN/IN %	N VALUE OR CORE RQD	STRATUM CHANGE DEPTH/EL (ft)	GRAPHIC LOG	nscs	WATER LEVEL		MATERIAL ESCRIPTION	ı		PP (tsf)	NMC %	- #200	ATT PL	ERBEI	RGS PI	REMARKS
				0.7	o various			Bituminous Concrete	(9-inches)									
				1.3				Concrete (6-inches)										
_	S1	6-5-5- 6	10	20.8 1.8 20.2	F.	CL	}	Aggregate Base (7-ind Moist, Stiff, Brown Sal		ill) [A-61								
	<u> </u>	1	_															
5	S2	3-3-5- 4	8	18.0		ML		Moist, Medium Stiff, B	rown Sandy	SILI [A-4	J							
	S3	6-8-7- 9	15	6.0 16.0				Moist, Medium Dense	, Brown Silty	SAND [A	-2]							
10	S4	4-5-5- 5	10	-		SM												(4)
	S5	5-8-7- 8	15	12.0														(1)
				10.0				Term	ninated at 12	.0 feet		7						
REM	ARKS: (*	1)Borii	ng ba	ckfille	ed wi	th dri	ill s	poils at completior	n for safety	y purpos	es.							

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-17** 

PAGE 1 OF 1

CLIEN	The	Wilson '	T. Balla	ard Co	mpany	/			PROJECT	NAME Ba	ick River Ne	ck Road	Wat	er Maiı	n Repl	aceme	ent	
PROJ	ECT LOC	ATION	Baltir	more (	County	, Mar	ylan	<u>d</u>	PROJECT	NUMBER	16613-0: M	<u>D</u> <b>D</b> /	ATE 1	ESTE	D			
RIG _	Truck CN	1E 45		_ ME	THOE	<u> Hol</u>	low	Stem Auger SAMPLE	<b>R</b> : _2-in OE	) SS	HAN	MER: _	140#	FAL	. <b>L</b> : _3	0"_ A	JTO?	_Yes
DATE	STARTE	<b>D</b> 6/1	2/15		_ C	OMPL	ETE	<b>ED</b> 6/12/15			WAT ELAPSED	CASING	ELS	HOLE	V	VATER	W	ATER
DRILL	ER Der	nnis Str	awdern	nan	_ н	ELPE	R _I	Dustin Hurd	DATE	TIME	HOURS	DEPTH (	ft) D	EPTH (1	t) DE	PTH (ft	) ĔĽÍ	EV (ft)
REVIE	WED BY	Kristo	opher C	Crist	SI	ITE DI	ELA	YS	6/12/15		0 ∑			6.7		Dry		
LOCA	TION A	s Stake	ed				В	BULK SAMPLES										
DЕРТН (ft)	SAMPLE TYPE AND NUMBER	SPT BLOWS/6" OR REC IN/IN %	N VALUE OR CORE RQD	STRATUM CHANGE DEPTH/EL (ft)	GRAPHIC LOG	nscs	WATER LEVEL	DE SURFACE EL = 20.0		1		PP (tsf)	NMC %	- #200	ATT	ERBE LL	RGS PI	REMARKS
				0.8 19.2	XX 9		Ц	Bituminous Concrete (										
				1.3			$\sqcap$	Aggregate Base (6-inc Moist, Stiff to Medium		h Brown S	andy CLAY							
	S1	3-6-5- 7	11	18.7		CL		[A-6]	oun, readio	in Brown o	andy OE (1	2.00	24					
5	S2	3-4-4- 4	8	6.0		OL						1.00	24					
_ =	S3	4-5-6- 7	11	14.0		CL		Moist, Stiff, Gray Sand	y CLAY [A-	6]		0.80	27					
10	S4	2-2-2- 3	4	8.0 12.0				Wet, Soft to Medium S	tiff, Gray CL	AY [A-4]		0.20	27	96	18	28	10	(4)
	S5	2-3-3- 3	6	40.0		CL							26					(1)
				12.0 8.0	(/////			Termi	inated at 12.	.0 feet		+		1				
REMA	ARKS: (*	l I)Borii	l ng ba	L ckfille	ed wi	th dr	∐ ill s	poils at completion	for safety	/ purpos	es.							

NEW GEOTECH BH LOG 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/14/15

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-18** 

	The \								PROJECT	NAME Ba	ack River Ned	ck Road	l Wate	er Mair	n Repl	aceme	ent	
PROJ	ECT LOC	ATION	Baltir								16613-0: MI	<u>D</u> <b>D</b> /	ATE T	ESTE	D			
RIG _	Truck CN	1E 45		_ ME	THOE	Hol	low	Stem Auger SAMPL	<b>ER</b> : 2-in O[	D SS		MER: _		FAL	. <b>L</b> : _3	O"_ A	JTO?	_Yes
DATE	STARTE	<b>D</b> 6/1	2/15		_ c	OMPL	ETE	<b>ED</b> 6/12/15			WAT ELAPSED	ER LEV	/ELS	HOLE	v	VATER	W	ATER
DRILL	ER Der	nnis Str	awdern	nan	_ н	ELPE	R _I	Dustin Hurd	DATE	TIME		CASING DEPTH (	ft) DE		t) DE	PTH (ft	) ELI	EV (ft)
REVIE	WED BY	Kriste	opher (	Crist	s	ITE DI	ELA	YS	6/12/15		0 ∑			7.0		Dry		
LOCA	TION A	s Stake	ed				В	BULK SAMPLES	-									
DЕРТН (ft)	SAMPLE TYPE AND NUMBER	SPT BLOWS/6" OR REC IN/IN %	N VALUE OR CORE RQD	STRATUM CHANGE DEPTH/EL (ft)	GRAPHIC LOG	nscs	WATER LEVEL		MATERIAL ESCRIPTION	N		PP (tsf)	NMC %	- #200	ATT	ERBE	RGS PI	REMARKS
				0.6 16.4	1000 1000		H	Bituminous Concrete	· ,									
L 4				1.2 15.8	F		$\sqcap$	Aggregate Base (7-ind Moist, Stiff, Gray Sand		[Δ_4]								
-	S1	4-5-5- 7	10		F	ML		Wolot, Ctin, Cray Carl	ay OILT (TIII)	[,, -1]								
5	S2	6-3-3- 3	6	4.0 13.0	F			Slightly Wet, Medium	Stiff, Gray S	Y (Fill) [A-6]								
	<b>S3</b>																	
 	S4	2-3-2-	5	8.0 9.0		SM		Wet, Loose, Gray Silt	y SAND [A-2	2]								
10	lack			10.0 7.0				Moist Medium Stiff G	Grav Sandy C	LAY [A-6]	1							(1)
-	S5	5	8			CL		Molot, Modiam Stin, C	ray canay c	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	1	2.00						
	S3 2-2-3- 5 8.0 9.0 SM Wet, Loose, Gray Silty SAND [A-2]  S5 3-3-5- 8 ON Moist, Medium Stiff, Gray Sandy CLAY [A-6]																	
REMA	ARKS: (*	⊥ I)Borii	⊥ ng ba	∟ ckfille	ed wi	th dr	Ш ill s	poils at completion	n for safety	y purpos	es.	1						

**BORING B-19** 

PAGE 1 OF 1

3

NEW GEOTECH BH LOG 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/14/15

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

CLIENT The	Wilson T	. Balla	rd Co	mpany	/			PROJECT	NAME Ba	ck River Ne	ck Road	Wate	er Mair	Repl	aceme	nt	
PROJECT LOC	CATION	Baltir	nore (	County	, Mary	/lan	<u>d</u>	PROJECT	NUMBER	16613-0: M	<u>D</u> <b>D</b>	ATE T	ESTE	<u> </u>			
RIG Truck CN	⁄IE 45		_ ME	THOD	Hol	low	Stem Auger SAMPLE	<b>ER:</b> 2-in OE	) SS	HAN	IMER: _	140#	FAL	L: _3	<u>0"</u> Al	JTO?	_Yes
DATE STARTE	<b>D</b> 6/11	/15		_ C	OMPL	ETE	<b>ED</b> 6/11/15			WAT ELAPSED	CASING	ELS	HOLE	V	VATER	W	ATER
DRILLER Der	nnis Stra	wdern	nan	_ H	ELPE	R _[	Dustin Hurd	DATE	TIME	HOURS	DEPTH (	ft) DE	EPTH (f	t) DE	PTH (ft	) ELÍ	EV (ft)
REVIEWED BY	' Kristo	pher C	Crist	SI	TE D	ELA	YS	6/11/15		0 ∑			7.4		Dry		
LOCATION A	s Stake	d				В	BULK SAMPLES 3-6'										
DEPTH (ft) SAMPLE TYPE AND NUMBER	SPT BLOWS/6" OR REC IN/IN %	N VALUE OR CORE RQD	o STRATUM CHANGE ∞ DEPTH/EL (ft)	GRAPHIC LOG	nscs	WATER LEVEL			ı		PP (tsf)	NMC %	- #200	ATT PL	ERBEI	RGS PI	REMARKS
			19.3			Ħ	Aggregate Base (3-inc										ĺ
S1	8-10- 5-7	15	1.0 19.0	 	CL	Y	Moist, Stiff, Brown San		ill) [A-6]		3.50						
5 S2	4-6-6- 7	12	6.0	F							4.50						
S3	6-6-6- 6	12	8.0		CL		Moist, Stiff, Gray-Brow				1.30						
- 10 S4	2-4-6- 7	10	12.0		SM		Moist to Wet, Loose to SAND [A-2]	Medium De	ense, Browi	n Silty							(1)
S5	6-6-6- 3	12	12.0						0.5								
DEMADKS: (/	1\Poriginal Poriginal Pori		8.0		الماء والماء		poils at completion	for opfoty									

**BORING B-20** 

PAGE 1 OF 1

3

NEW GEOTECH BH LOG 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/14/15

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

Bituminous Concrete (8-Inches)   Aggregate Base (4-Inches)   Aggregate Base (4-Inches)   Moist, Medium Dense, Brown Silty SAND (Fill) [A-2]	CLIENT _The Wilson T. Ballard Company	PROJECT	NAME Ba	ick River Ne	ck Road	Water	Main F	Replacem	ent	
DATE STARTED   0:11/15   COMPLETED   0:11/15   HELPR   Dustin Hard   HELPR   Dustin Ha	PROJECT LOCATION Baltimore County, Maryland	PROJECT	NUMBER	16613-0: M	D DA	TE TES	STED			
DRILLER   Dennis Strawderman   HELPER   Dustin Hurd   SITE DELAYS   SITE DELAYS   SITE DELAYS   SITE DELAYS   DESCRIPTION   As Staked   SITE DELAYS   DESCRIPTION   DESC	RIG _Truck CME 45 METHOD _Hollow Stem A	ger SAMPLER: 2-in O	D SS	HAN	MER: 1	40#	FALL:	_30"_ A	UTO?	_Yes
REVIEWED BY Kristopher Crist BULK SAMPLES  B	DATE STARTED 6/11/15 COMPLETED 6/		T	WAT	CASING	ELS	OLE	WATER	) W	ATED
BULK SAMPLES  BULK SAMPLES  MATERIAL DESCRIPTION  BULK SAMPLES  PL  A  A  A  A  B  A  A  A  A  A  B  A  A	DRILLER Dennis Strawderman HELPER Dustin	rd DATE	TIME	HOURS	DEPTH (fi	t) DEP	TH (ft)	DEPTH (	ft) EL	EV (ft)
	REVIEWED BY Kristopher Crist SITE DELAYS									
Bituminous Concrete (8-Inches)   Aggregate Base (4-Inches)   Aggregate Base (4-Inches)   Moist, Medium Dense, Brown Silty SAND (Fill) [A-2]	LOCATION As Staked BULK S	MPLES								
	CL   Staked   BULK Staked	MATERIAL DESCRIPTIO  CE EL = 17.0 ft ous Concrete (8-inches) te Base (4-inches) edium Dense, Brown Silt cose, Gray Clayey SAND dium Stiff, Gray-Brown S ose to Medium Dense, Gr	y SAND (Fil (Fill) [A-4] andy CLAY ay Silty SAI	[A-6]		NMC %	#20			(L) REMARKS
REMARKS: (1)Boring backfilled with drill spoils at completion for safety purposes.	REMARKS: (1)Boring backfilled with drill spoils	completion for safe	v purpose	es.						

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-21** 

PAGE 1 OF 1

**CLIENT** The Wilson T. Ballard Company PROJECT NAME Back River Neck Road Water Main Replacement PROJECT LOCATION Baltimore County, Maryland PROJECT NUMBER 16613-0: MD DATE TESTED 6/26/2015 METHOD Hollow Stem Auger SAMPLER: 2-in OD SS **RIG** Truck CME 45 HAMMER: 140# FALL: 30" AUTO? Yes **WATER LEVELS DATE STARTED** 6/11/15 **COMPLETED** 6/11/15 WATER DEPTH (ft) ELAPSED CASING DEPTH (ft) HOLE WATER DATE TIME DEPTH (ft) ELEV (ft) DRILLER Dennis Strawderman HOURS **HELPER** Dustin Hurd 6/11/15 0 🗸 6.7 Dry **REVIEWED BY** Kristopher Crist SITE DELAYS LOCATION As Staked **BULK SAMPLES** 3-6' STRATUM CHANGE DEPTH/EL (ft) SAMPLE TYPE AND NUMBER SPT BLOWS/6" OR REC IN/IN 9 GRAPHIC LOG **WATER LEVEL** N VALUE OR CORE RQD MATERIAL REMARKS DEPTH (ft) DESCRIPTION (tst) **ATTERBERGS** USCS - #200 NMC Ы SURFACE EL = 16.0 ft ΡL ы 0.8 Bituminous Concrete (9-inches) 15.3 Aggregate Base (8-inches) 1.4 14.6 Moist, Stiff, Brown Sandy CLAY (Fill) [A-6] 10 12 S1 CL 2.20 18 69 17 29 5 5 2-4-5 5.0 S2 9 Moist, Stiff to Very Stiff, Brown Sandy CLAY [A-6] 7 110 CL 11-10-S3 20 1.90 10-12 8.0 8.0 Moist, Stiff to Very Stiff, Tan Sandy CLAY [A-6] 4-6-7 4.50 13 S4 8 10 CL (1) 10-10-S<sub>5</sub> 24 14-14 12.0 4.0 Terminated at 12.0 feet

NEW GEOTECH BH LOG 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/14/15

REMARKS: (1)Boring backfilled with drill spoils at completion for safety purposes.

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-22** 

	CLIEN	IT The \	Wilson '	T. Balla	ard Co	mpan	у			PROJECT	NAME Ba	ick River Ne	ck Road	d Wat	er Main	Repla	aceme	nt	
	PROJ	ECT LOC	ATION	Baltir	more (	County	y, Mary	ylan	nd	PROJECT	NUMBER	16613-0: N	<u>1D</u> <b>D</b> .	ATE 1	ESTED				
	RIG _	Truck CN	1E 45		_ ME	ETHO	O Hol	low	Stem Auger SAMPLE	<b>R</b> : _2-in Ol	D SS	HAN	/IMER:	140#	FALL	: _30	<u>"</u> AU	TO?	_Yes
	DATE	STARTE	<b>D</b> 6/1	1/15		c	OMPL	ETE	<b>ED</b> <u>6/11/15</u>			FLAPSED	TER LEV		HOLE	W	ATER	W	ATER
	DRILL	.ER Der	nis Str	awdern	nan	_ н	IELPEI	R _I	Dustin Hurd	DATE	TIME	HOURS	DEPTH	(ft) D	EPTH (ft)	DEI	PTH (ft)	ELI	V (ft)
	REVIE	WED BY	Kristo	opher (	Crist	s	ITE DE	ELA	YS	6/11/15		0 ∑			6.0		Dry		
	LOCA	TION A	s Stake	ed				E	BULK SAMPLES										
16813-0 BACK RIVER NECK ROAD WATER MAIN, GPJ MTA REDLINE, GDT <i>714</i> 115	DEPTH (ft)	SAMPLE TYPE  SAMPL	"9/SMOT ALSO 10-15- 12-8 5-4-3- 6 4-5-7- 9 7-8-9- 8 7-6-5-	27 7 12 17	3.0 STRATUM CHANGE (ft) 0.0 8.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0	GRAPHIC LOG	SOSON SM SP-SSM	WATER LEVEL	SURFACE EL = 15.0  Bituminous Concrete (Aggregate Base (6-inc) Moist, Medium Dense Gravel (Fill) [A-2]  Moist, Medium Dense, Wet, Medium Dense, 7 [A-2]	8-inches) hes) to Loose, B	rown Silty S n Silty SAN Graded SA	ID [A-2]	PP (tsf)	% OWN 5 10 20 19 24	#2	ATTE	ERBER	PI	(I) REMARKS
NEW GEOTECH BH LOG 16	REM	ARKS: (1	⊔ I)Borii	ng ba	ckfille	⊥ ed wi	ith dri	⊥ ill s	spoils at completion		y purpos	es.			1				

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-23** 

	CLIEN	IT The V	Vilson	T. Balla	ard Co	mpan	У					ck River Ne					aceme	nt	
	PROJ	ECT LOC	ATION	Baltii	more (	County	y, Mary	/lan	id	PROJECT	NUMBER	16613-0: M	<u>D</u> <b>D</b>	ATE 1	ESTE				
	RIG _	Truck CN	1E 45		_ ME	ETHO	O Hol	low	Stem Auger SAMPLE	<b>R</b> : 2-in O[	) SS	HAN	MER: _	140#	FAL	L: <u>3</u> 0	<u>"</u> Al	JTO?	_Yes
	DATE	STARTE	<b>D</b> 6/1	1/15		c	OMPL	ETI	ED 6/11/15			WA <sup>-</sup> ELAPSED	CASIN		HOLE	V	/ATER	W	ATER
	DRILL	<b>ER</b> Der	nis Str	awdern	nan	_ н	IELPEI	<b>R</b> _	Dustin Hurd	DATE	TIME	HOURS	DEPTH	ft) D	EPTH (fi	) DE	PTH (ft		EV (ft)
	REVIE	WED BY	Kristo	opher (	Crist	s	ITE DE	ELA	YS	6/11/15		0 ∑			6.5		Dry		
	LOCA	TION A	s Stake	ed				E	BULK SAMPLES 3-6'										
NEW GEOTECH BH LOG 16613-0 BACK RIVER NECK ROAD WATER MAIN GPJ MTA REDLINE.GDT 7/14/15	DEPTH (ft)	Sample Type  Sampl	% N/N/N/S 2 4-4-5-6 4-4-5-5-4-2-2	27 9 8 6 CORE RQD	13.8 S.0.0 O.0.0 O.0. O.0.0 O.	GRAPHIC LOG	SC-SM ML SM	WATER LEVEL	SURFACE EL = 15.0 f Bituminous Concrete (7 Aggregate Base (8-inch Moist, Medium Dense t Gravel (Fill) [A-2]  Moist, Loose, Red-Brow Moist, Stiff, Reddish Br [A-4]  Wet, Loose, Brown Silty	r-inches) nes) to Loose, Bi vn Silty, Cla own Sandy y SAND [A	ayey SAND, Clayey SI -2]	LT (Fill)	1.00	NMC %	- #200	ATT PL	LL	RGS PI	(I) REMARKS
NEW GEOTECH BH LOG	REM	ARKS: (1	)Borii	ng ba	ckfille	ed wi	ith dri	ill s	spoils at completion		purpos	es.							

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-24** 

	CLIEN	The V	Vilson	T. Balla	ard Co	mpan	У			PROJECT	NAME Ba	ck River Ne	ck Road	d Wat	er Maiı	n Repl	aceme	ent	
	PROJ	ECT LOC	ATION	Baltiı	more (	County	y, Mary	ylan	<u>id</u>	PROJECT	NUMBER _	16613-0: M	<u>D</u> <b>D</b> .	ATE 1	<b>FESTE</b>	<b>o</b> 6/2	26/201	5	
	RIG _	Truck CM	IE 45		_ ME	THO	O Hol	low	Stem Auger SAMPLE	<b>R</b> : 2-in OE	) SS	HAN	IMER:	140#	FAL	L: _3	0"_ A	JTO?	_Yes
	DATE	STARTE	<b>D</b> 6/1	1/15		c	OMPL	ETE	ED 6/11/15			WA <sup>-</sup> ELAPSED	CASIN	/ELS	HOLE	V	VATER	W	ATER
	DRILL	.ER Den	nis Str	awdern	nan	_ н	IELPEI	R _I	Dustin Hurd	DATE	TIME	HOURS	CASIN DEPTH	(ft) D	EPTH (1	t) DE	PTH (fi		EV (ft)
	REVIE	WED BY	Kristo	opher (	Crist	s	ITE DE	ELA	YS	6/11/15		0 ⊻			6.7		Dry		
	LOCA	TION A	s Stake	d				Е	BULK SAMPLES										
l			%		병					1								-	
		띪	.9/S	<u>~</u>	¥ (	90		Æ											
	(ft)	T. B.	ŠΖ	S C C	NH SH SH	<u> </u>		LE		MATERIAL									S S
	ΤΤ		JE SE			PH	တ္ပ	ER	DE	SCRIPTION	1		tsf)	%	9	ATT	ERBE	RGS	AR
	DЕРТН (ft)	SAMPLE TYPE AND NUMBER	SPT BLOWS/6" OR REC IN/IN %	N VALUE OR CORE RQD	STRATUM CHANGE DEPTH/EL (ft)	GRAPHIC LOG	nscs	<b>WATER LEVEL</b>	SURFACE EL = 18.0	ft			PP (tsf)	NMC	- #200	PL	LL	PI	REMARKS
l					0.4	) } } }		Ħ	Bituminous Concrete (						1	FL	LL	FI	
İ					1.0			$\Box$	Aggregate Base (7-incl		U CAND								
		S1	2-4-3- 3	7	17.0		SM		Moist, Loose to Very Lo	oose, Tan S	ilty SAND	[A-2]		12					
	5	S2	1-2-1- 1	3	6.0						11								
		S3	WOH- 2- WOH-	2	12.0		CL-	[A-4]		25	76	17	21	4					
		S4	1-1-1	2			ML												
	10		1		10.0 8.0											(1)			
ŀ		S5	5-4-2- 1	6			SM		Wet, Loose, Brown Silt										
t					12.0 6.0			H		7									
2																			
7/14/1																			
GDT																			
LINE																			
MTA REDLINE.GDT 7/14/15																			
N.GP																			
MAII																			
ATEF																			
₽																			
S S																			
NEC																			
NVER.																			
Å																			
16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ																			
1661																			
1106	REM	ARKS: (1	)Borii	ng ba	ckfille	ed wi	ith dri	ill s	poils at completion	for safety	y purpose	es.							
CH B																			
NEW GEOTECH BH LOG										_									
NEW (									12	5									

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-25** 

PAGE 1 OF 1

CLIEN	IT The	Wilson '	T. Balla	ard Co	mpany	/			PROJECT	NAME Ba	ack River Ne	ck Road	Wate	er Mair	n Repl	aceme	ent	
PROJ	ECT LOC	CATION	l <u>Baltir</u>	more (	County	, Mary	/lan	d	PROJECT	NUMBER	16613-0: M	<u>D</u> <b>D</b>	ATE T	ESTE	<b>_</b>			
RIG _	Truck CN	/IE 45		_ ME	THOE	Hol	low	Stem Auger SAMPL	. <b>ER</b> : 2-in Ol	D SS	HAN	MER: _	140#	FAL	L: _30	<u>"</u> Al	JTO?	_Yes
DATE	STARTE	<b>D</b> 6/1	0/15		_ C	OMPL	ETE	<b>ED</b> 6/10/15		T	WA <sup>-</sup> ELAPSED	TER LEV	ELS	HOI E	_ \ \	/ATER	W	ATER
DRILL	.ER Der	nnis Str	awdern	nan	_ н	ELPE	<b>R</b> _[	Dustin Hurd	DATE	TIME	HOURS	CASING DEPTH (	ft) DE		t) DE	PTH (ft	) ĔĽÍ	EV (ft)
REVIE	WED BY	Kriste	opher C	Crist	SI	TE DE	ELA	YS	6/10/15		0 ∑			6.1		Dry		
LOCA	TION A	s Stake	ed				В	BULK SAMPLES 3-6'	_									
DЕРТН (ft)	SAMPLE TYPE AND NUMBER	SPT BLOWS/6" OR REC IN/IN %	N VALUE OR CORE RQD	STRATUM CHANGE DEPTH/EL (ft)	GRAPHIC LOG	nscs	WATER LEVEL	D SURFACE EL = 21.	MATERIAL ESCRIPTION	N		PP (tsf)	NMC %	- #200	ATT PL	ERBE LL	RGS PI	REMARKS
				0.8				Bituminous Concrete										
_				20.2			$\vdash$	Aggregate Base (10- Moist, Medium Stiff to		Brown San	dy CLAV							
	S1	4-2-4- 6	6	19.4				[A-6]	ouii, Olay-i	orown San	uy OLAT	3.50						
5	S2	4-2-4- 4	6			CL						2.50						
	S3	5-5-6- 7	11	8.0								1.70						
 _ 10	S4	2-3-2- 3	5	13.0		CL		Moist to Wet, Mediun [A-6]	n Stiff, Gray-I	Brown San	dy CLAY	1.20						(1)
	S5	3-3-3- 3	6	12.0		OL												(1)
				9.0				Terr	ninated at 12	2.0 feet								
REM	ARKS: (*	⊥ 1)Boriı	l ng ba	⊥ ckfille	ed wi	l th dri	∐ ill s	poils at completio	n for safet	y purpos	es.							

NEW GEOTECH BH LOG 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/14/15

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-26** 

		IT The V				-						ck River Ne					aceme	ent	
									<u>d</u>										
									Stem Auger SAMPLE	<b>R:</b> 2-in Ol	O SS		IMER: _		FAL	L: <u>30</u>	<u>)"</u> Al	JTO?	_Yes
									<b>ED</b> <u>6/10/15</u>	DATE	TIME	ELAPSED	CASIN	G	HOLE		ATER	W	ATER
									Dustin Hurd	6/10/15		HOURS 0 ♀	DEPTH	π) υι	<u>=ΡΙΗ (π</u> 5.7		PTH (ft Dry	) ELI	EV (ft)
									YS								,		
ļ	LUCA	TION A	з этаке	:a		1			BULK SAMPLES										1
•	DEPTH (ft)	SAMPLE TYPE AND NUMBER	SPT BLOWS/6" OR REC IN/IN %	N VALUE OR CORE RQD	STRATUM CHANGE DEPTH/EL (ft)	GRAPHIC LOG	nscs	WATER LEVEL	SURFACE EL = 26.0		N		PP (tsf)	NMC %	- #200	ATTI PL	ERBEI	RGS PI	REMARKS
ł					1.3 24.8	1440 140	ž		Aggregate Base (6-incl										
		S1	2-2-3- 3	5	1.8 24.3 4.0	F	СН		Moist, Medium Stiff, Gr [A-7]		AY, trace o	rganics (Fill)	1.20						
	5	S2	2-5-6- 7	11	22.0		<u>~</u> :		Moist, Stiff to Very Stiff [A-6]	, Light Gray	/ CLAY with	n Sand	2.60						
		S3	8-10- 9-9	19	8.0		CL			2.40									
	10	<b>S</b> 4	2-3-4- 4	7	18.0		CL		indy CLAY	1.50						(1)			
		S5	4-5-5- 6	10												(1)			
ł			0		12.0 14.0		1		Termi		+								
NEW GEOTECH BH LOG 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/14/15																			
HBHLOG 1	REM	ARKS: (1	∟ I)Boriı	ng ba	ckfille	ed wi	th dri	ill s	poils at completion	for safet	y purpose	es.		l	1 1				
NEW GEOTECH									12	7									

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-27** 

PAGE 1 OF 1

CLIEN	The \	/Vilson	T. Balla	ard Co	mpan	/			PROJECT	NAME Ba	ack River Ne	ck Road	l Wat	er Mai	n Repl	aceme	ent	
PROJ	ECT LOC	ATION	Baltir	more (	County	, Mar	ylan	<u>d</u>	PROJECT	NUMBER	16613-0: M	<u>D</u> <b>D</b> .	ATE 1	ESTE	<b>D</b> 6/2	26/201	5	
RIG _	Truck CN	1E 45		_ ME	THOE	Hol	low	Stem Auger SAMPL	<b>ER</b> : 2-in O[	O SS	HAN	IMER:	140#	FAL	L: _3	<u>)"</u> A	UTO?	Yes
DATE	STARTE	<b>D</b> 6/1	0/15		_ c	OMPL	ETE	<b>ED</b> 6/10/15		I	WAT ELAPSED	CASIN	/ELS	HOLF	V	VATER	w	ATER
DRILL	.ER Der	nis Str	awdern	nan	_ н	ELPE	R _I	Dustin Hurd	DATE	TIME	HOURS	CASIN DEPTH	(ft) D		ft) DE	PTH (ft	) EL	EV (ft)
REVIE	WED BY	Kriste	opher C	Crist	s	ITE DE	ELA	YS	6/10/15		0 ∑			7.2		Dry		
LOCA	TION A	s Stake	ed				E	BULK SAMPLES 3-6'	_									
DЕРТН (ft)	SAMPLE TYPE AND NUMBER	SPT BLOWS/6" OR REC IN/IN %	N VALUE OR CORE RQD	STRATUM CHANGE DEPTH/EL (ft)	GRAPHIC LOG	nscs	WATER LEVEL		MATERIAL ESCRIPTION	N		PP (tsf)	NMC %	- #200	ATT	ERBE	RGS PI	REMARKS
				1.1				Bituminous Concrete	(14-inches)									
	S1	2-3-3- 2	6	14.9 1.6 14.4 4.0		CL		Aggregate Base (6-inc Wet, Medium Stiff, Br		CLAY [A-6]	]		31					
5	S2	WOH- WOH- WOH-	0	12.0		CL- ML		Wet, Very Soft, Brown	-				29	71	21	28	7	
	<del>}</del>	WOH- 7-8-9 6-7-7-		9.5				Wet, Medium Dense,	Brown Silty S	SAND [A-2	2]		21	-				
10	S4	6 5-8-	14	-		SM							21					(1)
	S5	10-9	18	12.0									27					
				4.0				Tern	ninated at 12	.0 feet								
REMA	ARKS: (*	∟ I)Boriı	ng ba	ckfille	ed wi	th dri	ı ill s	poils at completion	n for safet	y purpos	es.		<u> </u>	1	-		I	1

NEW GEOTECH BH LOG 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/14/15

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-28** 

CL	IENT	The V	Vilson 7	T. Balla	ard Co	mpan	у			PR	OJECT	NAME Ba	ck River Ne	eck Road	d Wat	er Main	Repl	aceme	nt	
PR	OJEC	T LOC	ATION	Baltir	more (	County	, Mar	ylan	ıd	PR	OJECT	NUMBER	16613-0: N	<u>1D</u> <b>D</b> .	ATE 1	<b>TESTED</b>				
RIC	3 Tru	uck CN	IE 45		_ ME	THO	Hol	low	Stem Auger SAMPLE	R:	2-in O[	) SS	HAI	MMER: _	140#	FALL	<u>.: _30</u>	<u>"</u> Al	JTO?	_Yes
DA	TE S	<b>TARTE</b>	<b>D</b> 6/10	0/15		c	OMPL	ETE	ED <u>6/10/15</u>				WA   ELAPSED	TER LEV	VELS G	HOLE	_ v	/ATER	W	ATER
DR	ILLEF	R Den	nis Str	awdern	nan	_ н	ELPE	R _I	Dustin Hurd		DATE	TIME	ELAPSED HOURS	DEPTH	(ft) D	EPTH (ft	DE	PTH (ft	ELI	EV (ft)
RE	VIEW	ED BY	Kristo	opher C	Crist	s	ITE DI	ELA	YS											
LO	CATIO	ON A	Stake	d				E	BULK SAMPLES											
16813-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/14/15		SAMPLE TYPE SAMPLE	Stake	13 4 9 16 16 CORE RQD	12.0 1.0 1.0 1.0 1.0 1.0 1.0 1.0 1.0 1.0 1	GRAPHIC LOG	SOSN SM CL CL SM	WATER LEVEL	SURFACE EL = 13.0  Bituminous Concrete ( Aggregate Base (5-inc Moist, Medium Dense, [A-2]  Wet, Soft, Gray-Brown  Moist, Stiff, Gray Sand [A-6]  Wet, Medium Dense, 0	ft 11-i hes Gra Sa	ndy CLA	n Silty SAN Y (Fill) [A- ce rock fra	-6] gments	2.00	NMC %	- #200	ATTI PL	ERBE	RGS PI	(I) REMARKS
כיז	EMAR	RKS: (1	)Borir	ng ba	ckfille	⊥ ed wi	ith dri	ill s	spoils at completion		r safet	y purpos	es.							

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-29** 

PAGE 1 OF 1

	ECT LOC							_			16613-0: N					aceme	nt	
								Stem Auger SAMPLE				/MER:				O" AI	ITO?	Yes
								ED 6/10/15	.it. <u>2 111 OL</u>	3 00		TER LEV				<u></u>	,	
								Dustin Hurd	DATE	TIME	ELAPSED HOURS	CASING DEPTH (	3	HOLE EPTH (1	t) DE	VATER PTH (ft	W/	ATER EV (ft)
	WED BY							YS	6/10/15		0 ∑	,		5.7		3.0		8.0
	TION A							SULK SAMPLES 3-6'										
															<u> </u>			
DЕРТН (ft)	SAMPLE TYPE AND NUMBER	SPT BLOWS/6" OR REC IN/IN %	N VALUE OR CORE RQD	STRATUM CHANGE DEPTH/EL (ft)	GRAPHIC LOG	nscs	WATER LEVEL		//ATERIAL SCRIPTION ft	N		PP (tsf)	NMC %	- #200	ATT PL	ERBE	RGS PI	REMARKS
				1.1				Bituminous Concrete (	14-inches)									
	S1	4-5-4- 5	9	9.9 1.7 9.3 4.0		CL	Ž	Aggregate Base (7-inc Moist, Stiff, Reddish G		Sandy CLA	Y [A-6]							
5	S2	2-3-3- 4	6	7.0 6.0 5.0	1.20													
	S3	3-4-5- 7 5-5-5-	9	8.0 3.0		[A-2] rown Silty												
10	S4	6 4-5-5-	10	-		,							(1)					
	S5	5	10	12.0		→					1							
				-1.0					inated at 12									
REM	ARKS: (*	1)Borii	ng ba	ckfille	ed wi	th dri	ill s	poils at completion	for safety	y purpos	es.							

NEW GEOTECH BH LOG 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/14/15

130

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-30** 

		IT <u>The \</u>				•	•		-			ick River Ne					aceme	ent	
									<u>d</u>										
									Stem Auger SAMPLE	R: 2-in Ol	) SS		MER:		FALI	_: _30	<u>)"</u> Al	JTO?	_Yes
									<b>ED</b> 6/10/15	DATE	TIME	ELAPSED	CASIN	G	HOLE	V	ATER		ATER
	DRILL	.ER Der	nis Str	awdern	nan	_ н	ELPEI	R _	Dustin Hurd		IIIVIE	HOURS	DEPTH	ft) DI		- 1	PTH (ft		EV (ft)
	REVIE	WED BY	Kristo	opher C	Crist	s	ITE DE	ELA	YS	6/10/15		0 ∑			6.2		3.2	`	9.8
	LOCA	TION A	s Stake	d				E	BULK SAMPLES										
NEW GEOTECH BH LOG 16613-0 BACK RIVER NECK ROAD WATER MAIN GPJ MTA REDLINE GDT 7/14/15	DEPTH (ft)	SAMPLE TYPE SAMPLE TYPE AND NUMBER	% N/N/N/S 2-4-5-4 2-4-3-7 7-7-8-9	9 7 12 9 CORE RQD	STRATUM CHANGE 1.1 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0	GRAPHIC LOG	SOSN CL SM	WATER LEVEL	SURFACE EL = 13.0  Bituminous Concrete ( Aggregate Base (8-incl Moist, Stiff, Brown San  Moist, Medium Stiff, Br  Wet, Medium Dense, E  Wet, Loose to Medium [A-2]	nes) dy CLAY [ own Sandy  Brown Silty S  Dense, Ye	A-6] Clayey SII SAND [A-2 Ilow Brown	Silty SAND	PP (tsf)	% OWN 26 25 25 25 25	- #200	ATTI PL	ERBE	RGS PI	(I) REMARKS
NEW GEOTECH BH LOG	REM	ARKS: (1	)Borii	ng ba	ckfille	ed wi	th dri	ll s	poils at completion		y purpos	es.	•						

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-31** 

PAGE 1 OF 1

	The \								PROJECT	NAME Ba	ack River Ne	ck Road	l Wate	er Mair	n Repl	aceme	ent	
	ECT LOC		Baltir								16613-0: M			ESTE				
RIG _	Truck CN	/IE 45		_ ME	THOE	Hol	low	Stem Auger SAMPL	ER: 2-in O[	D SS		MER: _		FAL	. <b>L</b> : _3	<u>)"</u> Al	JTO?	_Yes
DATE	STARTE	<b>D</b> 6/9	/15		_ C	OMPL	ETE	ED 6/9/15			WA <sup>-</sup> ELAPSED	CASING	/ELS	HOLE	v	VATER	W	ATER
DRILL	.ER Der	nnis Str	awdern	nan	_ н	ELPE	R _I	Dustin Hurd	DATE	TIME		CASING DEPTH (	ft) DE		t) DE	PTH (ft	) ELI	EV (ft)
REVIE	WED BY	Kriste	opher (	Crist	SI	TE D	ELA	YS	6/9/15		0 ⊼			6.0		Dry		
LOCA	TION _O	ffset 3"	West				Е	BULK SAMPLES 2-6'										
DEPTH (ft)	SAMPLE TYPE AND NUMBER	SPT BLOWS/6" OR REC IN/IN %	N VALUE OR CORE RQD	STRATUM CHANGE DEPTH/EL (ft)	GRAPHIC LOG	nscs	WATER LEVEL		MATERIAL ESCRIPTION	N		PP (tsf)	NMC %	- #200	ATT PL	ERBE	RGS PI	REMARKS
				0.8	1940		$\Box$	Bituminous Concrete	·									
_				1.6			$\vdash$	Aggregate Base (9-ind Moist, Medium Stiff, B		Sandy Clay	VAV SILT	-						
	S1	1-3-6- 7	9	19.4		ML		[A-4]	iowii-Olay C	dilay, Olay	y Cy OIL I							
 _ 5	S2	5-5-6- 6	11	4.0 17.0				Moist, Stiff, Brown to	Gray-Brown	Sandy CLA	AY [A-6]	2.70						
	S3	7-8- 10-11	18			CL						3.00						
10	S4	3-6-5- 6	11			02												(1)
	S5	6-6-7- 7	13	12.0														
				9.0	7777			Term	inated at 12	.0 feet		7						
REM	ARKS: (1	⊥ 1)Boriı	∟ ng ba	∟ ckfille	ed wi	th dri	⊥ ill s	poils at completion	for safety	y purpos	es.							

NEW GEOTECH BH LOG 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/14/15

**BORING B-32** PAGE 1 OF 1

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**CLIENT** The Wilson T. Ballard Company PROJECT NAME Back River Neck Road Water Main Replacement PROJECT LOCATION Baltimore County, Maryland PROJECT NUMBER 16613-0: MD DATE TESTED METHOD Hollow Stem Auger SAMPLER: 2-in OD SS **RIG** Truck CME 45 HAMMER: 140# FALL: 30" AUTO? Yes **WATER LEVELS DATE STARTED** 6/9/15 COMPLETED 6/9/15 WATER ELAPSED CASING DEPTH (ft) HOLE WATER DATE TIME DEPTH (ft) ELEV (ft) DRILLER Dennis Strawderman HOURS DEPTH (ft) **HELPER** Dustin Hurd 6/9/15 0 🗸 5.6 Dry **REVIEWED BY** Kristopher Crist SITE DELAYS LOCATION Offset 6' West **BULK SAMPLES** STRATUM CHANGE DEPTH/EL (ft) SAMPLE TYPE AND NUMBER SPT BLOWS/6" OR REC IN/IN 9 GRAPHIC LOG **WATER LEVEL** N VALUE OR CORE RQD MATERIAL REMARKS DEPTH (ft) DESCRIPTION (tst) **ATTERBERGS** USCS - #200 NMC ద SURFACE EL = 21.0 ft PL ы 0.6 Bituminous Concrete (7-inches) 20.4 Aggregate Base (6-inches) 19.9 Moist, Stiff, Brown Sandy SILT [A-4] 4.50 S1 14 8 ML 5 5-7-7 S2 14 3.50 8 6.0 15.0 Moist, Stiff, Brown Sandy CLAY [A-6] 6-7-7 CL 4.50 S3 14 8.0 13.0 Wet, Medium Dense, Orangish Brown Silty SAND [A-2] 3-5-6 SM S4 11 7 10 10.0 (1) 11.0 Wet, Stiff, Brown to Gray Sandy CLAY [A-2] 3-5-5 S<sub>5</sub> 10 CL 0.70 4 12.0 Terminated at 12.0 feet NEW GEOTECH BH LOG 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/14/15

REMARKS: (1)Boring backfilled with drill spoils at completion for safety purposes.

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-33** 

PAGE 1 OF 1

		IT <u>The \</u>					-					ck River Ne					aceme	nt	
		ECT LOC													ESTEC				
									Stem Auger SAMPLE	<b>R</b> : 2-in OI	O SS		MER:		FAL	_: _30	<u>)"</u> Al	JTO?	_Yes
									<b>ED</b> <u>6/9/15</u>	DATE	TIME	ELAPSED	TER LEV	G	HOLE	_ w	ATER	W	TER
									Dustin Hurd			HOURS 0 ▽	DEPTH	(tt) Di			<b>PTH (ft</b> Drv	) ELE	V (ft)
				•						0.0.10					•		,		
	LOCA	TION A	s Stake	ed .				Е	BULK SAMPLES 2-6'										
CK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/14/15	REVIE		Kristo	opher C	Crist	s	ITE DE	ELA	SURFACE EL = 20.0  Bituminous Concrete (SAggregate Base (15 incomposit, Soft, Gray-Brown Moist, Medium Stiff, Gray-Moist, Medium Dense (A-2)  Wet, Medium Stiff, Grafragments [A-6]	O-inches) Ches) In Sandy CL ay Sandy C O Loose, G	AY (Fill) [ACCLAY (Fill) ray-Brown	[A-6] Silty SAND	4.50 2.20	% OWN 23 20 20 19 29	5.7 007# -		ERBEI	RGS	(I) REMARKS
NEW GEOTECH BH LOG 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ	REM	ARKS: (1	)Borii	ng ba	ckfille	ed w	ith dri	ill s	poils at completion		y purpose	<b>.</b> <b>.</b>							
NEW									134	+									

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

BORING B-34
PAGE 1 OF 1

CLIENT The								PROJECT	NAME Ba	ick River Ne	ck Road	Wate	er Mair	n Repl	aceme	nt	
PROJECT LO	CATION	Baltir	more C	County	, Mary	ylan	<u>d</u>	PROJECT	NUMBER	16613-0: M	<u>D</u> <b>D</b> /	TE T	ESTE				
RIG Truck CI			_ ME	THOD	Hol	low	Stem Auger SAMPLI	ER: 2-in O	O SS		MER: _		FAL	<b>L</b> : _30	) <u>"</u> AL	ITO?	Yes
DATE STARTE	<b>ED</b> 6/9/	/15		C	OMPL	ETE	<b>ED</b> 6/9/15			WA <sup>-</sup> ELAPSED	CASING	ELS	HOLE	ı v	/ATER	W	TER
DRILLER De	nnis Str	awdern	nan	_ HI	ELPE	<b>R</b> _[	Dustin Hurd	DATE	TIME		CASING DEPTH (	ft) DE			PTH (ft)	ELE	EV (ft)
REVIEWED BY	/ Kristo	opher C	Crist	SI	TE D	ELA	YS	6/9/15		0 ∑			7.2		7.2	1.	2.8
LOCATION _C	Offset 6'	West				В	ULK SAMPLES										
			Crist  Cr	GRAPHIC LOG	SOSN ML CL SM	WATER LEVEL	SURFACE EL = 20.0 Bituminous Concrete ( Aggregate Base (15-ir Moist, Medium Stiff, B Wet, Soft, Brown Sand Wet, Loose, Brown Sil Wet, Medium Stiff, Graftragments [A-6]	MATERIAL ESCRIPTION  ft (5-inches) rown Sandy  dy CLAY (Fil	SILT (Fill)  I) [A-6] 2]  andy CLAY	[A-4]	(Jst) dd 4.40 0.50 3.00 0.70	NMC %	- #500		ERBEF		(L) REMARKS
REMARKS: /	1)Bori	na ha	ckfille	ad with	th dri	ill e	poils at completion	n for safet	v nurnos	<b>A</b> S							

NEW GEOTECH BH LOG 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/14/15

**BORING B-35** 

PAGE 1 OF 1

3

NEW GEOTECH BH LOG 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/14/15

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**CLIENT** The Wilson T. Ballard Company PROJECT NAME Back River Neck Road Water Main Replacement PROJECT LOCATION Baltimore County, Maryland PROJECT NUMBER 16613-0: MD DATE TESTED METHOD Hollow Stem Auger SAMPLER: 2-in OD SS **RIG** Truck CME 45 HAMMER: 140# FALL: 30" AUTO? Yes **WATER LEVELS DATE STARTED** 6/9/15 COMPLETED 6/9/15 ELAPSED CASING DEPTH (ft) HOLE WATER WATER DATE TIME DEPTH (ft) DRILLER Dennis Strawderman HOURS DEPTH (ft) ELEV (ft) **HELPER** Dustin Hurd 6/9/15 0 🗸 7.0 15.9 6.1 **REVIEWED BY** Kristopher Crist SITE DELAYS LOCATION Offset 5' West BULK SAMPLES 2-5' STRATUM CHANGE DEPTH/EL (ft) SAMPLE TYPE AND NUMBER SPT BLOWS/6" OR REC IN/IN 9 GRAPHIC LOG WATER LEVEL N VALUE OR CORE RQD MATERIAL REMARKS DEPTH (ft) **DESCRIPTION** (tst) **ATTERBERGS** USCS - #200 NMC ద SURFACE EL = 22.0 ft ы ы 0.4Bituminous Concrete (5-inches) 21.6 Aggregate Base (4-inches) 0.7 21.3 Moist, Stiff, Brown CLAY with Sand [A-6] CL 12 S1 15 19 73 17 29 7 4.0 18.0 Moist, Loose, Brown Silty, Clayey SAND [A-4] 5 SC-3-3-4 S2 7 3.30 SM 3 6.0 16.0 Wet, Loose, Brown-Gray Silty SAND [A-2] 3-4-5 9 SM S3 8.0 14.0 Wet, Medium Stiff, Gray Sandy CLAY [A-6] 1-2-3 5 0.50 S4 2 10 CL (1) 4-4-5 S<sub>5</sub> 9 0.70 4 12.0 10.0 Terminated at 12.0 feet REMARKS: (1)Boring backfilled with drill spoils at completion for safety purposes.

136

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-36** 

PAGE 1 OF 1

CLIE	CLIENT The Wilson T. Ballard Company									PROJECT NAME Back River Neck Road Water Main Replacement										
PRO.	JECT LOC	ATION	Baltiı	more (	County	y, Mary	ylan	nd	PROJECT	<u> 1D</u> <b>D</b>	ATE 1	<b>TESTED</b>								
RIG	RIG Truck CME 45 METHOD Hollow Stem Auger SAMPL									ER: 2-in OD SS			140#	FALL	L: <u>30"</u> AUT		ITO?	_Yes		
DATE	STARTE	<b>D</b> 6/9	/15		c	OMPL	ETI	<b>ED</b> <u>6/9/15</u>			WA ELAPSED	TER LEY		HOLE	w	ATER	W	ATER		
DRIL	LER Der	nis Str	awdern	nan	_ н	IELPEI	<b>R</b> _	Dustin Hurd	DATE	TIME	HOURS	DEPTH	(ft) D	EPTH (ft)	DEI	PTH (ft)	ELI	EV (ft)		
REVI	EWED BY	Krist	opher (	Crist	s	ITE DE	ELA	YS	6/9/15		0 ⊼			6.1		Dry				
LOCA	ATION A	s Stake	ed				E	BULK SAMPLES												
NEW GEOTECH BH LOG 16613-0 BACK RIVER NECK ROAD WATER MAIN. GPJ MTA REDLINE.GDT 7/14/15  BA  O  DEPTH (ft)	SAMPLE TYPE  SAMPLE TYPE  AND NUMBER	"9/SMOT LdS"  4-6-7-7  3-4-3-3  5-7-7-8  2-3-4-5-6-6		5.0. 13.0 10.0 10.0 12.0 8.0	GRAPHIC LOG	SOSO CL SC SM CL	WATER LEVEL	Bituminous Concrete (: Aggregate Base (9-inc) Moist, Stiff, Brown San  Moist, Loose to Mediur [A-6]  Moist, Medium Dense, [A-2]  Moist, Loose, Gray Silt  Moist, Stiff, Gray Sand  Termi	5-inches) hes) dy CLAY [A n Dense, B Brown Silty y, Clayey S y CLAY [A nated at 12	rown Clayer SAND with SAND [A-4]	th Gravel	(Jst) dd 2.20 1.20 0.70	% OWN	#50	ATTE	LL	RGS PI	(L) REMARKS		
NEW GEOIECH BH LOC	MARKS: (1	l)Bori	ng ba	ckfille	ed wi	ith dri	ill s	spoils at completion		y purpos	es.									

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

**BORING B-37** 

	CLIENT The Wilson T. Ballard Company									PROJECT NAME Back River Neck Road Water Main Replacement										
	PROJECT LOCATION Baltimore County, Maryland									PROJECT	NUMBER _	16613-0: N	<u>1D</u> <b>D</b> /	ATE T	ESTED					
	RIG Truck CME 45 METHOD Hollow Stem Auger SAMPLE								<b>R:</b> 2-in Ol	O SS	HAN	MER: _	140#	FALI	_: _30	<u>"</u> AL	JTO?	_Yes		
	DATE	STARTE	<b>D</b> 6/9/	/15		c	OMPL	ETE	ED 6/9/15		I	WA' ELAPSED	TER LEV	/ELS	HOI F	W	ATER	W	ATER	
	DRILL	.ER Der	nis Str	awdern	nan	_ н	ELPEI	<b>R</b> _[	Dustin Hurd	DATE	TIME	HOURS	CASING DEPTH (	ft) DE			PTH (ft)		V (ft)	
	REVIE	WED BY	Kristo	opher C	Crist	s	ITE DE	ELΑ	YS	6/9/15		0 ∑			8.7		Dry			
	LOCA	TION A	s Stake	d				В	BULK SAMPLES											
NEW GEOTECH BH LOG 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/14/15	LOCA (#) HLd3O	SAMPLE TYPE  SAMPL	Stake	6 4 5 8 10	12.0 STRATUM CHANGE (#) 0.7 3 1.1 0.0 1.0 0.0	GRAPHIC LOG	SOSN	WATER LEVEL I	SURFACE EL = 21.0  Bituminous Concrete (8 Aggregate Base (6-incl Moist, Medium Stiff, Bri	3-inches) nes) own Sandy	CLAY [A-6		(Jst) dd 2.10 0.60	% OWN 23 21 21 23	- #200	ATTI	ERBEF	RGS	(I) REMARKS	
EW GEOTECH BH LOG 16	REM	ARKS: (1	)Borir	ng ba	ckfille	⊥ ed wi	th dri	∐ ill s	poils at completion		y purpose	es.								
z																				


# APPENDIX B – LABORATORY TEST RESULTS

GRAIN SIZE DISTRIBUTION
TEST METHOD ASTM D422

The Robert B. Balter Company
Geotechnical and Environmental Engineers
Materials and Construction Inspection and Testing
Telephone No. (410) 363-1555
www.balterco.com

**GRAIN SIZE** 

CLIENT The Wilson T. Ballard Company PROJECT NAME Back River Neck Road Water Main Replacement



The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 GRAIN SIZE DISTRIBUTION
TEST METHOD ASTM D422

Telephone No. (410) 363-1555 www.balterco.com CLIENT The Wilson T. Ballard Company PROJECT NAME Back River Neck Road Water Main Replacement PROJECT LOCATION Baltimore County, Maryland PROJECT NUMBER 16613-0: MD **DATE TESTED** U.S. SIEVE OPENING IN INCHES

6 4 3 2 1.5 1 3/4 1/23/8 U.S. SIEVE NUMBERS | 810 14 16 20 30 40 50 60 100 140 200 HYDROMETER 100 95 90 85 80 75 70 65 PERCENT FINER BY WEIGHT 60 55 50 45 40 35 30 25 20 15 10 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/13/15 5 100 10 0.1 0.01 0.001 **GRAIN SIZE IN MILLIMETERS GRAVEL** SAND **COBBLES** SILT OR CLAY coarse fine medium fine coarse Specimen Identification Classification LL PL Ы Cc Cu B-2, S-2 @ 4.5' - 6.0', Brown CLAY with Sand (CL) (Fill) [A-6] 32 18 14 Specimen Identification D100 D60 D30 D10 %Gravel %Sand %Silt %Clay ● B-2, S-2 @ 4.5' - 6.0', 4.75 0.0 17.8 82.2

**GRAIN SIZE** 

## **GRAIN SIZE DISTRIBUTION**

**TEST METHOD ASTM D422** 

3

16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/13/15

**GRAIN SIZE** 

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555

www.balterco.com CLIENT The Wilson T. Ballard Company PROJECT NAME Back River Neck Road Water Main Replacement PROJECT LOCATION Baltimore County, Maryland PROJECT NUMBER 16613-0: MD **DATE TESTED** 6/26/2015 U.S. SIEVE OPENING IN INCHES 6 4 3 2 1.5 1 3/4 1/23<u>/8</u> U.S. SIEVE NUMBERS | 810 14 16 20 30 40 50 60 100 140 200 HYDROMETER 100 95 90 85 80 75 70 65 PERCENT FINER BY WEIGHT 60 55 50 45 40 35 30 25 20 15 10 5 100 10 0.1 0.01 0.001 **GRAIN SIZE IN MILLIMETERS GRAVEL** SAND **COBBLES** SILT OR CLAY coarse fine medium fine coarse Specimen Identification Classification LL PL Ы Cc Cu B-5, S-4 @ 8.0' - 10.0', Dark Grayish Brown CLAY with Sand (CL) (Fill) [A-7-6] 45 19 26 Specimen Identification D100 D60 D30 D10 %Gravel %Sand %Silt %Clay ● B-5, S-4 @ 8.0' - 10.0', 9.5 0.1 19.7 80.1

## **GRAIN SIZE DISTRIBUTION**

**TEST METHOD ASTM D422** 



16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/13/15

**GRAIN SIZE** 

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555

Telephone No. (410) 363-1555 www.balterco.com CLIENT The Wilson T. Ballard Company PROJECT NAME Back River Neck Road Water Main Replacement PROJECT LOCATION Baltimore County, Maryland PROJECT NUMBER 16613-0: MD **DATE TESTED** 6/30/2015 U.S. SIEVE OPENING IN INCHES 6 4 3 2 1.5 1 3/4 1/23/8 U.S. SIEVE NUMBERS | 810 14 16 20 30 40 50 60 100 140 200 HYDROMETER 100 95 90 85 80 75 70 65 PERCENT FINER BY WEIGHT 60 55 50 45 40 35 30 25 20 15 10 5 100 10 0.1 0.01 0.001 **GRAIN SIZE IN MILLIMETERS GRAVEL** SAND **COBBLES** SILT OR CLAY coarse fine coarse medium fine Specimen Identification Classification LL PL Ы Cc Cu B-7, Bulk @ 0.0' - 5.0', Light Brown CLAY with Sand (CL) (Fill) [A-6] 31 18 13 Specimen Identification D100 D60 D30 D10 %Gravel %Sand %Silt %Clay ● B-7, Bulk @ 0.0' - 5.0', 9.5 1.5 14.0 84.6

### **GRAIN SIZE DISTRIBUTION**

**TEST METHOD ASTM D422** 

3

16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/13/15

**GRAIN SIZE** 

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555

www.balterco.com CLIENT The Wilson T. Ballard Company PROJECT NAME Back River Neck Road Water Main Replacement PROJECT LOCATION Baltimore County, Maryland PROJECT NUMBER 16613-0: MD **DATE TESTED** U.S. SIEVE OPENING IN INCHES

6 4 3 2 1.5 1 3/4 1/23/8 U.S. SIEVE NUMBERS | 810 14 16 20 30 40 50 60 100 140 200 HYDROMETER 100 95 90 85 80 75 70 65 PERCENT FINER BY WEIGHT 60 55 50 45 40 35 30 25 20 15 10 5 100 10 0.1 0.01 0.001 **GRAIN SIZE IN MILLIMETERS GRAVEL** SAND **COBBLES** SILT OR CLAY coarse fine medium fine coarse Specimen Identification Classification LL PL Ы Cc Cu B-13, S-4 @ 8.0' - 10.0', Yellowish Red Silty SAND (SM) [A-2-4] NP NP NP Specimen Identification D100 D60 D30 D10 %Gravel %Sand %Silt %Clay ● B-13, S-4 @ 8.0' - 10.0', 4.75 0.35 0.0 86.1 0.188 13.9

#### The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing

**GRAIN SIZE DISTRIBUTION** 

**TEST METHOD ASTM D422** 

16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/13/15

**GRAIN SIZE** 

Telephone No. (410) 363-1555 www.balterco.com

CLIENT The Wilson T. Ballard Company PROJECT NAME Back River Neck Road Water Main Replacement PROJECT LOCATION Baltimore County, Maryland PROJECT NUMBER 16613-0: MD **DATE TESTED** U.S. SIEVE OPENING IN INCHES 6 4 3 2 1.5 1 3/4 1/23/8 U.S. SIEVE NUMBERS | 810 14 16 20 30 40 50 60 100 140 200 HYDROMETER 100 95 90 85 80 75 70 65 PERCENT FINER BY WEIGHT 60 55 50 45 40 35 30 25 20 15 10 5 100 10 0.1 0.01 0.001 **GRAIN SIZE IN MILLIMETERS GRAVEL** SAND **COBBLES** SILT OR CLAY coarse fine medium fine coarse Specimen Identification Classification LL PL Ы Cc Cu B-17, S-4 @ 8.0' - 10.0', Grayish Brown CLAY (CL) [A-4] 28 18 10 Specimen Identification D100 D60 D30 D10 %Gravel %Sand %Silt %Clay ● B-17, S-4 @ 8.0' - 10.0', 0.85 0.0 3.7 96.3

#### GR

**GRAIN SIZE DISTRIBUTION** 

TEST METHOD ASTM D422

The Geometric Marketine Ma

16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/13/15

**GRAIN SIZE** 

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555

www.balterco.com CLIENT The Wilson T. Ballard Company PROJECT NAME Back River Neck Road Water Main Replacement PROJECT LOCATION Baltimore County, Maryland PROJECT NUMBER 16613-0: MD **DATE TESTED** 6/26/2015 U.S. SIEVE OPENING IN INCHES 6 4 3 2 1.5 1 3/4 U.S. SIEVE NUMBERS | 810 14 16 20 30 40 50 60 100 140 200 HYDROMETER 1/23/8 100 95 90 85 80 75 70 65 PERCENT FINER BY WEIGHT 60 55 50 45 40 35 30 25 20 15 10 5 100 10 0.1 0.01 0.001 **GRAIN SIZE IN MILLIMETERS GRAVEL** SAND **COBBLES** SILT OR CLAY coarse fine medium fine coarse Specimen Identification Classification LL PL Ы Cc Cu B-21, Bulk @ 3.0' - 6.0', Brown Sandy CLAY (CL) (Fill) [A-6] 29 17 12 Specimen Identification D100 D60 D30 D10 %Gravel %Sand %Silt %Clay ● B-21, Bulk @ 3.0' - 6.0', 12.5 4.0 26.8 69.2

### **GRAIN SIZE DISTRIBUTION**

**TEST METHOD ASTM D422** 

3

16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/13/15

**GRAIN SIZE** 

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555

www.balterco.com CLIENT The Wilson T. Ballard Company PROJECT NAME Back River Neck Road Water Main Replacement PROJECT LOCATION Baltimore County, Maryland PROJECT NUMBER 16613-0: MD **DATE TESTED** 6/26/2015 U.S. SIEVE OPENING IN INCHES 6 4 3 2 1.5 1 3/4 1/23/8 U.S. SIEVE NUMBERS | 810 14 16 20 30 40 50 60 100 140 200 HYDROMETER 100 95 90 85 80 75 70 65 PERCENT FINER BY WEIGHT 60 55 50 45 40 35 30 25 20 15 10 5 100 10 0.1 0.01 0.001 **GRAIN SIZE IN MILLIMETERS GRAVEL** SAND **COBBLES** SILT OR CLAY coarse fine medium fine coarse Specimen Identification Classification LL PL Ы Cc Cu B-24, S-3 @ 6.0' - 8.0', Dark Yellowish Brown Silty CLAY with Sand (CL-ML) [A-4] 21 17 4 Specimen Identification D100 D60 D30 D10 %Gravel %Sand %Silt %Clay ● B-24, S-3 @ 6.0' - 8.0', 9.5 1.1 23.3 75.6

#### **GRAIN SIZE DISTRIBUTION**

TEST METHOD ASTM D422



16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/13/15

**GRAIN SIZE** 

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555

www.balterco.com CLIENT The Wilson T. Ballard Company PROJECT NAME Back River Neck Road Water Main Replacement PROJECT LOCATION Baltimore County, Maryland PROJECT NUMBER 16613-0: MD **DATE TESTED** 6/26/2015 U.S. SIEVE OPENING IN INCHES

4 3 2 1.5 1 3/4 1/23/8 U.S. SIEVE NUMBERS | 810 14 16 20 30 40 50 60 100 140 200 HYDROMETER 100 95 90 85 80 75 70 65 PERCENT FINER BY WEIGHT 60 55 50 45 40 35 30 25 20 15 10 5 100 10 0.1 0.01 0.001 **GRAIN SIZE IN MILLIMETERS GRAVEL** SAND **COBBLES** SILT OR CLAY coarse fine medium fine coarse Specimen Identification Classification LL PL Ы Cc Cu B-27, S-2 @ 4.0' - 6.0', Light Yellowis Brown Silty CLAY with Gravel (CL-ML) [A-4] 28 21 7 Specimen Identification D100 D60 D30 D10 %Gravel %Sand %Silt %Clay ● B-27, S-2 @ 4.0' - 6.0', 25 15.0 13.5 71.4

The Robert B. Balter Company Geotechnical and Environmental Engineers
Materials and Construction Inspection and Testing

#### **GRAIN SIZE DISTRIBUTION**

**TEST METHOD ASTM D422** 

Telephone No. (410) 363-1555 www.balterco.com CLIENT The Wilson T. Ballard Company PROJECT NAME Back River Neck Road Water Main Replacement PROJECT LOCATION Baltimore County, Maryland PROJECT NUMBER 16613-0: MD **DATE TESTED** U.S. SIEVE OPENING IN INCHES
6 4 3 2 1.5 1 3/4 U.S. SIEVE NUMBERS | 810 14 16 20 30 40 50 60 100 140 200 HYDROMETER 1/23/8 100 95 90 85 80 75 70 65 PERCENT FINER BY WEIGHT 60 55 50 45 40 35 30 25 20 15 10 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/13/15 5 100 10 0.1 0.01 0.001 **GRAIN SIZE IN MILLIMETERS GRAVEL** SAND **COBBLES** SILT OR CLAY coarse fine medium fine coarse Specimen Identification Classification LL PL Ы Cc Cu B-35, Bulk @ 2.0' - 5.0', Brown CLAY with Sand (CL) [A-6] 29 17 12 Specimen Identification D100 D60 D30 D10 %Gravel %Sand %Silt %Clay ● B-35, Bulk @ 2.0' - 5.0', 12.5 1.7 24.9 73.4 **GRAIN SIZE** 


ATTERBERG LIMITS' RESULTS

**TEST METHOD ASTM D4318** 

The Robert B. Balter Company Geotechnical and Environmental Engineers Materials and Construction Inspection and Testing Telephone No. (410) 363-1555 www.balterco.com

CLIENT The Wilson T. Ballard Company

PROJECT NAME Back River Neck Road Water Main Replacement



L					LIQUID LIMIT			
	Specimen Identification	LL	PL	PI	Fines	Classification		
•	B-1, Bulk @ 3.0' - 6.0',	33	17	16	71	Yellowish red CLAY with Sand (CL) (Fill) [A-6]		
	B-13, S-4 @ 8.0' - 10.0',	NP	NP	NP	14	Yellowish Red Silty SAND (SM) [A-2-4]		
4	B-17, S-4 @ 8.0' - 10.0',	28	18	10	96	Grayish Brown CLAY (CL) [A-4]		
<u>ر</u>	B-2, S-2 @ 4.5' - 6.0',	32	18	14	82	Brown CLAY with Sand (CL) (Fill) [A-6]		
7/13/1	B-21, Bulk @ 3.0' - 6.0',	29	17	12	69	Brown Sandy CLAY (CL) (Fill) [A-6]		
	B-24, S-3 @ 6.0' - 8.0',	21	17	4	76	Dark Yellowish Brown Silty CLAY with Sand (CL-ML) [A-4]		
REDLINE	B-27, S-2 @ 4.0' - 6.0',	28	21	7	71	Light Yellowis Brown Silty CLAY with Gravel (CL-ML) [A-4]		
MTA N	B-35, Bulk @ 2.0' - 5.0',	29	17	12	73	Brown CLAY with Sand (CL) [A-6]		
MAIN.GPJ I	B-5, S-4 @ 8.0' - 10.0',	45	19	26	80	Dark Grayish Brown CLAY with Sand (CL) (Fill) [A-7-6]		
	B-7, Bulk @ 0.0' - 5.0',	31	18	13	85	Light Brown CLAY with Sand (CL) (Fill) [A-6]		
16613-0 BACK RIVER NECK ROAD WATER								
SOAD								
Ä								
VER								
ACK R								
13-0 B,								
LIMITS								
ATTERBERG								

#### MOISTURE-DENSITY RELATIONSHIP

CLIENT The Wilson T. Ballard Company PROJECT NAME Back River Neck Road Water Main Replacement PROJECT LOCATION Baltimore County, Maryland PROJECT NUMBER 16613-0: MD **DATE TESTED** 6/26/2015 145 140 B-1, Bulk @ 3.0' - 6.0', Source of Material 135 Yellowish red CLAY with Sand (CL) (Fill) **Description of Material** [A-6] AASHTO T-180 Method C 130 **Test Method Curve Number** 16613-0-001 125 **TEST RESULTS Maximum Dry Density** 130.7 PCF 120 9.8 % **Optimum Water Content** 13.6 % **Natural Water Content** DRY DENSITY, pcf 115 ATTERBERG LIMITS LL Ы 110 Curves of 100% Saturation 105 COMPACTION 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/13/15 for Specific Gravity Equal to: 2.80 100 2.70 2.60 95 90 85 80 75 10 15 20 25 30 35 40

WATER CONTENT, %

MOISTURE-DENSITY RELATIONSHIP

CLIENT The Wilson T. Ballard Company PROJECT NAME Back River Neck Road Water Main Replacement PROJECT LOCATION Baltimore County, Maryland PROJECT NUMBER 16613-0: MD **DATE TESTED** 6/30/2015 145 140 B-7, Bulk @ 0.0' - 5.0', Source of Material 135 Light Brown CLAY with Sand (CL) (Fill) **Description of Material** [A-6] AASHTO T-180 Method C 130 **Test Method Curve Number** 16613-0-004 125 **TEST RESULTS Maximum Dry Density** 124.6 PCF 120 11.6 % **Optimum Water Content** 19.1 % **Natural Water Content** DRY DENSITY, pcf 115 ATTERBERG LIMITS LL PLЫ 110 18 Curves of 100% Saturation 105 COMPACTION 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/13/15 for Specific Gravity Equal to: 2.80 100 2.70 2.60 95 90 85 80 75 10 15 20 25 30 35 40 WATER CONTENT, %

#### MOISTURE-DENSITY RELATIONSHIP

CLIENT The Wilson T. Ballard Company PROJECT NAME Back River Neck Road Water Main Replacement PROJECT LOCATION Baltimore County, Maryland PROJECT NUMBER 16613-0: MD **DATE TESTED** 6/26/2015 145 140 B-21, Bulk @ 3.0' - 6.0', Source of Material 135 **Description of Material** Brown Sandy CLAY (CL) (Fill) [A-6] AASHTO T-180 Method C 130 **Test Method Curve Number** 16613-0-002 125 **TEST RESULTS Maximum Dry Density** 128.9 PCF 120 9.9 % **Optimum Water Content** 17.5 % **Natural Water Content** DRY DENSITY, pcf 115 ATTERBERG LIMITS LL Ы 110 Curves of 100% Saturation 105 COMPACTION 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/13/15 for Specific Gravity Equal to: 2.80 100 2.70 2.60 95 90 85 80 75 10 15 20 25 30 35 40

WATER CONTENT, %

#### MOISTURE-DENSITY RELATIONSHIP

CLIENT The Wilson T. Ballard Company PROJECT NAME Back River Neck Road Water Main Replacement PROJECT LOCATION Baltimore County, Maryland PROJECT NUMBER 16613-0: MD **DATE TESTED** 145 140 B-35, Bulk @ 2.0' - 5.0', Source of Material 135 **Description of Material** Brown CLAY with Sand (CL) [A-6] AASHTO T-180 Method C 130 **Test Method Curve Number** 16613-0-003 125 **TEST RESULTS Maximum Dry Density** 127.1 PCF 120 9.8 % **Optimum Water Content** 18.5 % **Natural Water Content** DRY DENSITY, pcf 115 ATTERBERG LIMITS LL Ы 110 Curves of 100% Saturation 105 COMPACTION 16613-0 BACK RIVER NECK ROAD WATER MAIN.GPJ MTA REDLINE.GDT 7/13/15 for Specific Gravity Equal to: 2.80 100 2.70 2.60 95 90 85 80 75 10 15 20 25 30 35 40 WATER CONTENT, %

### APPENDIX C –PAVEMENT CORE PHOTOGRAPHS



Core	Total Asphalt Thickness (in)	Individual Asphalt Layer Thicknesses (in)	Concrete (in)	Comments
PC-01	13.0	1.00 1.50 1.50 1.50 1.50 1.50 2.00 2.50		Core in fair condition. Voids present between layers, bottom layers not bonded well. Layer 4 exhibits cracking.



Core	Total Asphalt Thickness (in)	Individual Asphalt Layer Thicknesses (in)	Concrete (in)	Comments
PC-02	18.0	2.00 2.00 2.50 3.50	8.00	Core in Fair Condition. Heavy tack coat between layers 1 and 2. Voids present in bottom asphalt layer.



•	Core	Total Asphalt Thickness (in)	Individual Asphalt Layer Thicknesses (in)	Concrete (in)	Comments
F	PC-04	12.5	12.5		Core in Fair Condition. Layers difficult to determine.




Core	Total Asphalt Thickness (in)	Individual Asphalt Layer Thicknesses (in)	Concrete (in)	Comments	
	13.0	1.50 1.50		_	
DC 05		2.50		Core in Good Condition.	
PC-05		1.75			
		2.50			
		3.25			



Core	Total Asphalt Thickness (in) Individual Asphalt Layer Thicknesses (in)		Concrete (in)	Comments	
PC-06	14.0	1.00 1.50 2.00 2.50 1.00 1.00 3.50 1.50		Core in Fair to Poor Condition. Bad layer bonds between layer 1-2 and 4-5. Air voids present at bottom of core.	



Core	Total Asphalt Thickness (in)	Individual Asphalt Layer Thicknesses (in)	Concrete (in)	Comments	
PC-08	8.0	2.00 1.25 1.00 1.50 2.25		Core in Fair Condition to Poor Condition at the base.	



Core	Total Asphalt Thickness (in)	Individual Asphalt Layer Thicknesses (in)	Concrete (in)	Comments
PC-10	9.0	2.00 1.50 1.50 4.00		Core in Good Condition.



Core	Total Asphalt Thickness (in)	Individual Asphalt Layer Thicknesses (in)	Concrete (in)	Comments
PC-12	9.0	2.00 1.50 2.50 3.00		Core in Good Condition.



Core	Total Asphalt Thickness (in)	Individual Asphalt Layer Thicknesses (in)	Concrete (in)	Comments
PC-14	10.0	1.50 1.00 2.00 1.50 1.25 2.00 0.75		Core in Good Condition to Poor Condition at the base.



Core	Total Asphalt Thickness (in)	Individual Asphalt Layer Thicknesses (in)	Concrete (in)	Comments
PC-17	$3.0 \qquad \frac{1.25}{1.75}$			Core in Fair Condition.

## **APPENDIX B**

## **Test Hole Reports**



A I DATA

WHAT'S UNDERGROUND

1100 Batavia Farm Rd., Suite 200 Baltimore, MD 21237

Phone: 410-686-5091 Fax: 410-686-5093

#### **TEST HOLE SUMMARY**

PROJECT: BACK RIVER NECK ROAD

CLIENT: THE WILSON T. BALLARD COMPANY

A/I/DATA PROJECT NO.: 14165

DATE: AUGUST 27, 2015

(ALL MEASUREMENTS IN DECIMAL FEET)

TH#	UTILITY REQUESTED	UTILITY FOUND	COVER	UTILITY ELEVATION	REMARKS
1	48" PRESTRESSED CONCRETE CYLINDER PIPE WATER	48" CAST IRON WATER	7.17	25.60	
2	4" WRAPPED STEEL GAS	4" WRAPPED STEEL GAS	3.57	25.97	
3	8" CAST IRON WATER	8" CAST IRON WATER	5.39	28.20	
4	ELECTRIC	4" PLASTIC ELECTRIC CONDUIT	2.76	35.29	
5	8" CAST IRON WATER	NO UTILITY FOUND	N/A	N/A	EXCAVATED TO A DEPTH OF 4'±
6	GAS	1.5" STEEL GAS	3.30	32.18	
7	12" CAST IRON WATER	12" CAST IRON WATER	5.00	29.24	
8	8" CAST IRON WATER	8" CAST IRON WATER	5.78	31.70	
9	12" CAST IRON WATER	WATER	5.20	31.18	
10	16" CAST IRON WATER	16" CAST IRON WATER	5.78	29.44	
11	60"X38" REINFORCED CONCRETE PIPE STORM DRAIN	60"X38" REINFORCED CONCRETE PIPE STORM DRAIN	3.82	20.05	
12	16" CAST IRON WATER	16" CAST IRON WATER	5.61	19.32	
13	ELECTRIC	6" CAST IRON UNKNOWN PIPE	3.35	20.97	
14	12" CAST IRON WATER	12" CAST IRON WATER	8.07	15.26	
15	8" CAST IRON WATER	NO UTILITY FOUND	N/A	N/A	EXCAVATED TO A DEPTH OF 4'±
16	12" CAST IRON WATER	12" CAST IRON WATER	4.48	16.53	
17	ELECTRIC	(3) 1" PLASTIC ELECTRIC CONDUITS	3.75	19.96	

TH#	UTILITY REQUESTED	UTILITY FOUND	COVER	UTILITY ELEVATION	REMARKS
18	TELECOMMUNICATION	1" PLASTIC TELECOMMUNICATION CONDUIT	2.81	20.78	
19	12" CAST IRON WATER	12" CAST IRON WATER	5.84	12.59	
20	16" DUCTILE IRON SANITARY SEWER FORCE MAIN	ASPHALT	4.94	13.47	
21	CATV	0.75 CATV DIRECT BURIED CABLE	2.29	15.75	
22	TELECOMMUNICATION	4" PLASTIC TELECOMMUNICATION CONDUIT	3.40	20.21	
23	12" CAST IRON WATER	12" CAST IRON WATER	5.62	17.18	
24	16" CAST IRON WATER	16" CAST IRON WATER & 1.25" STEEL WATER	4.67	17.33	DEPTH TO 1.25" WATER = 4.38
25	WATER	20" STEEL WATER CASING	4.23	10.23	



Accurate Infrastructure Data, Inc.

1100 Batavia Farm Rd., Suite 200 Baltimore, MD 21237

Phone: 410-686-5091 Fax: 410-686-5093

#### **TEST HOLE SUMMARY**

PROJECT: BACK RIVER NECK ROAD

CLIENT: THE WILSON T. BALLARD COMPANY


A/I/DATA PROJECT NO.: 14165.01


DATE: MAY 12, 2016


(ALL MEASUREMENTS IN DECIMAL FEET)


TH#	UTILITY REQUESTED	UTILITY FOUND	COVER	UTILITY ELEVATION	REMARKS
26	24" WATER PRESTRESSED CONCRETE CYLINDER PIPE	24" WATER PRESTRESSED CONCRETE CYLINDER PIPE, 1" COPPER WATER, & 2"- THICK WOOD SHEET	6.12	23.41	DEPTH TO 1" COPPER WATER = 4.45 DEPTH TO 2" THICK WOOD SHEET = 4.80
27	6" CAST IRON GAS	6" WRAPPED STEEL GAS	4.01	22.50	
28	8" CAST IRON WATER	8" CAST IRON WATER	4.37	21.83	
29	8" CAST IRON WATER	8" CAST IRON WATER	4.93	20.70	
30	TELECOMMUNICATION	CONCRETE TELECOMMUNICATION DUCT	TOP 6.67 BOT 7.96	TOP 26.10 BOT 24.81	
31	6" CAST IRON GAS	6" GAS	3.09	34.22	
32	8" CAST IRON WATER	8" CAST IRON WATER	4.43	29.94	
33	TELECOMMUNICATION	(3) 4" PLASTIC TELECOMMUNICATION CONDUITS & (2) TELECOMMUNICATION DUCTS	5.05	29.30	DEPTH TO TOP OF UPPER DUCT = 5.60 DEPTH TO BOTTOM OF LOWER DUCT = 8.00
34	24" WATER PRESTRESSED CONCRETE CYLINDER PIPE	24" WATER PRESTRESSED CONCRETE CYLINDER PIPE	6.50	27.83	
35	8" CAST IRON WATER	8" CAST IRON WATER	5.69	27.96	
36	8" WATER	8" DUCTILE IRON WATER	5.36	30.17	
37	6" WRAPPED STEEL GAS	6" WRAPPED STEEL GAS	3.00	34.11	
38	8" DUCTILE IRON WATER	8" DUCTILE IRON WATER	4.51	18.09	
39	12" DUCTILE IRON WATER	12" WATER	7.15	14.46	
40	12" CAST IRON WATER	NO UTILITY FOUND	N/A	N/A	TEST HOLE EXCAVATED TO A DEPTH OF 3±
41	8" WATER	8" DUCTILE IRON WATER	4.35	13.92	


TH#	UTILITY REQUESTED	UTILITY FOUND	COVER	UTILITY ELEVATION	REMARKS
42	12" WATER	12" WATER	4.94	3.92	
43	16" CAST IRON WATER	16" CAST IRON WATER	4.28	18.12	
44	16" CAST IRON WATER	16" DUCTILE IRON WATER	4.80	17.41	
45	16" CAST IRON WATER	16" DUCTILE IRON WATER	6.90	15.12	
46	16" CAST IRON WATER	16" DUCTILE IRON WATER	4.32	17.43	
47	16" CAST IRON WATER	16" DUCTILE IRON WATER	5.60	16.00	
48	16" CAST IRON WATER	16" DUCTILE IRON WATER	5.92	14.59	
49	16" DUCTILE IRON WATER	NO UTILITY FOUND	N/A	N/A	TEST HOLE EXCAVATED TO A DEPTH OF 9±.
50	16" CAST IRON WATER	16" DUCTILE IRON WATER	5.16	15.34	
51	16" CAST IRON WATER	16" DUCTILE IRON WATER	5.76	15.11	
52	16" DUCTILE IRON WATER	16" DUCTILE IRON WATER	4.26	18.03	
53	16" DUCTILE IRON WATER	16" DUCTILE IRON WATER	4.28	16.97	
54	16" DUCTILE IRON WATER	16" DUCTILE IRON WATER	4.76	16.25	
55	16" DUCTILE IRON WATER	16" DUCTILE IRON WATER	4.15	17.24	











































































UTILITY POLE









16.3


23.6


WV


6"G


44.8


BACK RIVER NECK ROAD














TEST HOLE DATA SHEET JOB #: 14165.01 TEST HOLE #: 32 PROJECT NAME: BACK RIVER NECK ROAD **EXCAVATION BY:** DATE DUG: 04/28/2016 A/I/DATA PROJECT LOCATION: FORM BY: GMZ BALTIMORE COUNTY, MARYLAND ASSISTED BY: EJN, JPS CHECKED BY: JPM CLIENT NAME: THE WILSON T. BALLARD COMPANY PAVING CONDITION: **GOOD** UTILITY REQUESTED: 8" CAST IRON WATER GENERAL SOIL CONDITIONS: HARD MOIST CLAY UTILITY FOUND: 8" CAST IRON WATER UTILITY CONDITION: **GOOD** SECTION VIEW OF TEST HOLE MARKER SURVEYED BY: A/I/DATA NOT TO SCALE SURVEY PK NAIL MARKING TAPE INSTALLED: **ELEV SURVEY MARKER** ABOVE: CROWN OF UTILITY **BLUE** 34.37 CONTROL POINTS PROVIDED BY: THE WILSON T. BALLARD CO. **EXISTING** N= 598553.06 E= 1469397.57 ELEV= 34.90 PK NAIL **GRADE** N= 599127.32 E= 1468913.97 ELEV= 36.18 REBAR & CAP 0.5 ASPHALT SURFACE **THICKNESS** AND MATERIAL DEPTH (TOP) A/I/DATA MARKER: NORTHING **EASTING ELEVATION** 598538.08 1469434.93 34.37 4.43 NOTES: 29.94 ELEV. (TOP) DEPTH (BOTTOM) SECTION ALL MEASUREMENTS ARE SHOWN IN DECIMAL FEET EXCEPT WHERE NOTED DRAWN TEST HOLE DATA PRODUCED BY: WIDTH **FACING** ACCURATE INFRASTRUCTURE DATA, INC. 1123 HANZLIK AVENUE, BALTIMORE, MD 21237 9.5"± NE ELEV. (BOTTOM) PH: 410-686-5091 FAX: 410-686-5093 PLAN VIEW OF TEST HOLE





TEST HOLE DATA SHEET JOB #: 14165.01 TEST HOLE #: 33 PROJECT NAME: BACK RIVER NECK ROAD EXCAVATION BY: DATE DUG: 05/02/2016 A/I/DATA PROJECT LOCATION: BALTIMORE COUNTY, MARYLAND FORM BY: GMZ ASSISTED BY: EJN, JPS CHECKED BY: JPM CLIENT NAME: THE WILSON T. BALLARD COMPANY PAVING CONDITION: GOOD UTILITY REQUESTED: TELECOMMUNICATION GENERAL SOIL CONDITIONS: HARD DRY SAND ROCKY (3) 4" PLASTIC TELECOMMUNICATION CONDUITS & UTILITY FOUND: UTILITY CONDITION: **GOOD** TELECOMMUNICATION DUCTS (SEE NOTES) SECTION VIEW OF TEST HOLE MARKER SURVEYED BY: A/I/DATA NOT TO SCALE SURVEY PK NAIL MARKING TAPE INSTALLED: **ELEV SURVEY MARKER** ABOVE: CROWN OF UTILITY **ORANGE** 34.35 CONTROL POINTS PROVIDED BY: THE WILSON T. BALLARD CO. **EXISTING** N= 598553.06 E= 1469397.57 ELEV= 34.90 PK NAIL **GRADE** N= 599127.32 E= 1468913.97 ELEV= 36.18 REBAR & CAP 0.7 ASPHALT **SURFACE THICKNESS** AND MATERIAL DEPTH (TOP) A/I/DATA MARKER: NORTHING **EASTING ELEVATION** 598524.40 1469408.08 34.35 -1.25--5.05 (3) 4" TELECOM CÓNDUITS NOTES: 29.30 PK NAIL SET OVER CROWN OF NE CONDUIT. NE EDGE OF DUCTS ELEV. (TOP) OBSCURED BY CONDUITS. UNABLE TO DETERMINE MATERIAL OF DUCTS. (2) TELECOM DUCTS DEPTH TO TOP OF UPPER DUCT = 5.60. DEPTH TO BOTTOM OF LOWER DUCT = 8.00.DEPTH (BOTTOM) SECTION ALL MEASUREMENTS ARE SHOWN IN DECIMAL FEET EXCEPT WHERE NOTED DRAWN TEST HOLE DATA PRODUCED BY: WIDTH **FACING** ACCURATE INFRASTRUCTURE DATA, INC. 1123 HANZLIK AVENUE, BALTIMORE, MD 21237 SEE NOTES




203













## TEST HOLE DATA SHEET JOB #: 14165.01 TEST HOLE #: 38 PROJECT NAME: BACK RIVER NECK ROAD EXCAVATION BY: DATE DUG: 05/03/2016 A/I/DATA PROJECT LOCATION: BALTIMORE COUNTY, MARYLAND FORM BY: GMZ ASSISTED BY: EJN, JPS, JEM CHECKED BY: JPM CLIENT NAME: THE WILSON T. BALLARD COMPANY PAVING CONDITION: GOOD UTILITY REQUESTED: 8" DUCTILE IRON WATER GENERAL SOIL CONDITIONS: SOFT MOIST CLAY UTILITY FOUND: 8" DUCTILE IRON WATER (SEE NOTES) UTILITY CONDITION: **GOOD** SECTION VIEW OF TEST HOLE MARKER SURVEYED BY: A/I/DATA NOT TO SCALE SURVEY PK NAIL MARKING TAPE INSTALLED: **ELEV SURVEY MARKER** ABOVE: CROWN OF UTILITY **BLUE** 22.60 CONTROL POINTS PROVIDED BY: THE WILSON T. BALLARD CO. **EXISTING** N= 593833.17 E= 1472820.23 ELEV= 20.28 **REBAR & CAP GRADE** ELEV= 22.92 REBAR & CAP N= 594228.57 E= 1472547.59 0.5 ASPHALT SURFACE **THICKNESS** AND MATERIAL DEPTH (TOP) A/I/DATA MARKER: NORTHING **EASTING ELEVATION** 594269.50 1472527.32 22.60 4.51 NOTES: 18.09 UNABLE TO MEASURE DIAMETER OF PIPE DUE TO CONCRETE ELEV. (TOP) ENCASEMENT FOR A BEND. RECORDS INDICATE A 8" PIPE AT THIS LOCATION. PK NAIL SET OVER CROWN OF PIPE, 2.2 NE OF CENTER OF **CONCRETE** BEND. **ENCASEMENT** DEPTH (BOTTOM) SECTION ALL MEASUREMENTS ARE SHOWN IN DECIMAL FEET EXCEPT WHERE NOTED DRAWN


TEST HOLE DATA PRODUCED BY:
























WV


STATE OF THE PERSON OF THE PER





UTILIT POLE




TEST HOLE DATA SHEET












TEST HOLE DATA SHEET 14165.01 TEST HOLE #: 49 **EXCAVATION BY:** PROJECT NAME: BACK RIVER NECK ROAD A/I/DATA DATE DUG: 05/05/2016 FORM BY: GMZ PROJECT LOCATION: BALTIMORE COUNTY, MARYLAND ASSISTED BY: EJN, JPS CHECKED BY: JPM CLIENT NAME: THE WILSON T. BALLARD COMPANY PAVING CONDITION: **FAIR** UTILITY REQUESTED: 16" DUCTILE IRON WATER GENERAL SOIL CONDITIONS: HARD WET CLAY UTILITY FOUND: NO UTILITY FOUND (SEE NOTES) UTILITY CONDITION: N/A SECTION VIEW OF TEST HOLE MARKER SURVEYED BY: A/I/DATA NOT TO SCALE MARKING TAPE INSTALLED: SURVEY PK NAIL **ELEV SURVEY MARKER** ABOVE: SEE NOTES OF UTILITY WHITE 20.22 CONTROL POINTS PROVIDED BY: THE WILSON T. BALLARD CO. **EXISTING** 101 N= 586591.24 E= 1474608.44 ELEV= 20.37 **REBAR & CAP** GRADE E= 1474582.27 **REBAR & CAP** 0.6 ASPHALT 1144 N= 587066.83 ELEV= 20.98 SURFACE THICKNESS AND MATERIAL DEPTH (TOP) A/I/DATA MARKER: NORTHING **EASTING ELEVATION** 1474550.69 587512.16 20.22 N/A NOTES: N/A TEST HOLE EXCAVATED TO A DEPTH OF 9±. UNABLE TO CONTINUE DUE ELEV. (TOP) TO GROUND WATER IN TEST HOLE. NO UTILITY FOUND. PK NAIL SET TEST HOLE ATTEMPT OVER ELECTRONIC SIGNAL. (NO UTILITY FOUND) DEPTH (BOTTOM) SECTION ALL MEASUREMENTS ARE SHOWN IN DECIMAL FEET EXCEPT WHERE NOTED DRAWN TEST HOLE DATA PRODUCED BY: WIDTH **FACING** ACCURATE INFRASTRUCTURE DATA, INC. 1123 HANZLIK AVENUE, BALTIMORE, MD 21237 N/A N/A ELEV. (BOTTOM) PH: 410-686-5091 FAX: 410-686-5093 PLAN VIEW OF TEST HOLE




TEST HOLE DATA SHEET 14165.01 TEST HOLE #: 50 **EXCAVATION BY:** PROJECT NAME: BACK RIVER NECK ROAD A/I/DATA DATE DUG: 05/05/2016 PROJECT LOCATION: BALTIMORE COUNTY, MARYLAND FORM BY: GMZ ASSISTED BY: EJN, JPS CHECKED BY: JPM CLIENT NAME: THE WILSON T. BALLARD COMPANY PAVING CONDITION: **FAIR** UTILITY REQUESTED: 16" CAST IRON WATER GENERAL SOIL CONDITIONS: HARD MOIST CLAY ROCKY UTILITY FOUND: 16" DUCTILE IRON WATER UTILITY CONDITION: **GOOD** SECTION VIEW OF TEST HOLE MARKER SURVEYED BY: A/I/DATA NOT TO SCALE MARKING TAPE INSTALLED: SURVEY PK NAIL ABOVE: CROWN OF UTILITY **ELEV SURVEY MARKER** BLUE 20.50 CONTROL POINTS PROVIDED BY: THE WILSON T. BALLARD CO. **EXISTING** 101 N= 586591.24 E= 1474608.44 ELEV= 20.37 **REBAR & CAP** GRADE E= 1474582.27 REBAR & CAP 0.6 ASPHALT 1144 N= 587066.83 ELEV= 20.98 SURFACE THICKNESS AND MATERIAL DEPTH (TOP) A/I/DATA MARKER: NORTHING **EASTING ELEVATION** 1474549.39 587318.89 20.50 5.16 15.34 NOTES: ELEV. (TOP) DEPTH (BOTTOM) **SECTION** ALL MEASUREMENTS ARE SHOWN IN DECIMAL FEET EXCEPT WHERE NOTED DRAWN TEST HOLE DATA PRODUCED BY: WIDTH **FACING** ACCURATE INFRASTRUCTURE DATA, INC. 1123 HANZLIK AVENUE, BALTIMORE, MD 21237 17.75"± **NORTH** ELEV. (BOTTOM) PH: 410-686-5091 FAX: 410-686-5093 PLAN VIEW OF TEST HOLE DIMENSIONS GOVERN; DO NOT SCALE TO SOMOGYI ROAD UTILITY POLE 35.5 UTILITY POLE 27.0 88.2 BACK RIVER NECK ROAD UTILITY **POLE** TO BAY AVENUE

220











223


MAILBOX



































#### **APPENDIX C**

### **Valve Shutdown Request Form**

# **Baltimore City & Baltimore County Contractor Shutdown Request Form**

Date Form Submitted		Submittal #				
	ng request form <i>must be email</i> l request to <b>Natassia.Landefel</b> d	led ten (10) working days prior to requested @baltimorecity.gov				
а	nd copy: Kris.Carter@baltimorec Jonathan.Cohen@baltim DWalker@baltimorecity.	orecity.gov				
If you have any questions, o	or need additional assistance, ple	ease call Ms. Landefeld at 410-709-8289.				
General Information						
Contract	Charge No: (For Contract Only)	Contract / D.A. Name & Number:				
Developer's Agreement (Check One)						
Contact Information (Tea	am listed below is responsible for '	72 hours advanced public notifications of water outages)				
Resident Engineer or Field Inspector Name: (Check One)	•	Resident Engineer or Field Inspector Phone #: Email:				
Contractor	Contractor	Contractor				
Name:	Phone #:	Email:				
Field Contact Name:		Field Contact Phone #:				
Shutdown Information		her or other cancellations, please contact allow at least 72 hours for the new date.				
Requested Date / Time						
Description of Work						
Location of Construction (address and/or street from point A to point B)						
☐ Copy of Relevant D.A./ Contract Drawing Attached						
Estimated Time of Water Work Construction						
Number of Services Affected						
Significant Consumers Affected						
Resident Engineer / Field	Contractor	Date				

#### APPENDIX D

# BALTIMORE COUNTY DEPARTMENT OF ENVIRONMENTAL PROTECTION & SUSTAINABILITY STORMWATER MANAGEMENT VARIANCE

(see Page 242 of Permits Section)

#### **APPENDIX E**

# MARYLAND DEPARTMENT OF THE ENVIRONMENT

(see Pages 245-248 of Permits Section)

#### SECTION III

#### **Permits**



# Baltimore County, Maryland Department of Permits, Approvals, and Inspections BUILDING PERMIT

Permit Number: CEN25-000055 Permit Type: Commercial Environmental

**Sub Type:** Grading

**Date Issued**: 09/30/2025 **Expiration Date**: 09/29/2027

Property Information				
Property Address: Back River Neck Rd (Homberg Ave-North of Hyde Pk Rd				
City, State, Zip: Essex, MD 21221				
Tax ID:				
District:				
Existing Use:				
Proposed Use:				
Is this property located in a Floodplain:				
Sprinkler to be Installed?:				
Plumbing Work?:				
Electrical Work?:				

#### **Owner Information**

Owner: Baltimore County DPW&T

Owner Address: 111 West Chesapeake Avenue, Towson, MD, 21204

Tenant: Applicant: Omar Muhammad

C. Pete Gutuald, AICP, Director

E. John Bryan

E. John Bryan, Building Engineer

\*Please log into your account to get up-to-date information regarding the permit process and related inspections. Refer to the Permit Number when making inquires.



# Baltimore County, Maryland Department of Permits, Approvals, and Inspections BUILDING PERMIT

Permit Number: CEN25-000055 Permit Type: Commercial Environmental

Sub Type: Grading

**Date Issued**: 09/30/2025 **Expiration Date**: 09/29/2027

Building Permit Contractor				
Name of Contractor:				
Phone Number:				
Address:				
City, State, Zip: , ,				
Is Owner Contractor?:				

#### **Building Permit Information**

**Description of Work:** Grade 40,887SF for water main. Permit expires two years from date of issue. No construction to begin until pre-construction meeting. Failure to comply will result in penalties. Schedule your pre-construction meeting in your portal

C. Pate Gutuald, AICP, Director

E. John Bryan

E. John Bryan, Building Engineer

\*Please log into your account to get up-to-date information regarding the permit process and related inspections. Refer to the Permit Number when making inquires.



KATHERINE A. KLAUSMEIER County Executive

HORACIO TABLADA, Director Department of Environmental Protection and Sustainability

May 14, 2025

The Wilson T. Ballard Company 17 Gwynns Mill Court Owings Mills, MD 21117 Attn: Daniel Savage

RE: Back River Neck Road 24- and 16-inch Water Main

Replacement - Phase 3

Stormwater Management Variance

Back River Watershed **Project I.D. M180190** 

Tracking Number: 07-25-4333

#### Dear Daniel Savage;

This office has reviewed the information submitted and finds that a stormwater management variance can be granted for this project under Section 33-4-113 (a) (2) of Title 4 of the Baltimore County Code. Section 33-4-113 (a) (2) allows a stormwater management variance to be granted if there are exceptional circumstances such that strict adherence to the provisions of the design standards would result in unreasonable hardship or practical difficulty and not fulfill the intent of the regulations.

This project is for the installation of 5,250 linear feet of 24 inch and 16-inch ductile iron water mains, including shorter sections of smaller diameter water main connections by cut and cover. The existing cover conditions will be re-established once the water mains are installed. Although the disturbed area is in excess of 5,000 square feet, there will be no increase in impervious area or runoff resulting from the project.

Please contact Abiy Geleta, P.E. at 410-887,3768 should you have any questions.

Very truly yours,

Kritty Udhin, P.E., Manager Stormwater Management

KU:ag

c:

## BALTIMORE COUNTY, MARYLAND DEPARTMENT OF ENVIRONMENTAL PROTECTION AND SUSTAINABIL ENVIRONMENTAL AGREEMENT Baltimore

ABILIAR 3 2025

Baltimore County Environmental Finance Administration

All grading and stormwater management permit application numbers should be included on this Environmental Agreement (EA). Please return completed form with ORIGINAL signatures to EPS, 111 W. Chesapeake Avenue, Room 319, Towson, MD 21204.

#### **ENVIRONMENTAL AGREEMENT** for:

M180190

g. Other (Specify)

Required performance security amount

Project Name: <u>24-in and 16-in Water Main Replacement Phase 3</u>
Back River Neck Road

J.O. 231-203-0067-0783, C# 23186-WXO

Plat Reference: N/A

Tax Acct. No. N/A

Total Estimated Cost: N/A

(All Environmental Securities) Grading Permit # CEN25-000055 Stormwater Management Permit # N/A EIR Plan #'s N/A THIS ENVIRONMENTAL AGREEMENT, NUMBER 64-2025 made this , 20 by and between Baltimore County Department of Public Works and Transportation hereinafter referred to as the applicant, party of the first part, and BALTIMORE COUNTY, MARYLAND, a political subdivision of the State of Maryland, hereinafter referred to as the County, party of the second part. WHEREAS, the applicant agrees to implement all environmental measures as set forth in this agreement, at no cost to the County, including: **AMOUNT** APP./DATE a. Grading, erosion and sediment control Required performance security amount N/A b. Storm water management Required performance security amount (List facilities separately) N/A c. Forest conservation Required performance security amount N/A d. Forest buffer mitigation Required performance security amount N/A e. Wetland mitigation Required performance security amount N/A f. Chesapeake Bay Critical Area Mitigation Required performance security amount N/A

N/A

#### Now, THEREFORE, THIS AGREEMENT WITNESSETH:

THAT, for and in consideration of the provisions and benefits herein contained, the parties do hereby agree as follows:

- 1. The applicant agrees:
- a. To implement all required environmental measures for this project in accordance with applicable permits, plans and performance requirements.
- b. To post security(ies) with the County as required in Baltimore County Code Section 32-4-312, in accordance with applicable time frames and procedures specified in the Baltimore County Code and the Department of Environmental Protection and Sustainability Policy, Rules and Regulations Manual.
- c. To process any request(s) for reduction to security(ies) in accordance with Baltimore County Code Section 32-4-313 and the Department of Environmental Protection and Sustainability Policy, Rules and Regulations Manual.

WITNESS the signatures of:

Date: _3/28/2025	Signed: Lisa K Eicholtz On and Control
Printed Name: Lisa K. Eicholtz	Title, if applicable: Deputy Director, DPWT
Witness Signature:	_ Address: County Office Building
Witness Printed Name:	111 W. Chesapeake Ave., Suite 307 Towson MD
	Email: <u>Leicholtz@baltimorecountymd.gov</u>
	Phone: 410-887-3788

**APPROVED** 

Director of Environmental Protection and Sustainability

Horacio Tablada

4pr. 1, 2025

By





#### WATER AND/OR SEWERAGE CONSTRUCTION PERMIT

Permit No.: 24-11-1007 Date Issued: 2/20/2025 Permit Fee: N/A Expiration Date: 2/20/2028

This permit authorizes Baltimore County Department of Public Works to construct a Water Main Replacement together with all appurtenances, at the site of Back River Neck Rd from Homberg Ave to Hyde Park Rd, Baltimore County, in accordance with an application dated 01/10/2024 and received by the Maryland Department of the Environment on 01/17/2024 titled in part:

24-INCH AND 16-INCH WATER MAIN REPLACEMENT – PHASE 3 BACK RIVER NECK ROAD FROM HOMBERG AVENUE TO NORTH OF HYDRE PARK ROAD BALTIMORE COUNTY CONTRACT NO. 23186-WXO SHEET NOS. 1 THRU 35 OF 35

#### THIS PERMIT IS ISSUED SUBJECT TO THE ATTACHED FOLLOWING CONDITIONS:

Note: This permit may be suspended or revoked upon a final, unreviewable determination that the permittee lacks, or is in violation of federal, state or local approval necessary to conduct the activity authorized by this permit.

Walid Saffouri, P.E., Program Administrator Engineering & Capital Projects Program Water and Science Administration

#### GENERAL CONDITIONS FOR WATER OR SEWERAGE CONSTRUCTION PERMIT

- The structural adequacy and expected performance characteristics of the various components are not certified by this permit.
- This permit is not transferable.
- A copy of this permit must be posted at the work site during construction.
- This permit will expire, if not specifically extended, unless the construction authorized under this permit has been initiated. The permit will then remain valid for the remainder of construction for a period of up to five years from the start of construction.
- If any provision of this permit shall be held invalid for any reason, the remaining provisions shall remain in full force and effect, and such invalid provision shall be considered severed and deleted from this permit.
- Persons violating the requirements of this permit are subject to penalties of up to \$1000 per day as set forth in Environment Article 9-268 and 9-334 through 9-342, Annotated Code of Maryland.
- A copy of the plans and specifications, authorized for use under this permit, shall be made available at the
  work site during construction of this project. A revised construction permit in accordance with COMAR
  26.03.12 is required prior to making substantive changes or material alteration to the construction
  authorized under this permit.
- The owner shall secure all Federal, State or local permits, including approval of Sedimentation and Erosion Control Plans that may be required before starting the construction of the project.
- The owner shall insure that this project is inspected during the progress of construction to assure substantial compliance with the approved plans and specifications. A log and construction records shall be maintained by the inspector and may be requested for review at any time by this office.
- The project engineer of the Maryland Department of the Environment (the 'Department') shall be notified prior to the start of construction.
- Inspectors of the Department shall be afforded access to the project site, at reasonable times and upon presentation of credentials:
  - a. to inspect construction authorized under this permit and to determine compliance with applicable regulations;
  - b. to have access to and copy any records required to be kept by this permit and by applicable regulations; and
  - c. to obtain any photographic documentation or evidence.
- Within 60 days after completion of construction, a copy of as-built drawings and the attached construction completion certificate (page 3 of this permit) shall be submitted to the Department. Where construction was completed in accordance with the original plans approved under this permit, the submittal of as-built drawings will not be required.
- The owner shall maintain a permanent record of the as-built drawings, or the original plans if as-built drawings are not required.

6/2022

#### GENERAL CONDITIONS (CONTINUED)

- Pursuant to Labor & Employment Article 9-201, the owner shall ensure that the contractor and subcontractors involved in the construction of this project must carry workers' compensation insurance for their employees. If the owner determines to perform the project construction by his/her labor force, the owner shall provide the same. If the entity, undertaking the project construction, is not covered by a workers' compensation policy, a Certificate of Compliance shall be submitted and approved by the Workers' Compensation Commission before initiation of the construction.
- Approval must be obtained from the Department before this project may be placed into service. Any exception allowing partial use of this project shall have the prior written approval of the Department. Approval may be obtained pursuant to the following procedure:
  - a. Where large political subdivisions, commissions, authorities etc. have their own inspection capabilities (satisfactory to the Department), the attached construction completion certificate shall be completed by the director of Public Works or similar responsible person and submitted to the Department.
  - b. Where an acceptable local construction inspection program does not exist, the attached construction completion certification shall be completed by a Professional Engineer licensed to practice in the State of Maryland (preferably the same engineer whose seal and signature appear on the plans approved under this permit) and submitted to the Department.
  - c. Upon receipt of the signed certificate, the Department shall, within (30) working days of the receipt, 1) issue an approval, 2) require further review and on-site inspection or 3) reject the construction certification. Approval shall be automatic for projects that have not received some form of written notification from the Department within (30) working days of receipt of the signed certificate.

24-11-1007

Permit Number

Stephen Liu
Project Engineer
Engineering & Capital Projects Program

#### WATER AND SEWER CONSTRUCTION COMPLETION CERTIFICATION

S		zed by this permit has been compl nvironment Article 9-204, Annota	
Signature	Title	Date	
The above project has bee Annotated Code of Maryla		nt within the terms of Environmen	t Article 9-204
Authorized Official			

Complete this certificate and return to:
Maryland Department of the Environment
Engineering & Capital Projects Program (ECPP)
Office of Budget and Infrastructure Financing
1800 Washington Boulevard
Baltimore, MD 21230

06/2022



#### **NOTICE**

Prior to starting construction, please notify Stephen Liu, Project Engineer at <a href="mailto:stephen.liu@maryland.gov">stephen.liu@maryland.gov</a>. Upon completion of the project, the construction must be certified with the signed permit returned to this office along with a set of as-built drawings.

Should you have any questions concerning the permit or its conditions, please contact me at walid.saffouri@maryland.gov.

Sincerely,

Walid Saffouri, Program Administrator Engineering and Capital Projects Program

Water and Science Administration

#### **SECTION IV**

**Proposal** 

This Section to be Completed by Time of Bid

#### SECTION-IV PROPOSAL

#### **DESCRIPTION OF WORK**

Bid Opening via Teleconference WebEx <u>Thursday</u>, <u>November 13, 2025 at 10:30 a.m. EST</u> via WebEx Phone Number 1-415-655-0001, Access Code Number 2307 981 0516##.

Begin Work Within Fifteen (15) Days After NOTICE TO PROCEED

Working Days for Completion: FOUR HUNDRED (400)

Liquidated and Other Damages: FIVE HUNDRED (\$500.00) PER WORKING DAY

Cost Group "F (\$5,000,001 to \$10,000,000)" (Prequalified contractors with a Cost Group restriction must bid within the dollar amount stated on their Certificate of Prequalification).

Work Classification: F-2

TO BALTIMORE COUNTY, MARYLAND: The work to be completed under this Contract includes all labor, materials, and equipment necessary to furnish and install various diameter ductile iron water mains along Back River Neck Road from Homberg Avenue to Hyde Park Road. Essex – District 15c7.

The following listed Drawing Number(s) are collectively the "Drawings", and are hereby incorporated in the Contract.

<u>Job Order Number</u> <u>Workday Number</u> <u>Drawing Number(s)</u> 231-203-0067-0783 PROJ-10000520 2023-2704 through 2023-2747

A pre-bid meeting scheduled ONLY for Prevailing Wage & Local Hiring and MBE/WBE requirements on Wednesday, October 15, 2025 at 10:00 a.m. EST via WebEx. Phone-In (Audio Only) – 1-415-655-0001, Meeting Number 2312 514 5226## Video Conference – Meeting Number 2312 514 5226, Password 8RUv8UyT8PH, go to <a href="https://signin.webex.com/join">https://signin.webex.com/join</a>,or for the WebEx link go to <a href="https://signin.webex.com/join">www.baltimorecountymd.gov/departments/public-works/engineering/contracts/current-solicitations</a>

Last day for questions will be Friday, October 17, 2025 at 4:00 p.m. EST. Questions should be emailed to Pawan Poudel at <a href="mailto:ppoudel@baltimorecountymd.gov">ppoudel@baltimorecountymd.gov</a> and Barbara Wentworth at <a href="mailto:bwentworth@baltimorecountymd.gov">bwentworth@baltimorecountymd.gov</a>.

NOTE: No successful bidder may withdraw their bid within NINETY (90) days after the opening thereof.

The Contractor hereby declares that it has carefully examined the solicitation, plans and specifications, form of contract, Special Provisions and Drawings (collectively the "Contract Documents"). The Contractor also hereby declares that it has carefully examined the September 2023 "Standard Specifications for Construction and Materials" and "Standard Details for Contraction", collectively the "Applicable County Law" and any and all Department of Public Works and Transportation revisions thereto as of the date of advertisement. The Contract Documents, the Applicable County Law and the Department of Public Works and Transportation revisions thereto are collectively the "Specifications" and are incorporated herein. Copies of any and all Department of Public Works and Transportation revisions including but not limited to the General Conditions Building Projects, are available online at <a href="https://www.baltimorecountymd.gov/departments/public-works/standards">www.baltimorecountymd.gov/departments/public-works/standards</a>. Also, the Contractor has, to its satisfaction, examined the locality of the proposed work and agrees to furnish all labor, tools, materials, machinery, equipment, and other means of construction called for in the manner provided in the Specifications for the prices shown on the next page(s) and as evidenced by Contractor's signature on the last page thereof.

#### SCHEDULE OF PRICES

NOTE: The Bidder shall fill out this Proposal, write in the unit prices in clear numerals, and make the extensions.

For complete information concerning these items, see Specifications and contract forms.

#### **CONTRACT PROPOSAL**

BACK RIVER NECK ROAD 16" AND 24" WATER MAIN REPLACEMENT - PHASE 3
CONTRACT NUMBER: 23186-WXO
WORKDAY NUMBER: 10000520
JOB ORDER NUMBER: 231-203-0067-0783
WORKING DAYS: 400

CONTRACTOR:	
ADDRESS:	
PHONE:	

BID ITEM	COMM.		DESCRIPTION	UNIT	ESTIMATED QUANTITY	UNIT PRICE	TOTAL AMOUNT
					Q0/11/11/1	0	
1	130850		MOBILIZATION	LS	1		\$
2	120500		MAINTENANCE OF TRAFFIC	LS	1		\$
3	WRITE-IN		INLET PROTECTION - CURB	EA	35		\$
4	704345		PLACING FURNISHED TOPSOIL 4 INCH DEPTH	SY	48		\$
5	707301		SEEDING	SY	48		\$
6	WRITE-IN		TEMPORARY MULCHING	SY	48		\$
7	130840		CONSTRUCTION STAKEOUT	LS	1		\$
8	800010	F	TEST PIT EXCAVATION IN COUNTY ROADS VIA TRADITIONAL METHOD	CY	300	\$360.00	\$108,000.00
9	110330		ENGINEER'S OFFICE NO.3	LS	1		\$
10	800050		MIX NO. 1 CONCRETE FOR MISCELLANEOUS STRUCTURES	CY	8		\$
11	833040		4 INCH DUCTILE IRON PIPE AND FITTINGS	LF	22		\$
12	863060		6 INCH DUCTILE IRON PIPE AND FITTINGS - CLASS 54	LF	321		\$
13	863080		8 INCH DUCTILE IRON PIPE AND FITTINGS - CLASS 54	LF	533		\$

14	863120	12 INCH DUCTILE IRON PIPE AND FITTINGS - CLASS 54	LF	169	\$
15	863160	16 INCH DUCTILE IRON PIPE AND FITTINGS - CLASS 54	LF	2,325	\$
16	863240	24 INCH DUCTILE IRON PIPE AND FITTINGS - CLASS 54	LF	2,913	\$
17	847060	6" FIRE HYDRANT / FURNISH AND INSTALL	EA	9	\$
18	836040	4 INCH VALVE AND VAULT - VERTICAL	EA	1	\$
19	836060	6 INCH VALVE AND VAULT - VERTICAL	EA	11	\$
20	836080	8 INCH VALVE AND VAULT - VERTICAL	EA	11	\$
21	836120	12 INCH VALVE AND VAULT - VERTICAL	EA	3	\$
22	836160	16 INCH VALVE AND VAULT - VERTICAL	EA	1	\$
23	836230	24 INCH VALVE AND VAULT - VERTICAL	EA	2	\$
24	842010	3/4 IN. WATER SERVICE TAP AND CORPORATION	EA	38	\$
25	843010	3/4 IN. COPPER WATER SERVICE AND FITTINGS	LF	1,036	\$
26	842020	1 IN. WATER SERVICE TAP AND CORPORATION	EA	5	\$
27	843020	1 IN. COPPER WATER SERVICE AND FITTINGS	LF	125	\$
28	842030	1-1/2 IN. WATER SERVICE TAP AND CORPORATION	EA	3	\$
29	843030	1-1/2 IN. COPPER WATER SERVICE AND FTTTINGS	LF	81	\$
	842040	2 IN. WATER SERVICE TAP AND CORPORATION	EA	4	\$
31	843040	2 IN. COPPER WATER SERVICE AND FITTINGS	LF	149	\$
32	849420	TEMPORARY BY-PASS LINES	LF	15,520	\$
	WRITE-IN C	REPLACEMENT OF WATER METER SETTING (ALL SIZES) (CONTINGENT	EA	8	\$

34	WDITE IN		REPLACEMENT OF WATER METER FRAME, COVER, AND VAULT (ALL SIZES) (CONTINGENT ITEM)	EA	8	\$
			ADDITIONAL M.J. FITTINGS FOR AVOIDING OBSTRUCTIONS OR EXISTING UTILITIES (VARIOUS SIZES 4"-24" AND VARIOUS BENDS 11.25°, 22.5°, AND 45°) (CONTINGENT ITEM)	LS	1	\$
36	120561		HOT MIX ASPHALT STAGE 1 FOR TEMPORARY TRENCH REPAIR @ 3" DEPTH	TON	850	\$
37	120562		HOT MIX ASPHALT STAGE 2 FOR PERMANENT TRENCH REPAIR	TON	2,500	\$
38	210011		REMOVE AND REPLACE EXISTING CURB AND GUTTER	LF	305	\$
39	210021		REMOVE AND REPLACE EXISTING CONCRETE SIDEWALK	SF	720	\$
40	WRITE-IN	С	DISPOSAL OF UNSUITABLE MATERIAL (FIXED PRICE CONTINGENT ITEM)	SY	8,000	\$
41	WRITE-IN	С	GEOTEXTILE CLASS ST (CONTINGENT ITEM)	SY	8,000	\$
42	800060	F	BORROW FOR BACKFILLING TRENCHES W/ PROPER OFFSITE DISPOSAL OF UNSUITABLE MATERIAL (FIXED PRICE CONTINGENT ITEM)	CY	9000	\$80.00 \$720,000.00
43	800020	F	CLASS 3 EXCAVATION W/ SELECT BACKFILL & PROPER OFFSITE DISPOSAL OF UNSUITABLE MATERIAL (FIXED PRICE CONTINGENT ITEM)	CY	300	\$130.00 \$39,000.00
44	WRITE-IN		TRENCH ROCK EXCAVATION WITH PROPER DISPOSAL (CONTINGENT ITEM)	CY	250	\$
45	530164		GAB FOR TRENCH REPAIR	TON	4,000	\$
46	585240		MILLING ASPHALT PAVING MINIMUM 2"	SY	27,319	\$
47	585210		5 INCH SOLID WHITE THERMOPLASTIC PAVEMENT MARKINGS	LF	3,290	\$
48	585286		5 INCH SOLID YELLOW THERMOPLASTIC PAVEMENT MARKINGS	LF	11,565	\$
49	585292		16 INCH SOLID WHITE THERMOPLASTIC PAVEMENT MARKINGS FOR CROSS HATCH	LF	775	\$
50	WRITE-IN	С	24 INCH SOLID WHITE THERMOPLASTIC PAVEMENT MARKINGS FOR STOP BARS	LF	235	\$
51	WRITE-IN		THERMOPLASTIC PAVEMENT MARKINGS AND LEGENDS AND SYMBOLS	SF	140	\$

52	WRITE-IN	PITCHER FILTER WITH S	IX MONTHS OF REPLACEMENT CARTRIDGES	EA	5		\$
TOTAL COST FOR CONTRACT \$					\$		
TOTAL COST FOR CONTRACT IN WORDS							•
		OFFICER SIGNATURE		_	TITI F		

#### PROPOSAL AFFIDAVIT

#### 1. AUTHORIZED REPRESENTATIVE

I HEREBY AFFIRM THAT:	
I am the [title] of [business] authority to make this Affidavit on behalf of myself a	and the duly authorized representative (the "Business") and that I possess the legand the Business for which I am acting.
2. PROPOSAL CERTIFICATION	
THE UNDERSIGNED HEREBY ACKNOWLEDGES (list by number and date):	receipt of the following Addenda

Accompanying this Proposal is a Bid Bond in an amount of 5% of the bid, the exact amount to be determined by the difference between the low bid and the next lowest bid, if two or more bids are received, or 5% of the bid if one bid is received. This guarantees payment to Baltimore County of the amount thus determined as liquidated damages in case of default in any matter specified as required before award or in any matter resulting in failure to execute and deliver an Agreement, together with Payment and Performance Bonds, after award.

#### 3. AFFIRMATION REGARDING BRIBERY CONVICTIONS

#### I FURTHER AFFIRM THAT:

Neither I, nor to the best of my knowledge, information, and belief, the Business, nor any of its officers, directors, partners, or any of its employees directly involved in obtaining or performing contracts with public bodies (as is defined in Section 16-101(f) of the State Finance and Procurement Article of the Annotated Code of Maryland), has been convicted of, or has had probation before judgment imposed pursuant to Section 6-225 of the Criminal Procedure Article of the Annotated Code of Maryland, or has pleaded nolo contendere to a charge of, bribery, attempted bribery, or conspiracy to bribe in violation of Maryland law, or of the law of any other state or federal law, except as follows [indicate the reasons why the affirmation cannot be given and list any conviction, plea, or imposition of probation before judgment with the date, court, official or administrative body, the sentence or disposition, the name(s) of person(s) involved, and their current positions and responsibilities with the Business]:

### 4. AFFIRMATION REGARDING OTHER CONVICTIONS

#### I FURTHER AFFIRM THAT:

Neither I, nor to the best of my knowledge, information, and belief, the Business, nor any of its officers, directors, partners, or any of its employees directly involved in obtaining or performing contracts with public bodies, has:

- (1) Been convicted under state or federal statute of a criminal offense incident to obtaining, attempting to obtain, or performing a public or private contract, fraud, embezzlement, theft, forgery, falsification or destruction of records, or receiving stolen property;
  - (2) Been convicted of any criminal violation of a state or federal antitrust statute;

- (3) Been convicted under the provisions of Title 18 of the United States Code for violation of the Racketeer Influenced and Corrupt Organization Act, 18 U.S.C. §1961, et seq., or the Mail Fraud Act, 18 U.S.C. §1341, et seq., for acts arising out of the submission of bids or proposals for a public or private contract;
- (4) Been convicted of a violation of the State Minority Business Enterprise Law, Section 14-308 of the State Finance and Procurement Article of the Annotated Code of Maryland;
- (5) Been convicted of conspiracy to commit any act or omission that would constitute grounds for conviction or liability under any law or statute described in subsection (1), (2), (3), or (4) above:
- (6) Been found civilly liable under a state or federal antitrust statute for acts or omissions in connection with the submission of bids or proposals for a public or private contract;
- (7) Admitted in writing or under oath, during the course of an official investigation or other proceedings, acts or omissions that would constitute grounds for conviction or liability under any law or statute described above, except as follows [indicate reasons why the affirmations cannot be given, and list any conviction, plea, or imposition of probation before judgment with the date, court, official or administrative body, the sentence or disposition, the name(s) of the person(s) involved and their current positions and responsibilities with the Business, and the status of any debarment]:

## 5. AFFIRMATION REGARDING DEBARMENT

#### I FURTHER AFFIRM THAT:

Neither I, nor to the best of my knowledge, information, and belief, the Business, nor any of its officers, directors, partners, or any of its employees directly involved in obtaining or performing contracts with public bodies, has ever been suspended or debarred (including being issued a limited denial of participation) by any public entity, except as follows [list each debarment or suspension providing the dates of the suspension or debarment, the name of the public entity and the status of the proceeding, the name(s) of the person(s) involved and their current positions and responsibilities with the Business, the grounds of the debarment or suspension, and the details of each person's involvement in any activity that formed the grounds of the debarment or suspension]:

#### 6. AFFIRMATION REGARDING DEBARMENT OF RELATED ENTITIES

#### I FURTHER AFFIRM THAT:

- (1) The Business was not established and it does not operate in a manner designed to evade the application of or defeat the purpose of debarment pursuant to Sections 16-101, et seq., of the State Finance and Procurement Article of the Annotated Code of Maryland; and
- (2) The Business is not a successor, assignee, subsidiary, or affiliate of a suspended or debarred business, except as follows: [you must indicate the reasons why the affirmations cannot be given without qualification]:

Rev. 09/2024 256

.

#### 7. SUB-CONTRACT AFFIRMATION

#### I FURTHER AFFIRM THAT:

Neither I, nor to the best of my knowledge, information, and belief, the Business, has knowingly entered into a contract with a public body under which a person debarred or suspended under Title 16 of the State Finance and Procurement Article of the Annotated Code of Maryland will provide, directly or indirectly, supplies, services, architectural services, construction related services, leases of real property, or construction.

#### 8. AFFIRMATION REGARDING COLLUSION

#### I FURTHER AFFIRM THAT:

Neither I, nor to the best of my knowledge, information, and belief, the Business, nor any of its officers, directors, members or partners, nor any of its employees, have in any way:

- (1) Agreed, conspired, connived, or colluded to produce a deceptive show of competition in the compilation of the accompanying bid or offer that is being submitted;
- (2) In any manner, directly or indirectly, entered into any agreement of any kind to fix the bid price or price proposal of the bidder or offeror or of any competitor, or otherwise take any action in restraint of free competitive bidding in connection with the contract for which the accompanying bid or offer is submitted:
- (3) Colluded with anyone to obtain information concerning the bid that would give the Business an unfair advantage over others.

#### 9. POLITICAL CONTRIBUTION DISCLOSURE AFFIRMATION

#### I FURTHER AFFIRM THAT:

The Business affirms that it is aware of, and will comply with, the provisions of Sections 14- 101 through 14-108 of the Election Law Article of the Annotated Code of Maryland, which require that every person who makes, during any 12-month period, one or more contracts, with one or more Maryland governmental entities involving cumulative consideration, or at least \$200,000.00, shall file with the State Board of Elections certain specified information to include disclosure of attributable political contributions in excess of \$500 during defined reporting periods.

#### 10. CERTIFICATION OF CORPORATION REGISTRATION AND TAX PAYMENT

#### I FURTHER AFFIRM THAT:

(1)	The Business is a	(State) (Corporation), (LLC),	(Partnership), (Sole
Proprietor/Indiv	vidual), (Other:	), that it <b>is</b> registered in a	ccordance with the
Corporations a	and Associations Article of the	Annotated Code of Maryland, that it <b>is</b>	in good standing in
•		all of its annual reports, together with	•
Maryland State	e Department of Assessment	s and Taxation, and that the name at of Assessments and Taxation is:	•
	а але стале дерагале.		
Name:			
ivallie.			-
Address:			<u>-</u>
			_
	(If none, so state)		

(2) Except as validly contested, the Business has paid, or has arranged for payment of, all taxes due the State of Maryland and Baltimore County, and has filed all required returns and reports with the Comptroller of the Treasury, the State Department of Assessments and Taxation, and the Employment Security Administration, as applicable, and will have paid all withholding taxes due the State of Maryland prior to final settlement.

#### 11. CONTINGENT FEES

#### I FURTHER AFFIRM THAT:

The Business has not employed or retained any person, partnership, corporation, or other entity, other than a bona fide employee or agent working for the Business, to solicit or secure the Contract, and that the Business has not paid or agreed to pay any person, partnership, corporation, or other entity, other than a bona fide employee or agent, any fee or other consideration contingent on the making of the Contract.

#### 12. NONDISCRIMINATION IN EMPLOYMENT STATEMENT

#### I FURTHER AFFIRM THAT:

During the performance of any contract awarded of which this affidavit is a part:

- (1) The Business will not discriminate against any employee or applicant for employment because of race, color, religion, sex, age, national origin, marital status, sexual orientation, genetic information, or disability unrelated in nature and extent so as to reasonably preclude the performance of the employment, or because of the individual's refusal to submit to a genetic test or make available the results of a genetic test. The Business will take affirmative action to ensure that applicants are employed, and that employees are treated during employment, without regard to their race, color, religion, sex, age, national origin, marital status, sexual orientation, genetic information, or disability unrelated in nature and extent so as to reasonably preclude the performance of the employment, or because of the individual's refusal to submit to a genetic test or make available the results of a genetic test. Such action shall include, but not be limited to the following: employment, promotion, upgrading, demotion or transfer, rates of pay or other forms of compensation; and selection for training, including apprenticeship. The Business agrees to post in conspicuous places, available to employees and applicants for employment, notices to be provided by the owner setting forth provisions of this nondiscrimination clause.
- (2) The Business will, in all solicitations or advertisements for employees placed by or on behalf of the Business, state that all qualified applicants will receive consideration for employment without regard to race, color, religion, sex, age, national origin, marital status, sexual orientation, genetic information, or disability unrelated in nature and extent so as to reasonably preclude the performance of the employment, or because of the individual's refusal to submit to a genetic test or make available the results of a genetic test.
- (3) The Business shall send to each labor union or representative of workers with which the Business has a collective bargaining agreement or other contract or understanding, a notice, to be provided by the owner, advising the said labor union or workers' representative of these commitments, and shall post copies of the notice in conspicuous places available to employees and applicants for employment.

- (4) The Business shall furnish, if requested by the County, a compliance report concerning our employment practices and policies in order for the County to ascertain compliance with the special provisions of this affidavit concerning nondiscrimination in employment.
- (5) In the event of the Business's noncompliance with the nondiscrimination clause of this affidavit, the contract may be canceled, terminated, or suspended in whole or in part, and the Business may be declared ineligible for further County work.
- (6) The Business shall include the special provisions outlined herein pertaining to nondiscrimination in employment in every subcontract, so that such nondiscrimination in employment provisions shall be binding on each subcontractor or vendor.

#### 13. FOREIGN CONTRACTS

#### I FURTHER AFFIRM THAT:

The Business affirms that it is aware of, and will comply with, the provisions of Sections 10-2-110 Article 10. Finance, Title 2 – Purchasing, Baltimore County Code 2003, which requires that prior to the award of a contract for services under the provisions of this title, and during the entire term of a contract award, the bidder or vendor shall disclose to the County whether any services covered by the bid or contract, including any subcontracted services, will be performed outside the United States. The disclosure shall be made to the Office of Budget and Finance, Purchasing Bureau.

#### 14. MINORITY BUSINESS ENTERPRISE AND FEMALE CONTRACTORS

THIS BUSINESS INTENDS to affirmatively seek out and consider minority business enterprises to participate in this contract as subcontractors and/or suppliers of materials and services.

THE UNDERSIGNED UNDERSTANDS AND AGREES: that any and all subcontracting of supplies and services in connection with this contract, whether undertaken before or after award of contract, will be in accordance with the Minority Business Enterprise and Female Contractor requirement included in the Bid Proposal package and incorporated herein as if fully set forth; and

THE UNDERSIGNED ALSO UNDERSTANDS AND AGREES that no subcontracting will be approved until Baltimore County has reviewed and approved the affirmative actions taken by this firm.

#### 15. REQUIREMENTS FOR EXECUTING AFFIDAVIT & PROPOSAL

The Affidavit must be signed in ink in order for the bid to be accepted and that the Proposal must be typewritten or filled out in ink.

THE UNDERSIGNED ALSO UNDERSTANDS that:

Proposals submitted by an INDIVIDUAL must be signed by an individual.

Proposals submitted by a PARTNERSHIP must be signed by the partner who is legally authorized authority to bind the partnership. Attach a copy of the Partnership Agreement and a duly certified resolution evidencing the authority of the partner so signing on behalf of the partnership.

Proposals submitted by a CORPORATION must be signed by a legally authorized officer of the corporation and attested to by the Corporate Secretary. Attach a copy of the Articles of Incorporation, By-Laws and a duly certified Board Resolution evidencing the authority of the officer so signing on behalf of the corporation.

Proposals submitted by a LIMITED LIABILITY COMPANY must be signed by a legally authorized member of the company and attested to. Attach a copy of the Operating Agreement, Articles of Organization and a duly certified resolution evidencing the authority of the member so signing on behalf of the limited liability company.

**NOTE**: The contractor may file with the County a list of the names of those officers, partners or members, as applicable, having legal authority to execute documents on behalf of and legally bind the contractor, duly certified, as applicable and legally required, together with the aforesaid corporate documents, which shall remain in full force and effect until such time as the County Department of Public Works and Transportation, Construction Contract Administration is advised in writing to the contrary.

#### 16. ACKNOWLEDGMENT

I ACKNOWLEDGE THAT this Affidavit is to be furnished to the County and may be distributed to units of (1) Baltimore County; (2) the State of Maryland; (3) other counties or political subdivisions of the State of Maryland; (4) other states; and (5) the federal government. I further acknowledge that this Affidavit is subject to applicable laws of the United States and the State of Maryland, both criminal and civil, and that nothing in this Affidavit or any contract resulting from the submission of this bid or proposal shall be construed to supersede, amend, modify or waive, on behalf of Baltimore County, or the State of Maryland or any unit of the State of Maryland having jurisdiction, the exercise of any statutory right or remedy conferred by the Constitution and the laws of Maryland with respect to any misrepresentation made or any violation of the obligations, terms and covenants undertaken by the Business with respect to (a) this Affidavit, (b) the contract, and (3) other Affidavits comprising part of the contract.

I DO SOLEMNLY DECLARE AND AFFIRM UNDER THE PENALTIES OF PERJURY THAT THE CONTENTS OF THIS AFFIDAVIT ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE, INFORMATION, AND BELIEF.

WITNESS/ATTEST:		
	By:	
	Name:	
Date:	Title:	
	(Authorized Representative and Affiant	(1)

В	ID BOND			
_	- DOND			
Principal	Business Add	ress of Principal		
Surety	Obligee:	BALTIMORE COUNTY A body corporate	,	
A Corporation of the State of a	nd authorized to do b	, ,	and pointe	
Five Percent of Bid Amount Penal Sum of Bond [shall be determined pursuant to latest revi	and Specification / C.D.	\$ 07 (2000 Ed.)	5% of Bid	
Back River Neck Road 16" and 24" Water Main Replaceme		2.07 (2000 Ed.)j		
Contract Name	<u></u>			
23186 WX0 Contract Number/Proposal Item Number				
KNOW ALL MEN BY THESE PRESENTS, that we, the Prir in the State of Maryland, are held and firmly bound unto the Obpayment of which sum well and truly to be made, we bind ourse severally, firmly by these presents.	ligee, above named, in	the penal sum of the ar	mount stated above, for	r the
THE CONDITION OF THIS OBLIGATION is such that if the matters required before award or if the aforesaid Principal is aw deliver to the Obligee a formal contract and good and sufficient obligation to be void; otherwise the Principal and Surety will, upliquidated damages.	arded the contract, the payment and performa	said Principal will, with nce bonds in the form p	in the time required, exc provided by the Obligee	ecute and then, this
THE SURETY FURTHER GUARANTEES No Proposal will Proposal in the form of either a certified check, bank cashier's of the Bid Bond must be executed by a Surety that is, as of the d A.M. Best Company, (c) on federal funded projects, authorized Circular 570, as amended, to guaranty the amount of the Bid, a must guaranty payment to the County of liquidated damages as (5%) percent of the Bidder's Bid amount, (b) if two or more Bids Bidder's Bid amount and the next lowest Bid amount, subject to of the Bidder's Bid amount. This Bid Bond is required in case the completely, with each of the requirements set forth under Section	check or a Bid Bond on ate of the Bid: (a) licens by the underwriting limind (d) in good standing follows: (a) if only one are received, the guar the limitation that the gues successful Bidder, af	the form provided there sed in the State of Mary itation contained in the as determined by the (Bid is received, the guanteed payment shall by guaranteed payment no	ein or an exact facsimile land, (b) rated "B" or be U.S. Department of the County's Engineer. The aranteed payment shall the the difference betwee t be greater than five (5	e thereof. etter by the Treasury Bid Bond be five en the 5%) percent
Signed and sealed Date				
<b>IN WITNESS WHEREOF</b> , the above-bounded parties have name and corporate seal of each corporate party being hereto to authority of its governing body.				
In Presence of:	Inc	lividual Principal		
Witness:	as to:			(SEAL)
Print Name:	Print Name:			
		armareta Dringinal		
In Presence of:		orporate Principal		
	,	ne of Corporation)		
Witness:				
Print Name:				
	Title:			
		Surety		
Business A		(Name of Surety)		
Witness:				Affix
Print Name:				Corporate
				-

Title: \_\_\_\_

# BALTIMORE COUNTY PREVAILING WAGE AND LOCAL HIRING

# AFFIDAVIT

(Project Name)
Proposal No.: Project No.:
On behalf of
1. I have submitted all documentation in accordance with Baltimore County Code § 10-2-500 and § 10-2-507 regarding the prevailing wage and local hiring laws and requirements of the prevailing wage guidelines located at ( <a href="Prevailing Wage and Local Hire Laws">Prevailing Wage and Local Hire Laws</a> ), and acknowledge that I have read and agree to all provisions of said law, as amended, and have a continuing obligation to be compliant with the law and any changes to the law.
I_shall not knowingly provide any false information relating to payroll documentation and/or hiring of local employees for capital improvement contracts that are subject to the prevailing wage and/or local hiring laws of Baltimore County. I further attest and certify that all documentation relating to the same will be accurate and complete and will remain accurate and complete on an ongoing basis, and will reflect the payroll and/or local hiring status of contractors subcontractors, apprentices, and independent contractors performing work for the Contract (contract n u m be r). I acknowledge that I have been informed and am aware of the foregoing requirements and that I am authorized to make this certification on behalf of myself and all subcontractors and parties performing work pursuant to this Contract.
3. I certify and attest that I am an officer or agent of the Contractor or subcontractor who supervises the payment of employees. I understand and agree that all documentation related to prevailing wages and/or local hiring required by law shall be submitted to Baltimore County' Prevailing Wage Administrator or designee before any surety is released or final payment durunder the terms of the Contract is made.
4. I further certify and attest that I will have personal knowledge of the wages paid to all employees of for work performed on the Contract and of all of the hour worked, and that I am an authorized agent of the Contractor and assume responsibility for mactions.
5. I further certify and attest that will comply with prevailing wage rates set by the State of Maryland as the same apply to the Contract and are a part of the bid documents and Contract, and that will comply with applicable local hiring requirements.

I attest and certify that, if the Contract is subject to the local hiring requirement under §10-6. 2-507 of the Baltimore County Code, will make best efforts to ensure that residents of Baltimore County constitute at least 51% of the new hires made for the Contract, subject to all exceptions allowable by law. 7. I certify and attest that, if the Contract is subject to prevailing wage requirements, no rebates or deductions will be made, directly or indirectly, from any wages paid in connection with the Contract, other than those provided for by law. 8. I certify and attest that, if awarded the Contract and if the Contract is subject to prevailing wage law, I will submit certified payroll to the County through its electronic compliance system or as instructed by the Prevailing Wage and Local Hire Unit. I certify that if awarded the Contract, I will provide a list of subcontractors who will participate as a beneficiary of this project to the agency and the Prevailing Wage and Local Hire Unit at Prevailing Wage @baltimorecountymd.gov. 10. I understand that no funds will be dispersed by the County until an Employment Analysis has been issued to the Prevailing Wage and Local Hire Unit in compliance with the local hire law. The Employment Analysis will include how many jobs will be required to complete the project; how many current employees are available to complete the project, and how many of those jobs will require new hires. Contractor/Bidder/Offeror By Printed Name **Printed Title** Date Phone License Number **Business Email** 

#### **BALTIMORE COUNTY, MARYLAND**

### **Prevailing Wage and Local Hiring Contract Requirements and Policies**

The Contractor and all Subcontractors must comply with the Prevailing Wage and Local Hiring Laws, contained in Baltimore County Code § 10-2-506 and § 10-2-507, respectively, as amended. Prevailing wage means the wage rate paid by employers that is determined by a governmental authority, based upon a particular geographic area, for a given class of labor and type of project. The County will use the prevailing wage established by the State of Maryland (the "State") Department of Labor for state funded construction contracts in the County at the time of award. These rates include the basic hourly rate and fringe benefits. Apprentices must be paid at least the rate that the State's Apprenticeship and Training Council sets for an apprentice in the trade involved, based on a percentage of the prevailing wage rate in that trade. Any Contractor that is subject to the prevailing wage or local hiring law will be required to agree to the below provisions:

For the purposes of these requirements, an employee means an apprentice, laborer or mechanic employed by a contractor or subcontractor on a capital improvement project with a value of over \$300,000 or a County-subsidized capital project with a value over \$5,000,000.

Capital Improvement Project does not include blanket order or open-end agreements, capital improvement projects subject to a federal or state prevailing wage law, awarded without competition; with another governmental entity; to the extent the contractor is precluded from compliance by the terms of any federal or state law, contract or grant; entered into pursuant to Baltimore County Code § 10-2-310(e); entered into as a joint or cooperative purchase; or entered into as an emergency purchase.

The purpose of a prevailing wage is to ensure that contractors institute local hiring practices for Capital Improvement contracts and Capital Projects under certain circumstances as required by law, and that the Contractor's employees who work on capital improvement contracts are paid the going rate for their services. The prevailing wage rates are established by the State of Maryland Department of Labor and apply to all of the Contractor's employees and any and all Subcontractors. The Contractor and all Subcontractors must comply with all of the requirements of the Prevailing Wage Law including, but not limited to, the following:

1. Pay employees the prescribed rate as annually established by the State's Department of Labor; the prevailing wage rates in effect on the date a solicitation is issued and will apply throughout the term of a contract resulting from that solicitation. Contractor or subcontractors may NOT split or subdivide a capital improvement contract, pay an employee through a third party, treat an employee as a subcontractor or independent contractor to avoid any requirement of the County's prevailing wage law; or employ an individual classified as a helper or trainee to perform direct and measurable work on a capital improvement contract.

- 2. Pay employees at a rate equal to or more than the prevailing wage rate currently in effect for the type of workperformed.
- 3. Pay employees overtime for work (I) more than eight hours in any single calendar day; (II) more than 40 hours in a work week; or (III) on a Sunday or a legal holiday.
- 4. Classify employees in their proper work classification in conformance with the schedule established by the State's Department of Labor.
- 5. May only make fair and reasonable deductions that are (a) required by law; (b) authorized in a written agreement between an employee and contractor or subcontractor signed at the beginning of employment (any deductions taken from employee paychecks including healthcare, pension, 401K, IRA, etc., child/spouse support, or tax levies); and submitted by the contractor or subcontractor to the Director of the County's Prevailing Wage Program; or required or allowed by a collective bargaining agreement between a bona fide labor organization and a contractor or subcontractor.

Electronically submit a certified copy of payroll records through the <u>County's designated certified payroll and compliance system</u> within 14 days after the end of payroll week ending date, to verify that Prevailing Wage rates have been paid to employees.

- 6. Backup documentation may be required upon demand from the County to be submitted for all 3<sup>rd</sup> party benefits being claimed, to include, but not limited to: *one month's healthcare transmittal showing employee name and amount company pays on their behalf, company vacation/sick policy, etc. or if Union, a Union transmittal for one month in which work has been performed.*
- 7. Retain records for a period of five (5) years after the work is completed and permit the Director of the County Prevailing Wage Program, or his/her designee, to inspect the payroll records at a reasonable time and as often as necessary.
- 8. Payroll records shall contain a statement signed by the contractor or subcontractor (including tiered subcontractors) certifying that the payroll records are complete and correct; the wage rates are not less than required by the Prevailing Wage Law; and the rate of pay and classification for each employee accurately reflects the work the employee performed.
- 9. All payroll records shall include the name, address, telephone number and email address of the contractor or subcontractor; the name and location of the job; and each employee's name, current address, unless previously reported; specific work classification; daily basic time and overtime hours; total basic time and overtime hours for the payroll period; rate of pay; fringe benefits by type and amount; and gross wages, and any deductions taken from employees' paychecks including, but not limited to, healthcare, pension/401K/IRA. Late submission of copies of any payroll records may be deemed deficient by the County until the required records are provided, and the County may postpone processing payments due under the Contract or under an agreement to finance the Contract.

- 10. Submit to random or regular audits and investigation of any complaint of a violation of the County's Prevailing Wage and Local Hiring Laws and requirements.
- 11. Make best efforts to fill at least 51% of new jobs required to complete the capital improvement contract or capital project with Baltimore County residents.
- 12. Submit monthly reports to the Director of the County's Prevailing Wage Unit relating to local hiring with respect to capital improvement contracts over \$300,00 or County-subsidized capital construction projects receiving assistance over \$5,000,000, that includes (a) the number of new hires needed for the contract or project, (b) the number of County residents hired during the reporting period, (c) the total number of all employees hired during the contract period, (d) best efforts made to fill open positions with County residents, and(e) 5) for new hires: name, last four (4) digits of the social security number, job title, hire date, address and referral source.
- 13. Agree that any and all disputes will be handled as set forth in the County's Prevailing Wage and Local Hire as a condition of award.
- 14. In the event the County determines that a provision of the Prevailing Wage and/or Local Hire Law has been violated, the County shall issue a written decision, including appropriate sanctions, and may withhold payment due the Contractor in an amount sufficient to pay each employee of the Contractor or any subcontractors the full amount of wages due under the Prevailing Wage Law, and an amount sufficient to satisfy a liability of the Contractor for liquidated damages as provided under the Prevailing Wage Law, pending a final decision on the violation by the County. The Contractor may appeal a written decision of the Director of the County's Prevailing Wage Unit that the Contractor violated a provision of the Prevailing Wage and/or Local Hire Law, to the Office of Administrative Hearings ("OAH"), within ten (10) working days after receiving a copyof the decision. OAH will conduct a hearing upon the receipt of a timely appeal. If no appeal, the decision of the Director of the County's Prevailing Wage Unit or his/her designee becomes final. A Contractor who is found to have violated the provisions of the Prevailing Wage or Local Hiring Laws intentionally, may not be awarded a County contract or work on any County project for a period of one year from the date of the OAH determination.
- 15. May not discharge, or otherwise retaliate against, an employee for asserting any right under the Prevailing Wage Law or for filing a complaint of a violation;
- 16. An aggrieved employee is a third-party beneficiary of the Contract and may by civil action recover the difference between the prevailing wage for the type of work performed and the amount actually received, with interest and a reasonable attorney's fee.
- 17. Each Contract subject to the Prevailing Wage and Local Hire Laws may specify the payment of liquidated damages to the County by the Contractor for any noncompliance with the Prevailing Wage and Local Law. Liquidated damages are:
  - a. \$10 for each calendar day that the payroll records are late (payrolls are to be submitted no later than 14 days after the week ending date shown on Certified Payroll Record CPR);
     \$20 for each day that an employee is misclassified and/or paid less than the prevailing

- wage rate; and a civil penalty of \$50 per violation of the requirement to post the prevailing wage rates at the work site.
- b. \$50 per month for each month the Local Hire report is not submitted by the last day of the existing month due.

These liquidated damages are solely related to prevailing wage and local hiring compliance and do not negate any other remedies available or set forth in the Contract, including delay damages or actual damages. These remedies are separate from, in addition to, and not in lieu of, any remedies available and set forth in the Contract, or at law, for other breaches or defaults under the Contract.

- 18. Where the initial Contract Sum is \$300,000 or below, but it is subsequently increased and exceeds \$300,000 due to an approved Contract Modification, the amount of any such Contract Modification that causes the Contract Sum to exceed \$300,000 is subject to the Prevailing Wage and Local Hiring Laws.
- 19. The Contractor and all subcontractors must post a clearly legible statement of each prevailing wage rate in a prominent and easily accessible place at the Work Site during the entire time Work is being performed, in English and any other language that is primarily spoken by the employees, at the Work Site.
- 20. A contract may include the actual cost of health and dental insurance, pension or retirement plan, paid time off such as vacation or sick days and life insurance. In calculating the cost per hour, divide the annual cost of benefits by 2,080 hours for each employee. Other benefits such as the use of a company vehicle, cell phones, lodging reimbursement, company owned tools may not be credited towards the fringe benefit amount.
- 21. All apprentices must be registered with the Maryland Apprenticeship and Training Council, V.A., or US DOL as well as be currently enrolled in, and attending appropriate classes, to which is considered "actively enrolled". Only actively enrolled apprentices may be employed on the project at the apprentice prevailing wage rate.

# BALTIMORE COUNTY PREVAILING WAGE RATES HIGHWAY CONSTRUCTION

Classification	Modification Reason	Basic Hourly Rate	Borrowed From	Fringe Benefit Payment
BRICKLAYER	CR	\$37.50	510	\$14.78
CARPENTER	CR	\$34.41		\$14.49
CARPENTER - SHORING SCAFFOLD BUILDER	CR	\$34.41		\$14.49
ELECTRICIAN	CR	\$47.00		\$20.17
IRONWORKER - REINFORCING	CR	\$30.70		\$23.91
IRONWORKER - STRUCTURAL	CR	\$36.50		\$21.86
LABORER - AIR TOOL OPERATOR	AD	\$26.12		\$7.40
LABORER - ASPHALT PAVER	AD	\$26.12		\$7.40
LABORER - ASPHALT RAKER	CR	\$18.80		\$3.23
LABORER - BLASTER - DYNAMITE	AD	\$26.12		\$7.40
LABORER - BURNER	AD	\$26.12		\$7.40
LABORER - COMMON	CR	\$18.80		\$3.23
LABORER - CONCRETE PUDDLER	CR	\$18.80		\$3.23
LABORER - CONCRETE SURFACER	AD	\$26.12		\$7.40
LABORER - CONCRETE TENDER	CR	\$18.80		\$3.23
LABORER - CONCRETE VIBRATOR	CR	\$18.80		\$3.23
LABORER - DENSITY GAUGE	CR	\$18.80		\$3.23
LABORER - FIREPROOFER - MIXER	CR	\$18.80		\$3.23
LABORER - FLAGGER	CR	\$18.80		\$3.23
LABORER - GRADE CHECKER	CR	\$18.80		\$3.23
LABORER - HAND ROLLER	CR	\$18.80		\$3.23
LABORER - HAZARDOUS MATERIAL HANDLER	AD	\$26.12		\$7.40
LABORER - JACKHAMMER	CR	\$18.80		\$3.23
LABORER - LANDSCAPING	CR	\$18.80		\$3.23
LABORER - LAYOUT	CR	\$18.80		\$3.23
LABORER - LUTEMAN	CR	\$18.80		\$3.23
LABORER - MASON TENDER	AD	\$26.12		\$7.40
LABORER - MORTAR MIXER	CR	\$18.80		\$3.23
LABORER - PIPELAYER	AD	\$26.12		\$7.40
LABORER - PLASTERER - HANDLER	CR	\$18.80		\$3.23
LABORER - SCAFFOLD BUILDER	AD	\$26.12		\$7.40
LABORER - TAMPER	CR	\$18.80		\$3.23
MILLWRIGHT	CR	\$38.61	025	\$17.21
PAINTER - BRIDGE	CR	\$44.18		\$16.08
POWER EQUIPMENT OPERATOR - BACKHOE	CR	\$33.00		\$13.55
POWER EQUIPMENT OPERATOR - BOOM TRUCK	CR	\$30.04	510	\$13.55
POWER EQUIPMENT OPERATOR - BROOM / SWEEPER	CR	\$30.04		\$13.55
POWER EQUIPMENT OPERATOR - BULLDOZER	CR	\$33.00		\$13.55
POWER EQUIPMENT OPERATOR - CONCRETE PUMP	CR	\$33.00		\$13.55
POWER EQUIPMENT OPERATOR - CRANE	CR	\$41.00		\$18.10
POWER EQUIPMENT OPERATOR - DRILL - RIG	CR	\$33.00		\$13.55
POWER EQUIPMENT OPERATOR - EXCAVATOR	CR	\$33.00		\$13.55
POWER EQUIPMENT OPERATOR - FORKLIFT	CR	\$30.04		\$13.55

CONTRACT NUMBER: 23186 WX0

# BALTIMORE COUNTY PREVAILING WAGE RATES HIGHWAY CONSTRUCTION

10/3/2025

POWER EQUIPMENT OPERATOR - GRADALL	CR	\$34.00		\$13.55
POWER EQUIPMENT OPERATOR - GRADER	CR	\$34.00		\$13.55
POWER EQUIPMENT OPERATOR - LOADER	CR	\$33.00		\$13.55
POWER EQUIPMENT OPERATOR - MECHANIC	CR	\$34.00		\$13.55
POWER EQUIPMENT OPERATOR - MILLING MACHINE	CR	\$32.10		\$13.55
POWER EQUIPMENT OPERATOR - PAVER	CR	\$33.15		\$13.55
POWER EQUIPMENT OPERATOR - ROLLER - ASPHALT	CR	\$32.10		\$13.55
POWER EQUIPMENT OPERATOR - ROLLER - EARTH	CR	\$30.04		\$13.55
POWER EQUIPMENT OPERATOR - SKID STEER (BOBCAT)	CR	\$30.04		\$13.55
POWER EQUIPMENT OPERATOR-VACUUM TRUCK	CR	\$37.50		\$14.85
STONE MASON	CR	\$44.30	510	\$21.22
TILE & TERRAZZO FINISHER	CR	\$28.09	510	\$12.59
TRUCK DRIVER - DUMP	CR	\$23.83		\$9.22
TRUCK DRIVER - LOWBOY	CR	\$29.68		\$10.51
TRUCK DRIVER - TACK/TAR TRUCK	CR	\$29.39		\$10.51
TRUCK DRIVER - WATER	CR	\$29.39	027	\$10.51

# BALTIMORE COUNTY, MARYLAND

## USE OF MINORITY BUSINESS ENTERPRISES AND WOMEN'S BUSINESS ENTERPRISES

IN COUNTY CONTRACTS

MWBE Plan Package



Division of Diversity, Equity and Inclusion
The Jefferson Building
105 West Chesapeake Avenue
Towson, Maryland 21204
410-887-3407

www.baltimorecountymd.gov/go/mwbe



# PROSPECTIVE BIDDERS/OFFERORS

Baltimore County Executive Order 2022-005 Use of Minority Business Enterprises and Women's Business Enterprises states:

#### SECTION 6. BID REQUIREMENTS.

(A)(l) All bidders shall submit a list of all subcontractors contacted in preparation of their bid package or proposal.
(2) The list shall include the service to be performed, bid amount, and the race/ethnicity/gender of the business owner(s).
(B)(l) All bidders shall submit a list of all subcontractors to be used on a county contract in the bid package.

(2) This list shall include all subcontractors (both MWBE and non-MWBE) used, the service to be performed, the total amount to be paid, and the race/ethnicity/gender of the owner.

If the solicitation includes a MWBE subcontracting goal, you MUST demonstrate "Good Faith" effort either by:

- 1. Complete and sign FORM A, FORM B (to include FORM B-Prime if MWBE Prime wishes to count towards the goal) and FORM C **listing all subcontractors** with the initial bid submission.
  - a. All Forms must be completed and signed. However, FORM C **MUST** be completed and signed by both the prime and the MWBE subcontractor.

#### OF

- 2. If you are unable to meet any portion of the goal, you MUST do one of the following:
  - a. If you are requesting a **partial waiver**, complete and sign FORM A with initial bid submission. FORM B (to include FORM B-Prime if MWBE Prime wishes to count towards the goal) and FORM C (**listing all subcontractors**). In addition, complete, sign and submit FORM D and FORM E **accompanied with all supporting documentation** for the portion of the goal that will not be achieved as specified on FORM A.
  - b. If you are requesting a **full waiver**, complete and sign FORM A indicating your intent to request a full waiver **accompanied with a completed and signed FORM** C **listing all subcontractors**, FORM D and FORM E **accompanied with all supporting documentation**. This MUST be submitted with the initial bid as **specified on FORM A**.
  - c. All Forms must be completed and signed. FORM C and FORM D MUST be completed and properly signed by both the Prime AND the MWBE subcontractor(s).

NOTE: The MWBE subcontracting goal applies to ALL prime/general contractors including certified and non-certified minority and women owned firms. However, a Minority-owned or a Women-owned prime may self-perform up to 50% of MWBE subcontracting goal set in the solicitation. The MWBE primes that wish to count towards the goal must list themselves on all appropriate forms.

12/2023

# BALTIMORE COUNTY, MARYLAND MWBE PARTICIPATION SUMMARY

<u>Executive Order</u>: Minority Business Enterprises and Women Business Enterprises (MWBE) shall have the maximum opportunity to participate in the performance of contracts financed in whole, or in certain circumstances, in part with County funds. Accordingly, on December 6, 2022, the County Executive adopted the EXECUTIVE ORDER No. 2022-005 addressing MWBE participation in County contracts. The December 6, 2022 Executive Order may be found on the Baltimore County website at <a href="https://www.baltimorecountymd.gov/go/mwbe">www.baltimorecountymd.gov/go/mwbe</a>.

Each Contract: The County shall establish a minimum MWBE participation amount for each contract, as applicable.

<u>Bidder/Offeror Responsibility</u>: The bidder/offeror shall ensure that MWBE participation occurs in accordance with the contract requirements and the County Executive's Executive Order. All bidder/offerors shall ensure that MWBE have the maximum opportunity to compete for and perform County contracts, as applicable. Baltimore County, Maryland, and/or its bidder/offerors and contractors shall not discriminate on the basis of race, color, national origin, disability or sex in the award and performance of any County contract.

Mobilization Payments: For subcontractors, project start-up costs can also be significant. A subcontractor that has limited resources and access to credit may find that start-up expenses inhibit its ability to bid County contracts. Under circumstances where mobilization payments are approved for the prime contractor, the subcontractor should be paid an amount equal to their participation percentage no later than five (5) business days before they are required to mobilize to perform the contracted work.

Mobilization costs represent pre-contract costs incurred by a contractor to prepare a job site before the actual commencement of the contract. These costs can include movement of personnel and equipment to the project site and for the establishment of the Contractor's offices, buildings, and other facilities necessary to begin work.

#### **APPROVED MWBE LISTINGS**

Published compilations of approved and certified MWBE, contractors, subcontractors, material suppliers, etc. include:

DIRECTORY OF MINORITY BUSINESS ENTERPRISE (MDOT):

#### https://marylandmdbe.mdbecert.com

MINORITY BUSINESS DIRECTORY OF THE CITY OF BALTIMORE:

https://baltimorecity.diversitycompliance.com

#### **BIDDER/OFFEROR'S ACTIONS**

#### Seeking Firms:

The bidder/offeror will seek commitments by subcontract or otherwise from MWBE firms for supplies and/or services, any combined value of which equals or exceeds the required percentage of MWBE participation goal for the County contract. However a MWBE Prime that affirms its MWBE status on the Minority and/or Women Prime Participation Affidavit may count up to 50% of the goal.

#### **Expenditures for Materials and Supplies:**

A bidder/offeror may count toward its MWBE contract requirements all expenditures for materials and supplies obtained from MWBE suppliers and manufacturers, provided that the MWBE firm is furnishing and installing the materials and is certified to perform these services. If the MWBE firm is only being used as a supplier, wholesaler and/or regular dealer or is not certified to install the supplies/materials, for purposes of achieving the MWBE participation goal, you may only count sixty percent (60%) of the value of the subcontract for these supplies/products (60% Rule). To apply the 60% Rule, first divide the amount of the subcontract for these supplies/products only (not installation) by the total Contract value. Then, multiply the result by sixty percent (60%) and insert the percentage in the Percent of Total Contract field of Form B Subcontractor Participation Schedule.

# MWBE PARTICIPATION SUMMARY

<u>Information to be supplied</u>: All bidder/offerors shall submit the following information to the County at the time of bid submission:

- 1. The name of an employee designated as the bidder/offeror's liaison to the County's Minority Business Enterprise Office.
- 2. The following forms shall be completed and submitted:
  - Certified MWBE Utilization and Fair Solicitation Affidavit (<u>Form A):</u> from among those names appearing in the Approved MWBE Listings (excepting Federal Highway Administration projects, which exclusively require DBE approved and certified by the Maryland Department of Transportation MBE Advisory Committee);
  - A Subcontractor Participation Schedule (<u>Form B</u>) completed by the prime contractor for each MWBE listed on the Form
  - A MWBE Prime Participation Schedule (Form B-Prime) completed by a MWBE prime contractor if the firm wishes to self-perform up to 50% of the MBE/WBE goal.
  - A MWBE Disclosure and Participation Statement (**Form C**) completed and signed by the prime contractor and MWBE firm for each MWBE listed on the Form. Form C **must match** what is stated on Form B.
  - If applicable, MWBE Subcontractor Unavailable Certificate (**Form D**) completed and signed by the prime contractor and MWBE for each MWBE listed on the Form.
- 3. If applicable, MWBE Outreach Efforts Compliance Statement (**Form E**) completed and signed by the Bidder/Offeror. The prime shall submit a list of all subcontractors.
- 4. For DPW contracts, if the bidder/offeror intends to fulfill the MWBE requirements by use of a joint venture, he/she must submit a Joint Venture Disclosure Affidavit (**Form D-EEO-006-A** and **B** showing the extent of MWBE participation. If a bidder/offeror intends to use a MWBE joint venture as a subcontractor to meet its MWBE requirements, the affidavit must be submitted through the bidder/offeror by the proposed subcontractors and signed by all parties.
- 5. If the bidder/offeror's proposed MWBE participation does not meet the MWBE contract requirements, information sufficient to demonstrate that the bidder/offeror has made every effort to meet the requirements must be submitted. (See DETERMINATION OF BID RESPONSIVENESS hereafter)

#### **RECORDS AND REPORTS**

<u>Returning Records</u>: The bidder/offeror must keep such records as are necessary to determine compliance with its MWBE utilization requirements:

- 1. The MWBE and non-minority contractors, type of work being performed, actual values of work and services.
- 2. Documentation of all correspondence, contacts, telephone calls, etc., to obtain MWBE services for the contract.
- 3. All prime contractors and MWBE sub-contractors are required to report monthly, by the 10th of each month, to the County through an online system called PRISM. If the contractor cannot submit his/her report on time, he/she will notify the County MWBE office and request additional time to submit the report. Failure of the contractor to report in a timely manner may result in a finding of noncompliance. The County in its sole discretion and/or upon written request may require additional reports regarding MWBE. In the event you are not able to enter your payments in PRiSM, a spreadsheet is attached for your use. Please be sure to list the PO for each invoice/payment reported and include in your submission any corresponding documentation (e.g. copies of invoices or cancelled checks).

<u>Retaining Records</u>: All MWBE records must be retained for <u>3 years</u> following the expiration or any earlier termination of the contract and shall be available for inspection and photocopying by the County.

Investigation and Notification: Whenever the County believes the bidder/offeror, contractor, or any subcontractor may not be operating in compliance with the MWBE requirements, the County may, in its sole discretion, conduct an investigation. If the County finds the bidder/offeror, contractor, or any subcontractor is not in compliance with the MWBE requirements, the County may exercise any and all rights and remedies available to the County, under the contract, at law or equity, as deemed applicable and appropriate by the County in its sole discretion.

MWBE Plan Packet Page 4

# BALTIMORE COUNTY, MARYLAND MWBE PARTICIPATION SUMMARY

#### **DETERMINATION OF BID RESPONSIVENESS**

Request for Deviation: If the bidder/offeror is unable to procure from MWBE firms (by subcontract or otherwise), supplies and services, any combined value of which equals the required percentage of the total value of the contract, the bidder/ offeror may request, in writing, a deviation or waiver of the contract requirements. To obtain such a waiver, the bidder/ offeror must submit the following information at the time bids are due:

- 1. The request for waiver request shall include (1) a signed unavailability statement (Form D) executed by all MBEs and WBEs that the bidder/offeror solicited for participation and (2) Outreach Efforts/Compliance Statement (Form E) that demonstrates the bidder/offeror's good faith efforts to comply with the contract requirements, including copies of solicitation documentation to all potential subcontractors:
- 2. Emails, letters, facsimile transmittals and confirmations containing plans, specifications, and anticipated time schedule for portions of the work to be performed and meeting notes and agendas clearly identifying the certified MBE or WBE classification and dates that the bidder/offeror contacted each MWBE; and
- 3. Telephone logs containing names, addresses, dates, telephone numbers, work to be performed, anticipated time schedule and classification of certified MBEs and WBEs contacted.

<u>Bid Rejection</u>: The failure of any bidder/offeror (including the apparent low bidder/offeror) to provide a responsive MWBE Plan as required by the solicitation may result in the bidder/offeror being deemed non-responsive and the County's rejection of the bid.

<u>Liquidated Damages</u> If the County issues a notice of intent to awards contract to the apparent low bidder/offeror who provided a responsive MWBE Plan, but, if after said notice and before execution of Contract Documents, it is determined by the County that the apparent low bidder/offeror has failed to comply with the MWBE Plan, such failure may result in the recommendation by the appropriate Procurement Official to annul the award and forfeit the bidder/offeror's Proposal Guaranty to the County, not as a penalty, but as liquidated damages, it being acknowledged that actual damages will be difficult if not impossible to accurately measure. In addition, the County may proceed as it determines to be in its best interest, including but not limited to, the Notice of Award may be made to the next lowest responsive and responsible bidder/offeror or the work may be re-advertised.

<u>Contract Breach</u>: If, after execution of a County contract, the contractor becomes aware it may or will fail to fulfill the applicable MWBE requirements and/or may or will deviate from the contractor's bid response/contract terms, the contractor shall promptly advise the County of this in writing. Thereafter, the County will determine what action or remedy is appropriate on a case-by-case basis, in the County's sole discretion.

<u>Approval Required for Changes</u>: Any and all changes to the MWBE subcontractors or the type or amount of work to be performed by such subcontractors during the contract term must be mutually agreeable to the County and the contractor and shall be documented via a contract amendment, executed by legally authorized representatives of the County and the contractor.

<u>Cooperation in Reviews</u>: The bidder/offeror will cooperate with the County in any reviews of the contractor's procedures and practices with respect to MBE or WBE firms, which the County may from time to time conduct in its sole discretion.

Other: If the documents used to determine the contractor's efforts, achievement of, and/or the status of an MWBE requirement or fulfillment thereof contain false, misleading or misrepresented information, the contractor may be declared in breach of the contract and the County may take any and all actions and/or remedies available to the County under the contract, at law, or in equity. If an MWBE is disqualified by any public entity, including but not limited to, Baltimore City, the State or MDOT, at any time after award or during the term of the contract, the County may, in its sole discretion, require the prime contractor to promptly submit for County approval, the contractor's plans for fulfilling the required MWBE participation under the contract, and/or request such detail and additional information as the County, in its discretion deems appropriate.



## PRIME CONTRACTOR MINORITY AND WOMEN PARTICIPATION AFFIDAVIT

## A. AUTHORIZED REPRESENTATIVE

ΙHΙ	EREBY A	AFFIRM THAT:	
	I am the		and the duly authorized representative of
Affi	idavit on		(the "Business") and that I possess the legal authority to make this usiness for which I am acting.
B.	AFFIR	RMATION REGARDING	MINORITY AND WOMEN PARTICIPATION
I FU	JRTHER	AFFIRM THAT:	
wor		ware that, pursuant to the I the meanings indicated.	ecember 6, 2022 Executive Order of Baltimore County, Maryland, the following
who	one or mo	ore minority group members least 51% ownership and	e" or "MBE" means a business enterprise that is owned, operated and controlled is (African American, Hispanic American, Asian American, or Native American) in which the minority group members have operational and managerial control, surate with their percentage of ownership.
•	one or mo rest in ca	ore women who have at lea	se" or "WBE" means a business enterprise that is owned, operated and controlled 51% ownership and in which the women have operational and managerial control, surate with their percentage of ownership.
		Maryland State Departm	nt of Transportation (MDOT)#
		City of Baltimore #	
		Name Other Jurisdiction	<u>#</u>
		The ownership of the Not total of %), each of commensurate with their	certified MWBE business consists of% minorities and% women (for a which has operational and managerial control, interest in capital and earnings percent ownership.
			nerican % Hispanic American % Women
_	MW	MWBE prime anticipates n	rican% Native American% Disadvantaged (DBE) setting up to 50% of the stated participation goal with its own workforce.  set be stated on the MWBE PRIME PARTICIPATION SCHEDULE (FORM B- bod.
_			anticipate utilizing subcontractors for % of the work of the contract bates % will be MBEs and % will be WBEs.
OF			FFIRM UNDER THE PENALTIES OF PERJURY THAT THE CONTENTS D CORRECT TO THE BEST OF MY KNOWLEDGE, INFORMATION, AND
			By:(Authorized Representative and Affiant's Name and Title)
PB04	40		(Authorized Representative and Affiant's Name and Title)  Revised 12/2024

## **BALTIMORE COUNTY, MARYLAND** Certified MWBE Utilization and Fair Solicitation Affidavit (FORM A)

\*This document must be completed and submitted with Bid/Proposal to Baltimore County.

NOTE: If you do not complete and submit this form with your bid or offer to the County, the County may, in its sole discretion, deem your bid or offer NON-RESPONSIVE and accordingly the COUNTY WILL NOT CONSIDER YOU FOR CONTRACT AWARD. I acknowledge the goal for solicitation #23186 WX0 is a minimum of 25%. This goal must be met by any combination of the MWBE subcontractors. However, for instances where the Prime is counting up to 50% of the goal, the remaining goal balance must be met by any combination of the MWBE subcontractors. The goal breakdown is as follows: % Minority/Women Prime % for certified MBE-owned businesses and/or % for certified WBE-owned businesses. I have made a good-faith effort to achieve this MWBE solicitation requirement. If awarded the contract, I will comply with this MWBE contract requirement and will continue to use my best efforts to increase MWBE participation during the contract term. PLEASE CHECK ONE BOX (EITHER 1, 2, OR 3) Prime has met the MWBE contract requirements for this solicitation and contract. I submit the 1 Subcontractor Participation Form B and Form C, along with this Affidavit, which details how the Prime will achieve the contract requirements. Submit a complete list of all additional subcontractors 2 After having made a good-faith effort to achieve the MWBE requirements, the Prime can only achieve partial success. I submit the Subcontractor Participation Form B, Form C, Form D and Form E along with this Affidavit, which details how the Prime will partially achieve the contract requirements. Submit a complete list of all additional subcontractors I request a partial waiver and will meet the following MWBE participation goals: Partial waiver of MWBE subcontract participation: o % Minority/Women Prime % for certified MBE-owned businesses and/or % for certified WBE-owned businesses. After having made a good faith effort to achieve the MWBE requirements for this contract, the Prime is unable to achieve the requirements and/or sub requirements for this contract. I submit the MWBE Participation Form D and Form E, along with this Affidavit, which details the steps the Prime has taken in an attempt to achieve the contract requirements. Therefore, I request a full waiver.

### IF YOU HAVE CHECKED BOX 2 OR 3, THE FOLLOWING IS APPLICABLE:

If a bidder is unable to comply with the goals established in a bid for a project, the bidder may submit a request for a waiver at the time of bid submission. However, occasions for granting waivers will be limited.

# BALTIMORE COUNTY, MARYLAND Certified MWBE Utilization and Fair Solicitation Affidavit (FORM A)

- 2) The request for waiver shall include documentation that demonstrates the bidder's good faith efforts to comply with the goals, including:
  - a. Signed unavailability statements from all MBEs and WBEs that the bidder solicited for participation; and
  - b. Copies of solicitation documentation to include the scope of services to be performed by the subcontractors accompanied with the following:
    - i. Emails, letters, facsimile transmittals and confirmations containing plans, specifications, and anticipated time schedule for portions of the work to be performed and meeting notes and agendas clearly identifying the certified MBE or WBE classification and dates that the bidder contacted each; and
    - ii. Telephone logs containing names, addresses, dates, telephone numbers, work to be performed, anticipated time schedule and classification of certified MBEs and WBEs contacted.
    - iii. Responses from MWBE firms contacted to fulfill the goal.

# As I have checked Box 2 or 3 of this Affidavit, I understand I must submit the following supporting documentation with the bid:

- Subcontractor Participation Schedule (Form B)
- *MWBE Subcontractor Disclosure and Participation Statement* (Form C)
- MWBE Subcontractors Unavailable Certificate (Form D) (if applicable)
- *MWBE Outreach Efforts Compliance Statement* (Form E) (if applicable)

I acknowledge that the MWBE subcontractors/suppliers listed on the *Subcontractor Participation Schedule* (Form B) will be used to accomplish the percentage of MWBE participation that the Prime shall achieve. A fully executed Form C must match Form B.

In the solicitation of subcontract quotations or offers, MWBE subcontractors were provided the same information and amount of time to respond, as were non-MWBE subcontractors.

The solicitation process was conducted in such a manner so as to not place MWBE subcontractors at a competitive disadvantage to non-MWBE subcontractors.

I solemnly affirm under the penalties of perjury that this Affidavit is true to the best of my knowledge, information, and belief.

Bidder/Offeror Name	Phone Number
Biddel/Offeror Paine	Thone Number
Address	Affiant Signature
Address (continued)	Printed Name & Title
E-mail address	Date

## BALTIMORE COUNTY, MARYLAND SUBCONTRACTOR PARTICIPATION SCHEDULE (FORM B)

\*This document <u>must</u> be completed and submitted with Bid/Proposal to Baltimore County.

NOTE: If you do not complete and submit this form with your bid or offer to the County, the County may, in its sole discretion, deem your bid or offer NON-RESPONSIVE and accordingly the COUNTY WILL NOT CONSIDER YOU FOR CONTRACT AWARD.

Prime Name	Prime Address, Telephone Number and Email			
Bid/Proposal Name and Number	Project Location			
	Base Bid\$			
1. Subcontractor Name and Tax ID	Subcontractor Address			
Telephone Number	Minority Status (If applicable):			
Email Address	□ African American □ Female □ Asian American Pacific □ Native American			
Select One: ☐ MBE ☐ WBE ☐ SBE ☐ N/A	☐ Asian American Sub-continent ☐ Hispanic American			
Provide if Applicable:  MDOT Baltimore City #	□ Supplier, Wholesaler and/or Regular Dealer - 60% Rule			
NAICS Code(s), Work to be Performed and Subcontract Dollar Amount	Percent of Total Contract (See instructions on Page 1 of the MWBE PARTICIPATION SUMMARY for 60% rule)%			
2. Subcontractor Name and Tax ID	Subcontractor Address			
Telephone Number	Minority Status (If applicable):			
Email Address	□ African American □ Female □ Asian American Pacific □ Native American			
Select One: MBE ☐ WBE ☐ SBE☐ N/A ☐	☐ Asian American Sub-continent ☐ Hispanic American			
Provide if Applicable:  MDOT Baltimore City #	□ Supplier, Wholesaler and/or Regular Dealer - 60% Rule			
NAICS Code(s), Work to be Performed and Subcontract Dollar Amount	Percent of Total Contract (See instructions on Page 1 of the MWBE PARTICIPATION SUMMARY for 60% rule)%			
3. Subcontractor Name and Tax ID	Subcontractor Address			
Telephone Number	Minority Status (If applicable):			
Email Address  Select One: MBE WBE SBE N/A	□ African American       □ Female         □ Asian American Pacific       □ Native American         □ Asian American Sub-continent       □ Hispanic American			
Provide if Applicable:  MDOT Baltimore City #	□ Supplier, Wholesaler and/or Regular Dealer - 60% Rule			
NAICS Code(s), Work to be Performed and Subcontract Dollar Amount	Percent of Total Contract (See instructions on Page 1 of the MWBE PARTICIPATION SUMMARY for 60% rule)%			
Subcontractor Total Dollar Amount \$	Total Subcontractor Percent of Entire Contract%			
Form Prepared by:	Reviewed and Accepted by Baltimore County Minority Business Enterprise Office			
Name/Date:	Name			
Title:	Title			
Email:	Date			
MBE or WBE Prime Participation To MBE Subcontracting Participation WBE Subcontracting Participation Total MWBE Participation  Rev 12/2024 Total SBE Participation				

MWBE Plan Packet Page| 9

## **BALTIMORE COUNTY, MARYLAND**

# MWBE PRIME PARTICIPATION SCHEDULE (Form B-Prime)

PLEASE COMPLETE AND SUBMIT THIS FORM TO ATTEST EACH SPECIFIC ITEM OF WORK THAT YOU AS THE MWBE PRIME FIRM WILL PERFORM USING ITS OWN WORKFORCE PERTAINING TO THE PERCENTAGE STATED ON THE SUBCONTRACTOR PARTICIPATION SCHEDULE (FORM B) FOR PURPOSES OF MEETING THE MWBE PARTICIPATION GOALS.

*This document <u>must</u> be completed and submitted with Bid/Proposal to Baltimore County.						
	omplete and submit this form with your bio PONSIVE and accordingly the COUNTY Wi					
count the distinct, clearly defined portion of the work of the con			(Prime Contractor's Name) with Certification Number th Solicitation No, such MWBE Prime Contractor intends to ontract that the MBE/WBE Prime Contractor performs with its own BE participation goal, at least \$ which equals to%			
NUMBER, LINE ITEMS OR		PR	SCRIPTION OF SPECIFIC ODUCTS AND/OR RVICES	VALUE OF THE WORK		
MWBE PRIME C	ONTRACTOR		MWBE PRIME CONTRACT	TOR		
Signature of Repres	sentative:		Minority Status:			
			☐ African American			
Printed Name and			☐ Hispanic American			
			□ Women			
Firm's Name:			☐ Asian American			
Federal Identification Number:			☐ Native American			
Address:						
Telephone:			Reviewed and Accepted by Baltimore County Minority Business Enterprise Office			
Email Address:			Name			
Certified Yes No No			Title			

Rev 12/2024

Date:

Certifying Jurisdiction \_

# BALTIMORE COUNTY, MARYLAND MWBE SUBCONTRACTOR DISCLOSURE AND PARTICIPATION STATEMENT (FORM C)

\*This document must be completed and submitted with Bid/Proposal to Baltimore County.

NOTE: If you do not complete and submit this form with your bid or offer to the County, the County may, in its sole discretion, deem your bid or offer NON-RESPONSIVE and accordingly the COUNTY WILL NOT CONSIDER YOU FOR CONTRACT AWARD.

NOTE: ANY INCONSISTENCY BETWEEN THIS FORM AND FORM B MWBE PARTICIPATION MAY RENDER A BID/PROPOSAL NON-RESPONSIVE AND THE COUNTY WILL NOT CONSIDER YOU FOR CONTRACT AWARD.

Contract Name, Bid/Proposal Number:	
Prime Contractor Name:	
Name of MWBE Subcontractor:	
Subcontractor Contact Name, Title	Subcontractor Email Address
☐ MDOT ☐ Baltimore City	Certification Number
☐ MBE ☐ WBE ☐ SBE ☐ N/A	
1. NAICS Code(s), Work/Services to be performed	l by MWBE Subcontractor:
	Percent of Total Contract (See instructions on Page 1 of the MWBE PARTICIPATION SUMMARY for 60% rule)
2. Subcontract Amount: \$	
3. Bonds - Amount and type required of Subcontra	actor if any:
•	Completion Date:
	No
	No ******************
NOTE: If the Prime is notified that it will be awarded the above enter into a subcontract for the work/service indicated above up Baltimore County, and provide a copy of the fully executed MV AWARD (FORM C-Subcontractor) accompanied with the antiemobilization timeframe) to <a href="mailto:mwbe@baltimorecountymd.gov">mwbe@baltimorecountymd.gov</a> with the authority of the subcontractor of the subcontracto	e referenced contract, the undersigned MWBE subcontractor and Prime must bon the Prime's execution of a contract for the above referenced project with WBE SUBCONTRACTOR PARTICIPATION NOTICE OF INTENT TO cipated Work Breakdown Schedule (providing the subcontractor's thin 10 calendar days of receipt by the Prime of FORM C- Subcontractor or Baltimore City certified MWBE firm. The terms and conditions stated
Signature of MWBE Subcontractor:	Date:
Prime's Printed Name and Title:	Email:
The terms and conditions stated above are consistent with our agreement of the conditions of the condi	eements.
Signature of Prime:	Date:

Revised 12/2024

# BALTIMORE COUNTY, MARYLAND MWBE -UNAVAILABILITY CERTIFICATE (FORM D)

If applicable, this document must be completed and submitted with Bid/Proposal to Baltimore County.

NOTE: If you do not complete and submit this form with your bid or offer to the County, the County may, in its sole discretion, deem your bid or offer NON-RESPONSIVE and accordingly the COUNTY WILL NOT CONSIDER YOU FOR CONTRACT AWARD.

1. It is here	by certified that the firm of			
		(Name of Minority fire	m)	
located at				
	(Number)	(Street)		
-	(City)	(State)	(Zip)	
was offered	an opportunity to bid on the		_contract.	
2. The_ the work/ser	vice or unable to prepare a bid for th	(MWBE Firm), is eith	er unavailable for eason(s):	
	The or analysis to propare a literary			
Signature of S	Subcontractor MWBE Representative	Title	Date	
MDOT/Baltin	nore City Certification #	Email Address #	Telephone #	
3. PRIME'S S	IGNATURE AND CERTIFICATION			
	oath that I contacted the Certified MWB ices for the above-contract or failed to			
Signa	ture of Prime	Title	Date	

Rev 12/2024

# BALTIMORE COUNTY, MARYLAND MWBE - OUTREACH EFFORTS - COMPLIANCE STATEMENT (FORM E)

\*This document must be completed and submitted with Bid/Proposal to Baltimore County.

NOTE: If you do not complete and submit this form with your bid or offer to the County, the County may, in its sole discretion, deem your bid or offer NON-RESPONSIVE and accordingly the COUNTY WILL NOT CONSIDER YOU FOR CONTRACT AWARD.

In conjuncti		he bid or offer submitted in response to Solicitation Number, I
	1.	Bidder/Offeror identified opportunities to subcontract in these specific work categories:
	2.	Attached to this form are copies of the solicitation documentation in accordance with Section 6 (E) Bid Requirements of the Executive Order, used to solicit certified MWBEs for the subcontract opportunities accompanied with the signed MWBE Subcontractor Unavailability Certificate (Form D).
	3.	Bidder/Offeror made the following attempts to solicit MWBEs:
G: 4 I	2:11 00	
Signature – I		
Print or Type	Name of	Firm
Street Addre	SS	
City	State	Zip Code
Date		



#### JOHN A. OLSZEWSKI, JR.

County Executive

#### SEVETRA PEOPLES-BROWN

Executive Director
Chief of Diversity, Equity and Inclusion

To: Contractors/Consultants

From: Minority and Women Business Enterprise Office

Date: December 13, 2024

Subject: Compliance Reporting and Penalties

Baltimore County, Maryland (the "County") requires all Prime Contractors and all Subcontractors to submit payment reports by the 10th of each month through an online MWBE Compliance Portal (PRISM). The Portal can be found under Compliance Reporting for Primes and Subcontractors at www.baltimorecountymd.gov/ go/mwbe. In the event you are not able to enter your payments in PRiSM, a spreadsheet is attached for your use. Please be sure to list the PO for each invoice/ payment reported and include in your submission any corresponding documentation (e.g. copies of invoices or canceled checks).

The County has found that a number of companies are failing to file reports in a timely manner, which makes it difficult for the County to verify compliance. As a result, the County has determined to assess penalties for non-compliance, effective September 1, 2018, as follows:

- (a) For failure to file timely monthly reports:
  - a. Assessment of a late fee of \$10 per day per task, up to a maximum of \$1,500 per task; and/or
  - b. For multiple violations, termination of the contract for convenience or for default, with the contractor suspended from participating in County contracts for five (5) years.
- (b) For failure to meet MWBE requirements:
  - a. Assessment of a penalty of up to 10% of the contract value; and/or
  - b. Termination of the contract for convenience, with the contractor suspended from participating in County contracts for five (5) years together with assessment of a penalty of up to 10% of the contract value; and/or
  - c. Termination of the contract for default together with assessment of a penalty of 10% of the contract value.

Each action and/or remedy described above is at the sole discretion of the County, and is in addition to any damages which the County may be entitled to under the contract. This short video can be used as guidance on submitting the Prime to Subcontractor Payment

Reporting:

http://stage.prismcompliance.com/etc/movies/vendor contractpayment tutorial.htm

If after contract expiration, it has been determined the MWBE firms named were not used or were under used, by the contractor and supporting documentation was not provided and approved by the County the contractor may be assessed a penalty of up to 10% of the contract value and/or suspended from participating in County contracts for 5 years.

Questions regarding this correspondence and/or the use of this system can be directed to the MWBE Office at mwbe@baltimorecountymd.gov or call (410) 887-3407.

Attachment: MWBE Payment Report Form

MWBE Payment Acknowledgement Form

Cc: File

# **SECTION V**

# **POST AWARD DOCUMENTS**

This Section to be Completed by Successful Bidder after Award

# CONTRACT AGREEMENT

THIS CONTRACT AGREEMENT ("Contract"), IS MADE THIS day of day of by and between Baltimore County, Maryland, a body corporate and
politic ("County"), and, by and between Baltimore County, Maryland, a body corporate and, ("Contractor").
WITNESSETH, that the Contractor, for and in consideration of the payment or payments herein specified and agreed to by the County, hereby covenants and agrees to furnish and deliver all the materials and to do and perform all the work, services, and labor in fulfillment of the requirements of Contract Number "Project") in strict conformity with the solicitation, plans, specifications, special provisions, any and all addenda, and the proposal, at the prices named therein, and all of which are collectively the Proposal, and said Proposal is attached hereto and made a part thereof.
The Project shall be done in strict compliance with (i) the Proposal, (ii) the Baltimore County Department of Public Works and Transportation September 2023 "Standard Specifications for Construction and Materials" and "Standard Details for Construction" (iii) and any and all revisions thereto as of the date of advertisement, including but not limited to the General Conditions Building Projects, as applicable, and all of which (i-iii) are made a part hereof and incorporated herein (collectively, the "Specifications"). Contractor understands and agrees it is Contractor's responsibility and obligation to obtain a copy of the "Specifications" and agrees the Specifications are incorporated herein. Copies are available on the County's website at <a href="https://www.baltimorecountymd.gov/departments/public-works/standards">www.baltimorecountymd.gov/departments/public-works/standards</a> .
The Project shall be subject to the inspection and approval of the Director of Public Works and Transportation for Baltimore County, or his authorized representative, and in the event any portion thereof shall be rejected by said Director or his representative as defective or unsuitable, then the said portion shall be removed and replaced and be performed anew to the satisfaction and approval of the said Director or his representative at the cost and expense of the Contractor.
THE CONTRACTOR AFFIRMS that it is aware of, and will comply with, the provisions of Sections 14-101 through 14-108 of the Election Law Article of the Annotated Code of Maryland, as the same may be amended from time to time, which require that every person who makes, during any 12-month period, one or more contracts, with one or more Maryland governmental entities involving cumulative consideration, of at least \$200,000.00, to file with the State Board of Elections certain specified information to include disclosure of attributable political contributions in excess of \$500 during defined reporting periods.
THE CONTRACTOR FURTHER COVENANTS AND AGREES that all the Project shall be furnished, performed and delivered, in every respect, to the satisfaction and approval of the Director of Public Works and Transportation, aforesaid, on or before the expiration of <b>FOUR HUNDRED (400) WORKING DAYS</b> (the "Contract Period") after written notice has been given by the Director or their authorized representative to begin the work.
IT IS AGREED THAT TIME IS OF THE ESSENCE. In the event the Contractor fails to achieve Final Completion and Final Acceptance of the Contract work within the Contract Period specified herein, plus any extensions thereto agreed to in writing by a legally authorized representative of the County pursuant to the terms of this Contract, then Contractor shall pay the County the sum of <b>FIVE HUNDRED DOLLARS</b> (\$500.00) as Liquidated Damages for each <b>WORKING DAY</b> after the expiration of the Contract Period, as may be extended by the County, until the Contractor achieves Final Completion and Final Acceptance of the Project.
Contractor's Initials

#### IT IS FURTHER AGREED that:

- (a) These Liquidated Damages are a reasonable estimate of the County's damages solely due to the public's loss of use of the Project during the delay period and is not a penalty.
- (b) It is very difficult, if not impossible, to accurately measure the damages to the County due to the public's loss of use of the Project during the delay period.
- (c) Notwithstanding GP 8.09 of the Baltimore County Standard Specification for Construction, in addition to the damages due to the public's loss of use of the Project during the delay period, the County is likely to incur additional direct costs during the delay period, including but not limited to, costs for construction management, consultants, architectural services, office trailer and supplies, utilities, County employees' time, County vehicles, and such other costs that the County will incur to continue administration of the construction and the Contract during the delay period, all of which will be monitored by the County, and if so required by the County, the Contractor shall pay such actual damages incurred during the delay period. THE PARTIES HERETO UNDERSTAND AND AGREE THAT CONTRACTOR'S OBLIGATION TO PAY THE COUNTY FOR ACTUAL DAMAGES DURING THE DELAY PERIOD SHALL BE IN ADDITION TO THE CONTRACTOR'S OBLIGATION TO PAY THE LIQUIDATED DAMAGES DUE TO THE PUBLIC'S LOSS OF USE OF THE PROJECT.
- (d) The County shall have the right, but not the obligation, to deduct the Liquidated Damages due to the public's loss of use of the Project, and the County's actual costs and costs to continue administration of the construction and the Contract, from any monies due or any monies that may become due to the Contractor.

IT IS DISTINCTLY UNDERSTOOD AND AGREED that no claim for extra work, material or overhead not specifically provided for in the Contract will be allowed by the County, nor shall the Contractor do any work or furnish any materials not covered by this Contract and the Specifications, unless the same is ordered in writing by a legally authorized representative of the Department of Public Works and Transportation in accordance with the terms of the Contract. Any such work or materials which may be done or furnished by the Contractor without any such written order first being given shall be at said Contractor's sole risk, cost and expense and Contractor hereby covenants and agrees that without such written order, Contractor shall make no claim for compensation for work, materials, or overhead so done or furnished.

NOTWITHSTANDING GP 4.06 OF THE BALTIMORE COUNTY STANDARD SPECIFICATIONS FOR CONSTRUCTION, IT IS SPECIFICALLY AGREED that the Contractor shall have no entitlement to damages arising out of delay, disruption, interference or hindrance from any cause whatsoever. However, this provision shall not preclude recovery or damages by the Contractor for hindrances or delays due solely to fraud or gross negligence on the part of the County or its agents.

IT IS FURTHER DISTINCTLY AGREED that the said Contractor shall not assign this Contract, nor any part thereof, nor any right to any of the monies to be paid hereunder, nor shall any part of the work to be done or material furnished under said Contract be sublet without the prior written consent of a legally authorized representative of the Department of Public Works and Transportation in accordance with the terms of this Contract. Further, the acceptance of the final payment by the Contractor shall effectuate a release in full of all claims against County and its officials, employees, representatives, and agents arising out of, or by reason of the Project and this Contract.

The Contractor shall review government issued identification and badge all employees of the Contractor and its subcontractors. The Contractor shall also review all federal forms, including but not limited to I-9's, for compliance as well as copies of all employment eligibility and identity documentation maintained to the extent required by law.

The Bonds, given by the Contractor in a sum equal to the total contract price of the Project in compliance with the terms and provisions of this Contract, are hereby attached and incorporated herein.

IT IS AGREED that in the event that the County is delayed or prevented from timely execution of this Contract, the Contractor releases County and agrees Contractor shall have no action, claim or demand against County therefore.

Contractor's	Initials

Date Rev. 09/2024

THE CONTRACTOR HEREBY FURTHER AGREES to receive the prices set forth in the Proposal incorporated herein as full compensation for the completion of the Project and, in all respects, to complete said Contract to the satisfaction of the County.

THE	CONTD	ACTOD	REPRESENTS	AND	WADDANTS
$-1$ H $_{\rm F}$	CONTR	ACTOR	KEPKESENIS	AND	WAKKANIS:

- (i) it is duly formed and validly existing under the laws of the State of \_\_\_\_\_;
- (ii) it is in good standing in the State of Maryland;
- (iii) it has the power and authority to consummate the obligations and responsibilities contemplated hereby, and has taken all necessary action to authorize the execution, delivery and performance required under this Contract;
- (iv) the Contractor and the person executing this Contract for the Contractor each warrant that he/she is duly authorized by the Contractor to execute and seal this Contract on the Contractor's behalf;
- (v) the warranties of merchantability and fitness for a particular purpose and use and warranties of title and against infringement, and all express warranties contained in this Contract, including but not limited to the Proposal (and any sample or model presented by Contractor and expressly accepted by the County) shall apply to the portion of this Contract pertaining to or for goods;
- (vi) all representations and warranties made in the Proposal and herein remain true and correct in all respects when made, as of the date of this Contract, and throughout the term of this Contract; and
- (vii) there exists no actual or potential conflict of interest between its performance under this Contract and its engagement or involvement in any other personal or professional activities and in the event such conflict or potential conflict arises during the term of this Contract, the Contractor shall immediately advise the County in writing thereof.

THE CONTRACTOR shall not disclose any documentation and information of any kind or nature disclosed to the Contractor in the course of its performance of duties hereunder without the express prior written consent of the County.

Those sections in this Contract which by their nature are intended to survive, including but not limited to, Contractor's representations and warranties, confidential information, and indemnification shall survive the termination of this Contract.

IN WITNESS WHEREOF, the Contractor has hereunto set its hand and seal the day and year first above written.

CONT	RACTOR NAME:		_
WITNESS FEDER	RAL TAX ID or SS #:		
	By:		(Seal)
Type (Print) Name	Name:		
Type (Print) Name	Title:	Date:	
WITNESS:	BALTIMORE COUNTY, MARYLAND		
Executive Secretary	By:	Date: Officer	_
Type (Print) Name			
APPROVED FOR FORM AND LEGAL AND SUFFICIENCY* (Subject to execution by the duly authorized	APPROVED:		
Administrative official and Chairperson of the County Council, as indicated).	Lauren T. Buckler, Director Department of Public Works & Transportation		

Office of the County Attorney

Rev. 09/2024

<sup>\*</sup>Approval of Form and Legal Sufficiency does not convey approval or disapproval of the substantive nature of this transaction. Approval is based upon typeset documents. All modifications require re-approval.

#### PERFORMANCE BOND

Principal	Business Address of Principal			
Surety	Obligee:	BALTIMORE COUNT A body corporate and	,	AND
A Corporation of the State of	and authorized to do business in Maryland			
		DOLLARS	\$	
Penal Sum of Bond (express in words and figures)				
Back River Neck Road 16" and 24" Water Main Replacement	ent - Phase 3			20
Contract Name	•	Date of Contrac	t	
23186 WX0				20

KNOW ALL MEN BY THESE PRESENTS, that we, the PRINCIPAL, above-named, and SURETY, above-named, and authorized to do business in the State of Maryland, are held and firmly bound unto the OBLIGEE, above-named, in the penal sum of the amount stated above, for the payment of which sum well and truly to be made, we bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

Contract Number

WHEREAS, THE PRINCIPAL entered into a certain contract with the OBLIGEE described and dated as shown above and is required to provide this bond pursuant to Maryland State law and/or County law and the contract.

NOW, THEREFORE, if the aforesaid PRINCIPAL shall well and truly perform and fulfill all the undertakings, covenants, terms, conditions, and agreements of said contract during the original term of said contract and any extensions thereof that may be granted by the OBLIGEE with or without notice to the SURETY, and during the life of any guaranty required under the contract, and shall also well and truly perform and fulfill all the undertakings covenants, terms, conditions and agreements of any and all duly authorized modifications of said contract that may hereafter be made, notice of which modifications to the SURETY being hereby waived, then, this obligation to be void; otherwise to remain in full force and effect.

THE SURETY FURTHER GUARANTEES That it is (a) licensed in the State of Maryland, (b) rated "B" or better by the A.M. Best Company, (c) on federal funded projects, authorized by the underwriting limitation contained in the U.S. Department of the Treasury Circular 570, as amended, to guaranty the amount of the Bid, and (d) in good standing as determined by the County's Engineer. A Performance Bond is required for each and every Contract in excess of twenty-five thousand (\$25,000). A Performance Bond shall be in the amount equal to at least one hundred (100%) percent of the Contract price. The fully executed Performance Bond shall be delivered by the Bidder to the Department's Division of Construction Contracts Administration no later than the time the Contract is to be executed by the Contractor.

IN WITNESS WHEREOF, the above-bounded parties have executed this instrument under their several seals on the date indicated above, the name and seal of each party being hereto affixed and these presents duly signed by its undersigned representative, pursuant to authority of its governing body.

In Presence of:	Individual Principal	
Witness:	as to:	(SEAI
Print Name:	Print Name:	
Attest:	Corporate Principal	
	(Name of Corporation)	
Witness:	Ву:	Affix
Print Name:	Print Name:	Corporate
	Title:	Seal
Attest:	Surety	
Business Address:	(Name of Surety)	
Witness:	Ву:	Affix
Print Name:	Print Name:	Corporate
	Title:	Seal

Bond No.

**Date Bond Executed** 

## PAYMENT BOND

Rond	Number	
DONG	number	

Principal	Business A	Address of Principal	
	Obligee: BALTIMORE COUNTY, MARYLAND		
Surety		A body corporate a	nd politic
A Corporation of the State ofa	and authorized to	o do business in Maryland	
Penal Sum of Bond (express in words and figures)	DOL	_LARS \$	<del></del>
• • • • • • • • • • • • • • • • • • • •	2		20
Back River Neck Road 16" and 24" Water Main Replacement – Pha Contract Name	<u>se 3</u> D	ate of Contract	_ 20
23186 WX0	_		_ 20
Contract Number	D	ate Bond Executed	
KNOW ALL MEN BY THESE PRESENTS, that we, the PRINC business in the State of Maryland, are held and firmly bound unto for the payment of which sum well and truly to be made, we bind cand severally, firmly by these presents.  WHEREAS, THE PRINCIPAL entered into a certain contract we provide this bond pursuant to Maryland State law and/or County L.  NOW, THEREFORE, the condition of this obligation is such the supplying labor and/or material to the PRINCIPAL and to any subscontract and any and all duly authorized modifications of said contbeing hereby waived, then, this obligation to be void; otherwise to the Surety Further Guarantees That it is (a) license on federal funded projects, authorized by the underwriting limitation to guaranty the amount of the Bid, and (d) in good standing as detevery Contract in excess of twenty-five thousand (\$25,000). A Papercent of the Contract price. The fully executed Payment Bond's Contracts Administration no later than the time the Contract is to be IN WITNESS WHEREOF, the above-bounded parties have exthe name and seal of each party being hereto affixed and these prices.	the OBLIGEE, abourselves, our hein with the OBLIGEE aw and the contract if the aforesaid contractor of the Fitract that may her remain in full force d in the State of Mon contained in the termined by the Cyment Bond shall thall be delivered the executed by the executed this instru	described and dated as sho act.  PRINCIPAL shall promptly no PRINCIPAL in the prosecution eafter be made, notice of where and effect.  Maryland, (b) rated "B" or before u.S. Department of the Treounty's Engineer. A Payme be in the amount equal to a by the Bidder to the Department of the Department of the Treounty's Engineer.	m of the amount stated above, so successors and assigns, joint own above and is required to make payments to all persons on of the work provided for in satisfich modifications to the SURE ter by the A.M. Best Company, easury Circular 570, as amendent Bond is required for each and t least one hundred (100%) nent's Division of Construction als on the date indicated above.
its governing body.  In Presence of:		Individual Principal	
Witness:	as to:		(SEAL)
Print Name:		ə:	
Finit Name.	riiit Naiit	j	
Attest:		Corporate Principal	·
	(1)	Name of Corporation)	
Witness:	Ву:		Affix
Print Name:	Print Name	:	Corporate
	Title:		Seal
Attest:		Surety	
Allooti		Curoty	
Pusiness Address		(Name of Surety)	
Business Address: _			
Witness:	-		
Print Name:		:	•
	Title:		Seal
Reviewed for Baltimore County Requirements			
Office of the County Att	torney		

#### **BALTIMORE COUNTY, MARYLAND**

#### **INSURANCE PROVISIONS**

#### 1. GENERAL REQUIREMENTS

1.1 <u>Coverages Required:</u>

Unless otherwise required by the specifications or the contract, the Contractor/Vendor shall purchase and maintain the insurance coverage's listed herein.

1.2 <u>Certificate of Insurance:</u>

Before starting work on the contract, or prior to the execution of the Contract on those bid, the Contractor/Vendor shall provide Baltimore County, Maryland with verification of insurance coverage evidencing the required coverages.

1.3 <u>Baltimore County as Insured:</u>

The coverage required, excluding Workers' Compensation and Employers' Liability and Medical Malpractice Liability/Professional Liability/Errors and Omissions Liability, must include Baltimore County, Maryland and its agents, employees, officers, directors, and appointed and elected officials as an additional insured.

1.4 <u>Contractor's/Vendor's Responsibility:</u>

The providing of any insurance herein does not relieve the Contractor/Vendor of any of the responsibilities or obligations the Contractor/Vendor has assumed in the contract or for which the Contractor/Vendor may be liable by law or otherwise.

1.5 Failure to Provide Insurance:

Failure to provide and continue in force the required insurance shall be deemed a material breach of the contract. The Contractor/Vendor must maintain the insurance coverages required under the terms and conditions on this Contract while this Contract is in effect including renewal and extension terms.

#### 2. INSURANCE COVERAGES

- 2.1 <u>General Liability Insurance</u>
  - 2.1.1 Minimum Limits of Coverage:
     Personal Injury Liability and Property
     Damage Liability Combined Single Limit
     \$500,000 each occurrence.
  - Such insurance shall protect the 2.1.2 Contractor/Vendor from claims which may arise out of, or result from, the Contractor's/Vendor's operations under the contract, whether such operations be by the Contractor/Vendor, any subcontractor, anyone directly or indirectly employed Contractor/Vendor or Subcontractor, or anyone for whose acts any of the above may be liable.
  - 2.1.3 Minimum Coverages to be Included:
    - (a) Independent Contractor's coverage;
    - (b) Completed Operations and Products
      Liability coverage:
    - (c) Contractual Liability coverage.

2.1.4 Damages not to be Excluded:
Such insurance shall contain no exclusions applying to operations by the Contractor/Vendor or any Subcontractor in

the performance of the Contract including but not limited to:

- (a) Collapse of, or structural injury to, any building or structure;
- (b) Damage to underground property; or
- (c) Damage arising out of blasting or explosion.

#### 2.2 Automobile Liability Insurance

2.2.1 Minimum Limits of Coverage: Bodily Injury Liability and Property Damage Liability Combined Single Limit - \$500,000 any one accident.

2.2.2 Minimum Coverages to be Included: Such insurance shall provide coverage for all owned, non-owned and hired automobiles.

2.3 Workers' Compensation and Employers' Liability Insurance

Such insurance must contain statutory coverage, including

Employers' Liability insurance with limits of at least:
Bodily Injury by Accident - \$250,000 each accident
Bodily Injury by Disease - \$500,000 policy limit
Bodily Injury by Disease - \$250,000 each employee

2.4 Valuable Papers and Records Coverage and Electronic Data Processing (Data and Media) Coverage

Minimum Limits of Coverage: \$100,000 Per Claim and Each Occurrence \$100,000 in the Aggregate

2.5 Other

Such other insurance in form and amount as may be customary for the type of business being under taken by the Contractor/Vendor.