BALTIMORE COUNTY, MARYLAND DEPARTMENT OF PUBLIC WORKS AND TRANSPORTATION DIVISION OF CONSTRUCTION CONTRACTS ADMINISTRATION 111 WEST CHESAPEAKE AVENUE TOWSON, MARYLAND 21204



Contract No. 25067 GX0 Project No. 10000752 Cloverland Park Renovations & Enhancements -12340 Dulaney Valley Road, Phoenix, Maryland 21131 Phoenix – District 10c3

ADDENDUM NO. 1

DATE: 6/6/2025

Contact: Anthony Crews, 410-887-3531, tcrews@baltimorecountymd.gov

To All Bidders

This addendum is hereby made a part of the Proposal and the Special Provisions, and is hereby incorporated into the Contract. Should this addendum conflict with any portion of the Special Provisions, the Proposal, or any prior addenda, this addendum shall supersede and control.

Please note the attached changes, corrections, and/or information in connection with the contract and submit bids and be otherwise governed accordingly.

In the Specifications

Attached are new pages 145A&B, referencing Watering Schedule.

In the Drawings

Attached are revised drawings: Sheet 23 of 24 Drawing No. C431 and Sheet 24 of 40 Drawing No.C432.

Attachments - 4

Please sign below acknowledging receipt of this addendum and return with your bid.

Company Name

Signature

Athletic Field Maintenance - Newly Established Turfgrass

Watering Schedule:

Initial Establishment Phase (Immediately After Seeding):

- **Frequency**: Water 2–3 times per day to keep the seedbed consistently moist and prevent drying out. This is critical for seed germination and early seedling survival.
- **Amount**: Apply enough water each cycle to moisten only the top 0.5–1 inch of soil. Avoid overwatering or creating puddles, as this can cause disease and seed washout.
- **Timing**: Early morning is optimal for irrigation to minimize evaporation and disease risk, but during establishment, multiple cycles throughout the day may be necessary depending on weather (hot, dry, or windy conditions may require more frequent watering).
- **Duration**: *<u>First 10-14 days</u>*, continue this schedule until seeds have germinated and seedlings reach about 1.5-2 inches in height.

Transition Phase (After Seedlings Reach 2 Inches Tall): typically, starts after 14 days from seeding

- **Frequency**: Gradually reduce watering to 1–2 times per day as seedlings mature and roots develop.
- **Amount**: Increase the depth of watering slightly to encourage deeper root growth, moistening the top 1.5–2 inches of soil.
- **Goal**: Begin shifting toward deeper, less frequent irrigation as the turf becomes established.

Post Establishment (After First Mowing, Solid Stand):

Frequency: Water once per day, unless rain event provided root zone with adequate moisture content, then transition to every other day as turf density increases and roots deepen.

Amount: Increase run times to moisten the soil to a depth of 4 inches, which promotes strong root development.

Long-Term Maintenance: Once the turf is established and has been mowed two or three times, adopt a deep and infrequent watering schedule (once or twice per week, applying 1–1.5 inches of water per week, including rainfall).

Summary Table

Phase	<u>Frequency</u>	Amount per Cycle	<u>Soil Depth</u> Moistened	<u>Notes</u>
Immediately after seeding	2–3 times/day	Light, avoid puddling	0.5–1 inch	Keep surface moist, prevent drying
Seedlings 2" tall	1–2 times/day	Moderate	1.5–2 inches	Begin reducing frequency, increase depth
Post- establishment	1/day → every other day	Deep, infrequent	Up to 4 inches	Encourage deep roots, prepare for mowing
Established turf	1–2 times/week	1–1.5 inches/week	4 inches	Deep, infrequent, adjust for rainfall

**Note: Always adjust the schedule based on specific field conditions, weather, and soil type for best results



-	DIVATIN	LI DUALL						
	PLAN SCALE:	AS SHOWN	APPROVED BY:	BALTIMORE	COUNTY	OFFICE OF	F BUDGET	AND FINA
	PROFILE SCALE:		DATE:			CLOVERI	AND PAI	RK CRICH
	WATER	FIELD ENGINEER				STORN	I DRAI	N PRO
						CONS	STRUCTIC	N DOCU
				SUBDIVISION: PHOENIX	12340	DULANEY	VALLEY	ROAD, P

Contract No.25067 GX0 Addendum No.1

Revised, June 6, 2025

EXISTING UTILITY NOTE

THE ENGINEER IN NO WAY GUARANTEES THE ACCURACY OR COMPLETENESS OF EXISTING UTILITIES. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THE LOCATION AND ELEVATION OF EXISTING UTILITIES TO HIS OWN SATISFACTION AND NOTIFY THE ENGINEER IMMEDIATELY, PRIOR TO CONSTRUCTION, IF FINDINGS CONTRADICT THOSE LOCATIONS AND ELEVATIONS SHOWN.

GENERAL UTILITY NOTES

- 1. MAINTAIN AT LEAST 12" OF VERTICAL CLEARANCE BETWEEN UTILITIES. WHEREVER UTILITY CLEARANCES ARE LESS THAN 12" OR DO NOT PERMIT FULL COMPACTION OF BACKFILL WITH POWER EQUIPMENT, CONTRACTOR SHALL PROVIDE CONCRETE ENCASEMENT WITH FLOWABLE FILL EXTENDING AT LEAST 5' ON ALL SIDES OF CROSSING.
- 2. PROVIDE SUMP INSERTS FOR ALL NYLOPLAST DRAIN BASINS.

STRUCTURE TABLE

STRUCTURE #	STRUCTURE TYPE	TOP ELEV.	INV. IN	INV. OUT	COORDINATES
E-101	HPDE END SECTION	- 291.22	15" HDPE (N) 289.76		N: 656,800.56 E: 1,439,750.62
M-102	30" NYLOPLAST DRAIN BASIN	GRATE 296.05	12" HDPE (E) 290.74 12" HDPE (N) 293.20 12" HDPE (W) 290.73	15" HDPE (S) 290.48	N: 656,860.82 E: 1,439,766.02
M-103	18" NYLOPLAST DRAIN BASIN	GRATE 298.47	12" HDPE (N) 295.47	12" HDPE (S) 293.37	N: 656,877.85 E: 1,439,766.52
M-104	18" NYLOPLAST DRAIN BASIN	RIM 303.45	12" HDPE (N) 297.22	12" HDPE (S) 297.22	N: 656,895.29 E: 1,439,767.03
I-105	18" NYLOPLAST DRAIN BASIN	GRATE 303.97	12" HDPE (E) 299.35 12" HDPE (NW) 299.35	12" HDPE (S) 299.35	N: 656,995.36 E: 1,439,804.72
I-106	18" NYLOPLAST DRAIN BASIN	GRATE 303.82		12" HDPE (SE) 301.78	N: 657,060.90 E: 1,439,702.47
I-107	24" NYLOPLAST DRAIN BASIN	GRATE 294.00	4" PERF. PVC (E) 290.83	12" HDPE (W) 290.83	N: 656,859.72 E: 1,439,775.65
I-108	24" NYLOPLAST DRAIN BASIN	GRATE 294.00	4" PERF. PVC (NW) 290.83	12" HDPE (E) 290.83	N: 656,862.19 E: 1,439,756.16
I-109	18" NYLOPLAST DRAIN BASIN	GRATE 303.01		12" HDPE (W) 300.96	N: 657,013.72 E: 1,439,963.90
E-201	HPDE END SECTION	- 295.19	12" HDPE (NE) 294.00		N: 656,900.78 E: 1,439,682.21
I-202	TYPE S INLET SINGLE GRATE BACO D-2.16A	GRATE 303.44	12" HDPE (SE) 299.92	12" HDPE (SW) 294.74	N: 656,932.39 E: 1,439,701.34
I-203	TYPE S INLET SINGLE GRATE BACO D-2.16A	GRATE 303.44		12" HDPE (NW) 300.44	N: 656,909.11 E: 1,439,747.98
E-301	HPDE END SECTION	- 295.11	12" HDPE (N) 294.00		N: 656,850.56 E: 1,439,867.03
I-302	TYPE S INLET SINGLE GRATE BACO D-2.16A	GRATE 303.44	12" HDPE (W) 299.87	12" HDPE (S) 294.74	N: 656,887.41 E: 1,439,866.23
I-303	TYPE S INLET SINGLE GRATE BACO D-2.16A	GRATE 303.44		12" HDPE (E) 300.44	N: 656,891.84 E: 1,439,809.55
E-401	HPDE END SECTION	- 286.15	12" HDPE (E) 284.96		N: 656,695.40 E: 1,439,756.24
I-402	24" NYLOPLAST DRAIN BASIN	GRATE 290.00	4" PERF. PVC (SE) 285.83	12" HDPE (W) 285.73	N: 656,693.70 E: 1,439,832.22
E-501	HPDE END SECTION	- 277.09	12" HDPE (SE) 275.90		N: 656,536.04 E: 1,439,574.07
I-502	24" NYLOPLAST DRAIN BASIN	GRATE 282.00	4" PERF. PVC (E) 277.83	12" HDPE (NW) 277.73	N: 656,450.93 E: 1,439,735.53
E-601	HPDE END SECTION	- 296.08	15" HDPE (W) 294.62		N: 657,279.65 E: 1,440,099.21
I-603	24" NYLOPLAST DRAIN BASIN	GRATE 303.10	12" HDPE (SW) 299.11	15" HDPE (E) 298.86	N: 657,383.06 E: 1,439,764.01
I-604	24" NYLOPLAST DRAIN BASIN	GRATE 303.07		12" HDPE (NE) 301.10	N: 657,217.76 E: 1,439,653.06
		1		1	1

OWNER/DEVELOPER: BALTIMORE COUNTY PROPERTY MANAGEMENT 12200 LONG GREEN PIKE GLEN ARM, MARYLAND 21057 CONTACT: MATTHEW LEEBEL EMAIL: MLEEBEL@BALTIMORECOUNTYMD.GOV PHONE: 410-887-3834		DESIGN PROFESSIONAL: SITE RESOURCES, INC. 4 NORTH PARK DRIVE, SUITE 100 COCKEYSVILLE, MD 21030 CONTACT: PETER SOPRANO EMAIL: PSOPRANO@SITERESOURCESINC.COM PHONE: 410-689-0438			PROJECT INFORMATION: CLOVERLAND PARK CRICKET FIELD 12340 DULANEY VALLEY ROAD PHOENIX, MD 21131 ELECTION DISTRICT: 10C3 COUNCILMANIC DISTRICT:3					
SEAL	L CERTIFICATION		AS-BUILT / RI	EVISION	BY	DATE	P.W.A. NO.	KEY SHEET	POSITION SH	
MARSOF MARLING	I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF								USE	65NE12 65NE13
IN AD SA AND								R.O.W NO.		63NE12 63NE13
	LICENSE NO. <u>42977</u> ,	EXPIRATION I	DATE <u>06/07/2025</u> .	CONTRACT COMPLETION BOX						64NE14
	ENGINEER: PETER C. S	OPRANO	DGN BY:	BUREAU OF ENGINEERING AND CONSTRUCTION	TRAFFIC	HIG	HWAYS	STRUCTURES	STORM DRAINS	SEWER
03/19/2025	AS-BIILT PER RECORD PE	איז	DWN BY:	REVIEWED BY:						
DATE 03/19/2025	BY:	****	CHKD BY:	DATE REVIEWED:						



T	DRAWINC	G SCALE	PROPERTY MANAGEMENT					
3	PLAN SCALE:	AS SHOWN	APPROVED BY:	В	BALTIMORE COUN	ITY OFFICE OF	' BUDGET	AND FIN
3	PROFILE SCALE:		PROPERTY MANAGER DATE:			CLOVERL	AND PAI	RK CRIC
	WATER	FIELD ENGINEER				STORM	[DRAI]	N PRO
						CONS	STRUCTIC	N DOCU
				SUBDIVISION: PHOENIX	1234	0 DULANEY	VALLEY	ROAD, H